












GARDENS FOR SMALL COUNTRY HOUSES

HUDSON & KEARNS LIMITED, PRINTERS, . . LONDON, S.E.





GARDENS FOR SMALL COUNTRY HOUSES

BY

GERTRUDE JEKYLL & LAWRENCE WEAVER

THIRD EDITION.



LONDON:

PUBLISHED AT THE OFFICES OF COUNTRY LIFE 20, TAVISTOCK STREET, COVENT GARDEN, AND BY GEORGE NEWNES, LTD., 8-11, SOUTHAMPTON STREET STRAND, W.C. NEW YORK: CHARLES SCRIBNER'S SONS

MCMXIV.

Main Lib. Agric. Dept.



TO VINIL ALMENERALIA

HOURDON

First Edition, October, 1912.

Second Edition, Revised and Enlarged, January, 1913.

Third Edition, Revised, May, 1914.

PREFACE

TO THE

THIRD EDITION.


WITHIN eighteen months of its first issue, the need has arisen to print a third edition of "Gardens for Small Country Houses." This seems proof enough that the volume, concerned chiefly as it is with problems of garden design, has filled a place, hitherto empty, on the bookshelves of the garden-loving public.

The opportunity afforded by the second edition was taken to expand the introductory chapter by including in it some further examples of gardens, notable either for the apt use which has been made of a hillside site, as at Markyate Cell and Owlpen Manor, or for the possibilities of a walled enclosure, as at Edzell, or of topiary work in a limited space, as at Bridge End, Saffron Walden. The measured drawings of these gardens which are now reproduced were not completed in time for the first edition, but their inclusion (especially in the case of the hillside examples) has added much to the practical value of the book.

For this edition fewer alterations have been made, but some further notes on plants for rock gardens have been added to Chapter XXI.

G. J.

L. W.



CONTENTS

Introduction.	CHAPTER VIII.—ON HILLSIDE GARDENS.
Relation of garden to house. Importance of	Lady Mary Wortley Montagu on terraces.
preserving or creating character. Hillside	Stairways. Terraced gardens. Inexpensive
Gardens. Owlpen Manor and Markyate	materials. Various examples . 74
Cell. Misuse of conifers. Beauty of native	
evergreens. Various sites. Yew and other	CHAPTER IX.—Steps and Stairways.
hedges. Topiary work in small gardens.	
Walls. Treillage. Quiet entrances.	Approach steps from road. Stairways in
Planting at house-foot XVII	children's dramas. Stepped treatment for
CHAPTER I.—MILLMEAD, BRAMLEY, SURREY.	gentle slopes. Straight and curved stairs. Terrace steps. Unformal stairs . 85
Site of ancient buildings. Shapeless ground.	2011 acc stops. Onformat states . 03
Terraced in successive levels. Steps and dry-	
walling. Summer-houses I	CHAPTER X.—BALUSTRADES AND WALLS.
C II To Conserve in Forget	The design of balusters. The imitation of
CHAPTER II.—Two GARDENS IN FOREST CLEARINGS.	historical examples. Walls and parapets
Woodgate, Four Oaks. Virgin woodland.	of open brickwork. Walls surmounted by
Emerson and Reginald Blomfield on design.	beams. A coronal garden. Serpentine
High Coxlease, Lyndhurst. Rock and water	walls. Building in concrete . 100
10	
CHAPTER III.—A GARDEN IN BERKSHIRE.	CHAPTER XI.—CLIMBING AND OTHER PLANTS
Roses grown as "Fountains." Brick dry-	on Walls and Houses.
walling. Stone-edged water garden. Refined	Misuse of ivy. Of ampelopsis. Of
detail and ornaments 17	wistaria. Various climbers. Shrubs trained
	to walls III
CHAPTER IV.—WESTBROOK, GODALMING.	
Situation. Special compartments. Careful	CHAPTER XII.—RETAINING WALLS AND
planting scheme. Winter garden. Covered	THEIR PLANTING.
seats. Flower border facing north . 27	Hillside sites. Turf banks. Dry walling.
CHAPTER V.—A GARDEN IN WEST SURREY.	Grouping in planted dry walls in sun and
Poor soil. No definite plan. Paved court	shade. Construction. Importance of ram-
with tank and steps. Colour in flower	ming. Steps 119
borders. Woodland paths. Thunder-	
house	CHAPTER XIII.—YEW AND OTHER HEDGES.
CHAPTER VI.—HIGHMOUNT, GUILDFORD.	Yew hedges in ancient gardens. In modern
Site and views. Excavation of chalk. Rose	use. Other trees for hedges. Box. Holly.
garden. Planted Walls. Garden-houses.	Privet. Laurel. Beech. Hornbeam.
Colour schemes. Framing the views 46	Thorough planting. Topiary work . 129
CHAPTER VII.—THE TREATMENT OF SMALL	
SITES.	CHAPTER XIV.—WATER IN THE FORMAL
Some gardens by Mr. Inigo Triggs. The	GARDEN.
value of historical examples. Paved	"The soul of gardens." Reflections. Pools
parterres. The use of treillage. A town	and their water-levels. Varied shapes.
garden by Mr. Lutyens. A seaside garden	Lily ponds and their depth. Separate pool
by Mr. Mallows. Planting scheme by Mr.	gardens. Water parterres. Fountains and
H. Avray Tipping. Various typical	their sculpture. Leadwork. Well-heads.
examples 55	Pumps

CHAPTER XV.—METHODS OF PAVING.

Rectangular jointing. Random jointing. Local methods. Pitched paving. Paving of shingle. Of brick and tile . 171

CHAPTER XVI.—THE PERGOLA.

Italian pergolas. English, of oak and of larch poles. With stone, brick and tile piers. Proportions. Garlands on chains. Suitable plants. Covered alleys. Treillage. 179

CHAPTER XVII.—GATES AND GATEWAYS.

Entrance stairways. Gates to forecourts. Carriage gates. Notes on eighteenth century smiths. Gateways and vistas. In walled gardens. Wooden gates . . . 194

CHAPTER XVIII.—GARDEN-HOUSES.

The place of summer-houses in general scheme. Building in vernacular manners. Thatched roofs. Cob. Use of old materials. In walled gardens. Shelters and tool-houses

CHAPTER XIX.—STATUES AND VASES.

CHAPTER XX.—SUNDIALS AND SEATS.

CHAPTER XXI.—ROCK GARDENS (contributed by Raymond E. Negus).

Modern rock gardening. Principles of design. Stratification. Formation of the rock garden. Kinds of rock. Likes and dislikes of alpines. Planting. Shrubs. Situation of the rock garden. Uses of rockwork. Pools. Bog gardens. Paths. Steps. Moraines. 240



OF ILLUSTRATIONS. LIST

COLOURED FRONTISPIECE: JUNE BORDERS OF LUPIN AND IRIS IN THE GARDEN AT MUNSTEAD WOOD.

Lily Pool and Colonnaded Screen of Treillage at Ravensbury Manor. xxxiv. A Broad Treillage Arch. Treillage. XXXV. Drawing Showing Close Connection of xxxvi. A Treillage Colonnade. Trellis at Orchards. House and Garden. xxxvii. Plan of a Garden by C. E. Mallows. Plan of Rock Garden Near but Screened xxxviii. from House. THE GARDEN OF OWLPEN MANOR: xxxix. Effect of Simple Flagged Path Across Hillside Garden. View from Southiv. Treatment for the Forecourt of a Small xl. Plan. v. Cottage. vi. Sections. Another Forecourt Treatment. xli. View from North-west. vii. Suggested Plan to Provide Turning xlii. Bird's-eye View. viii. Space for Motor-car. THE GARDEN OF MARKYATE CELL: MILLMEAD: The Pergola. The First Summer-house. ix. I. View Across Forecourt. Planting Plan. X. 2. Chief Stairway Looking Eastwards. xi. Planting of Retaining Wall and Border. 3. Access to the Rose Garden. General Plan. xii. 4. Plan. Planting Plan. xiii. 5. Section. 6. xiv. Border by Lower Steps. 7· 8. XV. The House from Bottom of Garden. Looking Across Rose Garden to xvi. Yew Hedge. Steps and Sundial. 9. Curved Stair at Corner of Rose xvii. IO. The Dipping Well. Garden. WOODGATE: xviii. Plan of Mr. Horace Hutchinson's Garden. Steps and Garden-house. TT. Yews at Shepherd's Gate. xix. Garden Plan. 12. Walled Garden at The Murrel, Aberdour. XX. 13. Pool in Water Garden. Plan of a Garden by E. White. xxi. A Lily Pond. Plan of Garden of Hardy Flowers on 14. xxii. One and a-half Acre. HIGH COXLEASE: Entrance Front. 15. BRIDGE END GARDEN, SAFFRON WALDEN: The South Front. 16. Lead Fountain. In the Rock and Water Garden. xxiii. 17. View from Platform at East End. Lilies and Gables. XXIV. 18. Plan and Cross Section. XXV. A GARDEN IN BERKSHIRE: Topiary Work. xxvi. The Garland Rose. 19. GARDEN AT DORMY HOUSE, WALTON General Plan. 20. HEATH: The Tank Garden. 21. Planting Plan. xxvii. Plan. 22. Planting Plan of Tank Garden. Approach from Golf Club. 23. xxviii. West End of Flower Border. Pergola. 24. xxix. The Garland Rose, Hanging Over a A Planted Pavement. 25. XXX. Dry Wall. Walled Garden at Edzell Castle. xxxi. Steps and Dry Walling. An Idea for Wall Gardening. 26. XXXII. Planted Dry Wall. Flower Border Against Wall. 27. xxxiii.

2841	iiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiii	0110
28.	Rambling Rose in Old Apple Tree.	72. Paved Forecourt at Seal Hollow, Sevenoaks
		D 1 C 1 - + Combolanda Dulborough
29.	Planting Plan.	The Diette Deterched
30.	Flower Border Near Back Gate.	a to t to telem Dlanting
31.	Planting Plan.	75. Sunk Garden at Cray before Planting.
	Westbrook, Godalming:	PLEWLAND, HASLEMERE:
		76. Plan of Garden.
32.	The Pleached Lime Walk, from the	XX: (County County
	Study Window.	
33.	General Plan of Garden.	C1 / 1
34.	A Roofed Seat.	79. Sketch ,, ,, ,,
35.	The Loggia.	100, CHEYNE WALK, CHELSEA:
36.	The Circular Sunk Garden: Planting	
	Plan.	- 1 1 0
37.	The Sunk Garden from the South.	my O
38.	The Sunk Garden from the West.	82. The Screen
39.	Planting Plan of the Winter Garden.	83. A Sheltered Seaside Garden on the Eas
40.	The Winter Garden.	Coast: Drawing by C. E. Mallows.
41.	A Sheltered Seat.	84. A Sheltered Seaside Garden: Plan.
4	TA DIRECTOR DOWN	85. Pool and Paving.
	A GARDEN IN WEST SURREY:	86. A Little Garden at Walberswick: Plan.
42.	The Tank and Steps.	87. ,, Masonry Seat.
43.	The Paved Court and Steps.	88. ,, Stepped Path.
	General Plan.	Comment Howard
44.	The Paved Court.	GOODRICH HOUSE:
45.	The East End of the Main Flower	89. Plan of Garden.
46.		90. Fountain.
	Border.	gr. View.
47.	Yuccas in the Flower Border.	92. View.
48.	A Special Border of Grey, White,	93. Plan of a Garden at Dorchester.
	Pink and Purple.	94. A Scheme for Treatment of a Narrow Plot
49.	Ditto: Planting Plan.	Perspective Sketch.
50.	The Green Wood-walk.	95. Ditto: Plan.
51.	One of the Ways from Wood to Lawn.	95.
52.	Planting Plan of a Group at the Wood	HURTWOOD, SURREY:
	Edge for Winter and Early Spring.	96. Treatment of Sloping Ground Withou
53.	Autumn-blooming Shrubs.	Stairway.
54.	The Thunder-house.	97. A Steep Ascent.
		98. Plan of Gardens, near House.
	HIGHMOUNT, GUILDFORD:	99. Design by C. E. Mallows for Stairway or
55.	Circular Tank and Steps at West End	Gentle Slope.
	of Rose Garden.	donte bioper
56.	General Plan.	LITTLEHOLME, GUILDFORD:
57.	Steps and Pavement at the East End	100. Plan and Section Showing Treatmen
37	of Rose Garden.	of Sloping Site.
58.	Planting Plan of Top of Circular Dry	101. View from Loggia, Across First and
Jo.	Wall.	Second Terraces.
59.	From the Middle of the Rose Garden.	102. Terraces and Stairs from South-west.
60.	Sketch of Wall Planting.	103. Showing Outline of Upper Terrace.
61.	Angle of Dry Wall.	104. The Terrace Stairs.
62.	Campanula isophylla alba, in the Dry	104. The Terrace Starts.
02.	Wall.	HURTWOOD EDGE:
63.	Planting Plan of Borders of West Walk.	105. Perspective View of Scheme for Garden.
_	The Garden-houses.	106. Terrace from Below.
64.		107. The Terrace.
65.	The West End of the Pergola.	108. Plan of Garden Scheme.
66.	LITTLE BOARHUNT, LIPHOOK:	C
67.	The Sunk Garden.	110. A Hillside Garden at Petersfield.
68.	Steps, Gate and Wall.	111. Widening Stairway at Ardkinglas.
69.	A Simple Brick-built Dovecote.	
70.	Plan of Garden.	113. Curved Entrance Stairway at Owlpen Manor
71.	Rose Garden at Island, Steep.	114. An Unrailed Stair.

- An Angled Stairway with Low Coping. 115.
- Terrace Stairway Divided by Small Pool. 116. Terrace Staircase of Flags and Flint. 117.
- At Home Place, Norfolk. 118.
- Alteration of Round and Square Steps. IIQ.
- Stepped Approach to Pergola. Detached Porch and Stair. 120.
- 121.
- Round Stair on Terrace. 122.
- Steep Flight of Steps at Mathern. 123.
- 124. Roughly-built Stair from Terrace to Lawn.
- 125. Terrace Steps by E. L. Lutyens.
- Broad Stairway from Terrace to Lawn. 126.
- 127. Double Stairway with Pool: Perspective Sketch.
- T28. Plan.
- 129. Simple Stairway for a Woodland Walk.
- A Jacobean Balustrade. 130.
- Balustrade at Newton Ferrers, Cornwall. 131.
- Terrace Balustrade at Rotherfield. 132.
- Details of Terrace Walls. 133.
- Wall in Moulded Brick. 134.
- Open Parapet of Curved Tiles. 135.
- Wall of Hollow Hexagonal Tiles. 136.
- Wall with Openwork Panels. 137.
- Stone Wall with Timbered Piers. 138.
- The Same in Brick with Flower Boxes. 139.
- The Coronal: Round Walled Garden at 140. Athelhampton.
- 141. Serpentine Wall at Heveningham Hall.
- 142. Flower-bed Against Serpentine Wall: Plan.
- Alternative Plan. 143.
- Wall with Square Breaks. 144.
- Concrete Walls at Lambay. 145.
- 146. Wall Masking Kitchen Quarters.
- 146A. Wall at Wroxall Abbey.
- Overgrowth of Ivy on Sculptured Gateway. 147.
- 148. Gate-pier and Gardenhouse.
- Gate-pier and Wall. 149.
- Stone Gateway Moderately Clothed. 150.
- 151. Wistaria Misplaced.
- Rambling Roses, Vine and Ivy on Rough 152. Buildings.
- Clematis Montana. 153.
- Ampelopsis Veitchii Restricted in Growth. 154.
- Thin Slate Stones Laid Level. 155.
- 156. Brick Dry-walling: Planted with Pansies, Snapdragons, London Pride and Other Saxifrages, with Tufted Pansies at Foot.
- A Ten-foot Wall Planted with Gypsophila, 157. Valerian, Santolina, Rock Pinks and Cerastium, Lupines and Rosemary at Top.
- Brick Dry-walling Planted with Rambling 158. Roses Above and Tea Roses Below.
- Colour Scheme in Dry Wall of Purplish-grey 159. Brick: Cerastium, White and Lilac Tufted
- Pansy at Foot; China Roses Above. Pale Pink Rose, Valerian, Cerastium and 160. Rock Pink in a Rough Stone Wall.


- 161. White Foxglove in Dry-walling of Large
- 162. Brick Wall with Spaces Left for Plants.
- Steps with Front Edges Only of Stone 163. (Plan).
- Section of Dry-walling. 164.
- 165. Steps with Front Edges Only of Stone (Section).
- 166. Section of Dry Wall Showing Planting of Top and Face.
- 167. Elevation of Planted Wall, Showing Grouping of Plants.
- 168. Lawn Enclosed by Ancient Trimmed Yews.
- 169. Cleeve Prior: The Twelve Apostles.
- 170. An Ancient Bowling Green.
- 171. A Quiet Bowling Green.
- Yew Hedge as a Background to Flowers. 172.
- Yew Hedges in a Design by C. E. Mallows. 173.
- Yew-hedged Garden by H. Inigo Triggs: 174. Perspective.
- Ditto: Plan. 175.

184.

- Yews at Bulwick. 176.
- Yew Hedge Screening Offices from Garden. 177.
- 178. Hedge of Portugal Laurel Backing a Pool Garden.
- 179. Hedge Cut into Little Gables.
- Pollarded Limes Used to Heighten a Wall. 180. 181. Topiary Work at Mathern: Ten Years'
- Growth.
- 182. A Garden Avenue of Lombardy Poplars.
- 183. Hurtwood: Fan-shaped Lily Pool.
 - Relation of Steps and Pool.
- 185. Fountain with Basin Oblong Lily Pools.
- 186. At Great Baddow: Reflections.
- 187. Hurtwood: Looking Down on Fountain.
- 188. Parapeted Pool at Blythburgh.
- 189. Pool in Paved Court.
- at Morton House, 190. Hatfield.
- Shaped Pool at Athelhampton. IQI.
- at Wootton Lodge, Stafford-192.
- Small Pool and Niche at Athelhampton. 193.
- Pool in a Petersfield Garden. 194.
- " at Island, Steep. 195.
- 196. Sketch for Pools, Grouped Round Sundial.
- Pool Shaped for Tubs. 197.
- 198. a Simple Shape.
- with Raised Inlet. 199. ,,
- with Jet and Cascade. 200.
- Plan of Shaped Pool. 201. 202.
- Pool and Fountain Design by H. Inigo 203. Triggs.
- Plan and Section of Brick Fountain. 204.
- Lily Pond at Millfield, Brentwood: Sections. 205.
- Photograph. 206.
- Small Pools Interspersed in Paving. 207.

XIV	. ILLUSTRATI	ON5-	commuea.
208.	Marsh Court: Sunk Pool Garden.	257.	Pergola of Larch of too Slight a Construc-
209.	" Pool, Steps and Balustrade.	0,	tion.
210.	Pool at Papillon Hall.	258.	" with Well-shaped Braces
211.	Water Parterre: Plan for.	259.	
212.	" Sketch of.	260.	A Well-built Pergola Adjoining Racquet
213.	Walled Pool with Angle Fountains.	July 170	Court at St. Clere.
214.	Extended Pool at Chelwood Vetchery.	261.	Pergola with Piers of Brick and Stone.
215.	Tile-built Fountain by E. L. Lutyens.	262.	" with Piers, some Round, Some
216.	Lion Mask for Fountain.	1000	Square.
217.	Section of Basin with Lead Tortoises on	263.	,, with Piers of Tiles, Well-jointed.
	Rim.	264.	,, with Alternate Round and Square
218.	Lead Tortoise by Lady Chance.		Piers.
219.	Lead Dolphin.	265.	A Meeting-place of Radiating Paths.
220.	Gargoyle for Garden Wall.	266.	A Pergola Surrounding a Fruit-room.
221.	Hippocampus in Lead by Lady Chance.	267.	Pergola at Sandhouse.
222.	Garden Fountain by Alfred Gilbert.	268.	" at Ewelme Down.
223.	Wall Fountain at Hampton Court.	269.	A Pergola Sheltering a Garden Door.
224.	Lead Tank and Fountain by George	270.	" of Cordon Fruit Trees.
	Bankart.	271.	Outer View of the Cordon Fruit Pergola.
225.	Lead Cistern by George Bankart.	272.	Stepped Pergola at Acremead: Plan and
226.	" " "	1	Section.
227.	Chalice Bird Bath.	273.	Ditto: View.
228.	Shallow Bird Bath of Lead.	274.	A Garden of Treillage.
229.	A Good Eighteenth Century Tank.	275.	A Green Tunnel of Laburnum.
230.	Kelsale Manor: A Little Wooden Bridge.	276.	Gate and Mounting Block at Cleeve Prior.
231.	" , A Stone Bridge.	277.	Entrance to Biddestone Manor.
232.	Bathing Pool at Stoneywell Cottage.	278.	Gateway to a Courtyard.
233.	Well-head of Istrian Stone.	279.	Entrance from Road to Small Garden.
234.	" Modern.	280.	Treatment of Wall and Gates.
235.	" Italian, with "Overthrow."	281.	Carriage Gates.
236.	A Wooden Pump Casing.	282.	A Grille in Screen Wall.
237.	Lead Pump-head.	283.	A Foot-gate.
238.	Well-head at Sutton Courtenay.	284.	Vista Between Two Gates in Walled Garden.
239.	Pump-house at Pitsford.	285.	Garden Gate Made by the Brothers Roberts.
240.	Paving of Ironstone and Bargate Stone for	286.	Gate at Wych Cross Place.
	a Summer-house.	287.	,, at Wotton House.
241.	Paving Simply Treated with Stones of	288.	" at Packwood House, Birmingham.
	Natural Shape.	289.	,, at Norton Conyers.
	Paving of Rough-edged Slabs.	290.	,, at Wittersham House.
243.	Pavement of Rectangular Flags of Port-	291.	At Great Maytham: Main Gate to Walled
	land Stone.		Garden.
244.	Stone Paving with "Random" Joints.	292.	In the Walled Garden at Great Maytham.
245.	A Circular and Concentric Brick Paving.	293.	Gate on Terrace at Chelwood Vetchery.
246.	Paving Jointed to Follow the Terrace	294.	Wooden Door with Postern.
	Plan.	295.	A Trellis Door.
247.	Plan Showing Suitable Planting for the Side-	296.	Garden-house Designed by H. Inigo Triggs.
0	joints of a Paved Path.	297.	,, at Athelhampton.
248.	Pavement of Rectangular Flags in a Rose	298.	,, at Hurtwood: Above Lily
	Garden by Gilbert Fraser and T. H.		Pool.
	Mawson.	299.	Gazebo at Corner of Terraced Forecourt.
249.	An Old Sussex Church Paving of Brick.	300.	Garden-house at the End of a Long Walk.
250.	Plan of a Pavement Rather Over-planted	301.	An Angle Summer-house near Liphook
2=-	in the Middle.	302.	—and Another of Unusual Plan.
251.	Brick and Tile Paving, Scale Plan.	303.	Garden-house at The Grove, Mill Hill.
252.	" "	304.	,, Thatched, in Norfolk.
253.	,, ,,	305.	,, Thatched, in Angle of Cob
254.	A Dowgolo of Polos in Vonice	2-6	Walls.
255.	A Pergola of Poles in Venice.	306.	at Little Boarhunt, Liphook.
256.	Piers of Rubble, Plastered, at Amalfi.	307.	,, Built of Old Materials.

308.	Garden-house of Two Storeys.	351.	An Isolated Seat.
309.	,, at Little Ridge.	352.	Seats and Table in Appropriate Setting.
310.	" in Corner of Walled Garden.	353.	Garden Seat Designed by E. L. Lutyens.
311.	,, at St. Clere.	354.	" by J. P. White.
312.	" at Wittersham House.	355.	,, ,,
313.	" at Staplefield Grange.	356.	Table and Chairs Designed by Maurice
314.	A Trellis Garden Shelter.		Webb.
315.	Thatched Garden Shelter.	357.	Garden Seat.
316	and 316A. Two Typical Scottish Garden	358.	
	Pavilions.	358A.	Small Stone Seat at Markyate Cell with Lead
317.	A Seemly Toolhouse.		Figures at Ends.
318.	Statue on Gate-pier.	359.	Outcrop of Stratified Rock at Corners.
319.	Boy Figure in Niche at End of Grass	360.	Rocks Properly Stratified and Skilfully Laid.
	Walk.	361.	Bold Stratified Rockwork and Mass-planting.
320	and 321. Statues on Gate-piers at Papillon	362.	Rocks Ill-placed Without Uniformity or
222	Hall.	262	Enough Space for Plants.
322.	Boy and Dolphin in Pool.	363.	Treatment of an Odd Corner with Rockwork. Alpine Primulas Growing in Vertical
323	A Piping Boy. Boys Modelled by Jan Van Nost.	364.	Fissure.
324.	Quarrelling Cupids at Melbourne, Derby-	365.	in Horizontal
325.	shire.	303.	Fissure.
326.		366.	A Rough Retaining Wall.
327.	A Terminal Pan	367.	Rock Formations.
328.	Cupid and Swan Rising from Pool.	368.	Simplicity: The Keynote of Success in
329.	Fountain Figure by Puech at Wych Cross		Planting.
3-7	Place.	369.	Planting in Bold Masses.
330.	Flower-pot on Millstone and Statue of	370.	Large Clumps of Plants Giving an Appear-
227	Mercury in Background.	277	ance of Solidity. Bold Treatment of Rock and Plants.
331.	Statues Guarding Stairway. Vase at Hampton Court.	371.	A Judicious Use of Compact Shrubs.
332.	,, with Tinned Ornament by George	372. 373.	Retaining or Boundary Wall of Rough,
333.	Bankart.	3/3.	Unhewn Blocks.
334.		374.	Boundary Wall with Its Top Planted with
335.	"	3/1	Shrubs.
336.	Simple Sundial on Adequate Base.	375.	Boundary Walls.
337.	A Good Sundial Badly Placed.	376.	Bog and Water Garden.
338.	Sundial at Ditton Place, Balcombe.	377.	A Good Rock Pool.
339.	The "Blackamoor" Sundial.	378.	Stepping Stones.
340.	Modern Sundial at Marsh Court.	379.	Bold Stratified Rockwork and Small
341.	An Eighteenth Century Sundial.		Cascade.
342.	Sundial of Two Rough-dressed Stones.	380.	Pond for Small Garden.
343.	A Lead Sundial.	381.	A Rocky Path.
344.	An Old Garden Roller in a New Employ-	382.	A Rough Paved Path.
345.	ment. A Sundial: The Game of "Clocks."	383.	Cypripediums Thoroughly at Home on the Upper Margin of a Rock Garden.
346.	Statue Holding Dial in Rose Garden.	384.	Rock Steps Leading from Terrace Through
347.	Sundial Placed at Intersecting Paths.	3.1	Rock Wall to Rock Garden.
348.	" at Sedgwick Hall, Horsham.	385.	Constructions of Small Moraine.
349.	,, at Danby Hall, Yorkshire.	386.	Construction of Moraine on Slope.
350.	Stone Seat Designed by H. Peto.	387.	" Level Ground.
		15. T.P. 11.	



INTRODUCTION.

Relation of Garden to House—Importance of Preserving or Creating Character—Hillside Gardens—Owlpen Manor and Markyate Cell—Misuse of Conifers—Beauty of Native Evergreens—Various Sites—Yew and Other Hedges—Topiary Work in Small Gardens—Walls—Treillage—Quiet Entrances—Planting at House-foot.

T is upon the right relation of the garden to the house that its value and the enjoyment that is to be derived from it will largely depend. The connection must be intimate, and the access not only convenient but inviting. The house, in the greater number of cases, will stand upon a slight platform, not only because it is better that it should be raised above the ground-level, but also because the making



FIG. II.-CLOSE CONNECTION OF HOUSE AND GARDEN.

of such a platform is an obvious and convenient way of disposing of the earth or sand excavated for foundations and cellars. It is also desirable to have one wide, easy terrace on the sunny side. The plan and sketch (Figs. ii. and iii.) show a clever treatment by Mr. C. E. Mallows of a rectangular space of about an acre. The house is near the middle—an advantage on a small plot; it is well bounded laterally by a pergola,




FIG. III, -PLAN OF A GARDEN BY MR, C. E. MALLOWS.

walled on its outer side to the east, and by an evergreen hedge, thick and high, to the west. A small loggia is notched into the house itself—we are in the house and yet in the garden—a step down leads to a comfortable space of terrace; four more steps go directly into the garden. There is a fairly large lawn, a winding walk through a home spinney, and the rest is kitchen garden.

In the arrangement of any site the natural conditions of the place should first be studied. If they are emphatic, or in any way distinct, they should be carefully maintained and fostered. It is grievous to see, in a place that has some well-defined natural character, that character destroyed or stultified, for it is just that quality that is the most precious. Many a hillside site has been vulgarised by a conventionally commonplace treatment, when it presented infinite possibilities to both the formal and natural schools of design. Among the notable examples of little hillside gardens treated in formal fashion, none is more delightful than that of Owlpen Manor, Gloucestershire. Its plan and sections appear in Figs. v. and vi. bird's-eye view (Fig. viii.) has been prepared to supplement the photographs, which in the nature of things cannot give a fair idea of the wealth of incident crowded into an area of little more than half an acre. Fig. vii. shows indeed with what modesty the house nestles against the hillside and seeks to hide itself amidst regiments of yews. Great skill has been shown in their planting, for they emphasise the drops between the succeeding levels of the terrace, even though they partly veil them. The great square yew parlour is an unusual feature, the outcome of very many years of growth and of patient tending.



FIG. IV.—HILLSIDE GARDEN AT OWLPEN MANOR: VIEW FROM SOUTH-WEST FROM POINT C (SEE PLAN FIG. V.)

Its green walls vary in thickness from six to ten feet and are no less than twenty-five feet in height. The garden slopes downwards from north-east to southwest and faces the road on the south and east boundaries. It steps upwards from the road in five terraces, and the whole rise is about twenty-five feet. The front of the house is on the second terrace and the back on the third. The main entrance to




FIG. V.—PLAN OF GARDEN AT OWLPEN MANOR.

the garden is on the south, where there is a gateway (illustrated among Steps and Stairways on page 86) with a broad path leading to the house. On the north boundary there is a wall, which forms an embankment to the churchyard rising above it.

Not unlike Owlpen in some of its characteristics is the garden of Markyate Cell, near Dunstable. While Owlpen has known no change save that of maturing growth







FIG. VII.—OWLPEN: VIEW FROM NORTH-WEST FROM POINT B (SEE PLAN.)







FIG. IX -MARKYATE CELL: THE PERGOLA.



FIG. X.—HILLSIDE GARDEN AT MARKYATE CELL: VIEW ACROSS FORECOURT.



tor a great number of years, Markyate Cell is an example of what can be done to improve an old garden by judicious changes. The house, as its name reveals, contains part of an old monastic building which served as cell to the Abbey of St. Albans. To this considerable extensions in the Tudor manner were added in the second quarter of the nineteenth century. Although the period was an unfortunate one for domestic architecture, Markyate Cell is one of the shining exceptions. Its detail reveals its date, but the general grouping is very picturesque, and demanded an appropriate garden setting, which, until two years ago, it lacked. There were, however, some good materials, notably a fine yew hedge, and some terra-cotta balustrading of simple but




FIG. XII.- MARKYATE CELL : THE ACCESS TO THE ROSE GARDEN.

very effective design. The house is approached from the south, and stands on a hill which slopes downwards to the west and upwards to the east. The terrace on the west side of the house was already enclosed by the old terra-cotta balustrading, but the eastward slope had been planted without thought or conscious design, except for a great stepped yew hedge, which destroyed the vista that was possible, and stood in no definite relation to the house or anything else. When the owners of Markyate Cell, Mr. and Mrs. MacLeod, called in Mr. Dillistone of Messrs. R. Wallace and Co. to advise them in re-modelling the garden, one of the principal difficulties was the lack of communication between its different parts. The governing feature of the changes

made was the cutting of a way through the middle of the old stepped hedge, so that a vista might be secured from the forecourt up a new stairway through the hedge and across the rose garden that was then formed on the upper level, which was once a bowling green. This vista is picturesquely closed by a great purple beech, which stands out from the woodland at the east boundary. Thus was established a scheme




FIG. XIII. - MARKYATE CELL: PLAN OF GARDEN.

the chief feature of which is a marked axial line at right angles to the longer axis of the house. The effect of the vista was emphasised by a fine old stone vase on a roughly paved round base in the middle of the rose garden. A central feature of this kind is very valuable in increasing the impression of distance, and is attractive in its own right as an ornament of simple and pleasing character. The upper piers of the flight of steps which lead through the break in the stepped hedge are made the more




FIG. XIV.—MARKYATE CELL: SECTION OF GARDEN AT M-M (SEE PLAN).

interesting by a pair of leaden peacocks. Above the rose garden is a final terrace, from which delightful views are secured over the whole estate. The obvious method of giving access to it would have been by providing another flight of steps on the




FIG. XV.—SECTION AT N—N.

main axial line, but the obvious in garden design is often dreary. Considerable variety has been achieved by providing a series of steps, curved on plan, which wind from the south-east corner of the rose garden round to the upper terrace (shown in Figs. xvi. and xvii.).

These notes, taken in conjunction with the plan and photographs, explain how the garden was treated from west to east, but it was felt that a sense of breadth was also needed, and its provision has brought with it that valuable quality in garden



FIG. XVI.--MARKYATE CELL: LOOKING ACROSS ROSE GARDEN TO STEPPED YEW HEDGE.

designing, viz., surprise. Running east and west, and dividing the area already described from the kitchen garden, is an old wall. An opening was made in it at the end of the paved walk, which runs below the big stepped hedge and parallel with it. This opening was filled with a charming old iron gate, slenderly wrought, through which access is given to a long pergola with brick piers, leading to the far wall with an opening filled by a similar gate. This pergola is very well placed. A too frequent defect in the use of such a feature is its obtrusiveness, and the failure to relate it to other features of the garden design. Here, however, it forms a natural shelter for the path leading across the kitchen garden to the open parkland beyond. It must be explained that all these alterations have only just been made, and that the photographs now reproduced were taken in December. They, therefore, reveal only the bones of the design, and





FIG. XVII.—MARKYATE CELL: CURVED STAIR AT SOUTH-EAST CORNER OF ROSE GARDEN.

do not give any idea of the added richness which will come when the rose garden is blazing with colour and the borders are gay with lavender, pinks and hollyhocks.

Markyate Cell is altogether a very good example of what can be done in the treatment of a hillside site by a just use of architectural features and formal growths.

Owlpen and Markyate Cell are both jewels in rich and gracious settings, but, beautiful as they are, a like treatment would accord ill with a wild moorland hillside. Such a place has possibilities that are delightful, and all the easier to accommodate because the poor soil imposes certain conditions and restricts the choice of plants. There are natural gardens in these places, and especially natural groves, that cannot be bettered in the way of consistent and harmonious planting by any choice from a nursery catalogue. Such a region is a hillside clothed with



juniper, holly, birch, mountain ash, scrub oak and Scotch fir, in delightfully spontaneous grouping, with undergrowth of bracken and whortleberry, and heaths in the more open places, and other delights of honeysuckle, wild thyme, wood sage and dwarf scabious. It is grievous to see this natural and well-adjusted beauty ruthlessly destroyed, and common nursery stuff, such as laurels and a collection heterogeneous exotic conifers, put in its place, whereas it may be so well planted with the native trees that are absolutely sympathetic to its own character, with the addition of the hardier of the cistus, brooms and their kindred species, with rosemary, lavender, phlomis and many another good plant of Southern Europe. So it is with any other place that has a distinct natural character, whether of granite, limestone or slate-rock. All these have their own flora, indicating to the




FIG. XIX.—YEWS AT SHEPHERD'S GATE.




FIG. XX.-WALLED GARDEN AT THE MURREL, ABERDOUR, FIFE.

careful observer the classes of trees and plants that will best flourish and best adorn.

Happily, our newer gardens are no longer peppered over with specimen conifers. Much as we honour those heads of our great nursery firms and others, whose enterprise and practical encouragement of botanical explorers has so greatly increased the number of coniferous trees that we may now choose from, the earlier




FIG. XXI.—PLAN OF GARDEN AT THURSLEY DESIGNED BY MR. E. WHITE.

mistakes in planting have in many cases been disastrous to gardens. About fifty years ago, when they were being raised and distributed, and horticultural taste was at a low ebb, a kind of fashion arose for planting conifers. It mattered not that they took no place in garden design, and that those who planted had no idea what they would be like when full grown; the object was merely to have one each of as many kinds as possible. If the intention had been simply to make a collection from the botanical point of view there would be nothing to criticise; but they were




FIG. XXII.—A GARDEN OF HARDY FLOWERS ON AN ACRE AND A-HALF.

crowded into nearly every garden as exponents of the horticultural taste of the day. Now, when they are approaching maturity of growth, they have either been cut away wholesale, or their owners, of the later generation that has learnt better gardening, look ruefully at the large trees so unwisely planted. In fact, unless space is so great that experimental planting may be done on a large scale, or the foreign

trees are so well known in all stages of growth that they can be used with a sure hand. it is safer to trust to our native evergreens and the few European kinds that we have long known. In their way nothing is better than the native juniper, Scotch fir and yew for our sandy uplands; yew also for chalky soils, and spruce and silver fir for cool hollows. Our noble English yew is nearly always beneficial in the garden landscape. Whether as a trimmed hedge or as a free-growing tree, its splendid richness of deepgreen, and, indeed, its whole aspect, is of the utmost value. No tree is more satisfactory for emphasising important points. Fig. xix. shows two vigorous vews of upright habit in Mr. Horace Hutchinson's garden at Shepherd's Gate,





FIG. XXIII.—LEAD FOUNTAIN IN BRIDGE END GARDEN, SAFFRON WALDEN.



in the old forest region of Sussex. They stand just within the rose garden above and flanking a flight of steps that leads to lower ground. Standing in the rose garden, and looking between the yews to the half-distant view of wooded hill and down, so typical of the beautiful Ashdown Forest district, they form the frame of the picture, and the tender colouring of the distance is much more fully appreciated than it would be if they were not present. It is a good lesson, and suggestive of what might with great advantage be oftener done in gardens, namely, to frame a distant view in near greenery, either by an occasional arch or by a whole arcade. Roses are well used at Shepherd's Gate; they rejoice in the rich loam of the district, not only growing strongly but also flowering profusely. The whole country is richly wooded, and gives a feeling of protective shelter that is all the




FIG. XXV.—PLAN OF TOPIARY WORK IN BRIDGE END GARDEN.

more favourable to the well-being of the roses and of the many other good garden

plants that flourish in this pleasant place. (For plan see Fig. xviii.)

Very different as a site is that of The Murrel in Fife, the work of Mr. F. W. Deas, in a country of wide spaces and low, wind-swept hills (Fig. xx.). The house and all the outbuildings are closely grouped together, and one feels, with this accomplished architect, how much the whole needed the protection of the great stone wall, whose height, varying from twelve to eighteen feet, rises to one level as the ground falls. It is heavily buttressed, and, like the house, roofed with pantiles.

A site of about two acres at Thursley in Surrey has been cleverly treated by Mr. Edward White (Fig. xxi.). House and pleasure garden occupy about half




FIG. XXVI.—BRIDGE END GARDEN: TOPIARY WORK.




FIG. XXVII.-DORMY HOUSE: PLAN OF GARDEN.

the ground. The entrance path is square with the road, and the house door cuts across an angle formed by the meeting of the main block and the office wing. The house, standing diagonally to the road, allows of a longer extension of the flower-borders and the circular garden at the end than could otherwise have been put upon the site. Kitchen garden and orchard are conveniently placed, and the

remaining space becomes a useful paddock.

When the site is a bare field, or any place without individuality, the designer has a free hand, but will be wise in choosing something that is definite, so as to give that precious quality of character. It can only be created by simplicity of aim; by doing one thing at a time as well and distinctly as possible, and so avoiding complexity and confusion. For instance, if it is desired to treat the ground of a small site of about an acre and a-half as a garden of hardy flowers it may be conveniently laid out as in Fig. xxii. The lawn next the terrace has a shady retreat at each end,



FIG. XXVIII.—THE DORMY HOUSE, WALTON HEATH: APPROACH FROM GOLF CLUB.

and the wide turf path leading to the further cross path gives the impression of the whole space being given to pleasure garden, while there are still two good plots for kitchen garden, completely screened, on each side, and space for a play lawn between the house and the road. Tennis players prefer a ground whose longer axis runs north and south, but in this case the exigencies of the site oblige

the lawn to run east and west. Such a garden can be worked by a single-handed gardener, with possibly occasional help at pressing times. The green parlours on the front lawn are made with weeping elm, a tree not so much used as it deserves. A slight framework of something like split chestnut is wanted at first to guide the branches laterally to form the roof. As they grow, and then hang down the

sides, a complete shelter is formed in a few years.

Yew and holly hedges, such as are shown in this garden, are necessarily costly. The best size to plant, in the case of yew, is from two and a-half feet to three feet, at a cost of five pounds a hundred, putting them eighteen inches apart. Holly of the same height would cost a little more, but the price would be about the same for bushy plants a little under two feet high—a good size to begin with. To make a thick hedge, well furnished to the bottom, yew should have its yearly growth tipped at the ends by at least one-third of the length. Hollies will not want any trimming for the first few years. Such hedges, in favourable conditions, would take from

twelve to fourteen years to come to a full growth of six feet to seven feet. Box and holly would be rather slower than yew; privet, thorn and hornbeam faster, but as these would have to be cut down nearly to the ground after their first twelvemonth's growth, they would make very little show for the first two years. These are fairly average indications of growth, but on some sites the rate of increase would be considerably more.

It must be confessed that the gardener who is drawn towards topiary work needs to be equipped with ample patience and the prophetic eye. Without these qualities

he will not be prepared to devise a scheme which must take many years to mature. Given foresight and patience, however, there is nothing unreasonable in attempting, even on a very small site, a conscious scheme of shaped hedges on lines quite elaborate. Bridge End Garden at Saffron Walden is especially interesting in this connection, because its treatment, as shown by plan in Fig. xxv. and by photographs in Figs. xxiii., xxiv. and xxvi., covers an area of no more than one hundred and twenty-one feet by one hundred and seventy-three feet, which amounts to a little less than half an acre. This garden was laid out some seventy years ago by the late Mr. Francis Gibson, a cultivated amateur, who had the courage to break through the dreary traditions of landscape gardening which obsessed people in the eighteen-forties. At the east end of the garden an iron platform has been built. with a stair of access from which the visitor may survey the whole scheme, and that is the view-point taken by the



FIG. XXIX.—AT THE DORMY HOUSE: THE PERGOLA.

camera in Fig. xxiv. From this and from the plan it is clear how cleverly the yews have been spaced and the beds shaped. In the middle of the round grass plat is a lily pool, and kneeling on a column is a lead Triton, whose horn serves as fountain. The figure is almost an exact replica of one in the Rijks Museum at Amsterdam. The Bridge End Garden should stimulate anyone who has patience and half an acre unplanted to emulate its charms. It has the further merit of being visible at all times, for its present owner, the Right Hon. Lewis Fry, allows access to it throughout the year, a privilege which the folk of Saffron Walden very fully appreciate.

In the case of the very successful garden of the Dormy House at Walton Heath Golf Club the yews and hollies lately planted have made surprising growth. In this garden the object was to obtain the greatest effect that could be secured while involving the least labour. This has been effected by having several well-arranged flower-borders, and by the use of a quantity of rambling roses on posts and chains. One large double flower-border gives a charming look-out from the club sitting-rooms; another border is at the entrance to the Dormy House (Fig. xxviii.), whose walls already have a luxuriant growth of vines, the most beautiful



FIG. XXX.—THE DORMY HOUSE: A PLANTED PAVEMENT.

of wall ornaments. On its southern side there is a fine piece of stone paving, widening at the two ends into large square platforms (Fig. xxx.). The joints are planted with Alpines—perhaps just a little too freely. Many small plants take so kindly to this treatment that the temptation to plant them may easily result in too much invasion of the walking space. A warning as to this over-planting will be found at page 128. A plan showing a suitable amount of planting is given on page 175 (Fig. 247).

The excellent growth of the yew and holly hedges in the Dormy House garden will, in a few years, give such good protection and sense of enclosing comfort that the absence of built walls will not be felt: but where the cost is not prohibitive, walls of brick or stone are the best of garden boundaries. An ancient wall is in itself a thing of beauty. In the course of long years Nature paints the stone or brick with a number of tender tints, mellowing the whole surface colour; even the passing

of twenty years will often show the beginning of this precious *patina*. Then the walls enable us to enjoy many beautiful things, such as myrtle and pomegranate, that are not generally hardy in our climate.

Chapter XII. is devoted to Retaining Walls and Their Planting, but all the examples there shown illustrate what may be called informal planting. There is, however, at Edzell Castle in Forfar a walled enclosure which shows a formal treatment of wall planting full of suggestion (Figs. xxxi. and xxxii.). This pleasure garden was made at the beginning of the seventeenth century, and it is remarkable

that the idea thus admirably set on foot should not have been imitated or developed since. The pleasure garden is oblong, and has an area of rather more than half an acre. Three of the walls were divided by stone shafts into compartments. which are. alternately filled with two types of device which made possible charming effects in wall gardening. Of these, the more important consists in a series of twelve small recesses arranged checker-wise in three rows of four each. The garden wall was built by a Lindsay of Edzell. and the recesses represent the checkered fesse of his coat-of-arms. The Lindsay checkers blue and silver, and no doubt the recesses were filled with some blue flowering plant of dwarf habit and inconspicuous leaf. Parkinson's Paradisi in Sole, published in 1629, gives many flowers that Lord Edzell might have employed. Dwarf campanulas, bell-flowers, double blue daisies. globe-flowers or even cornflowers might have been used to give a compact mass of blue. Perhaps the best flower for the purpose to-day would be the lobelia; but it was not available in 1604. If he chose to use the silver of his coat, in the recesses of an adjoining




FIG. XXXI.—TREATMENT OF WALL AT EDZELL CASTLE.





FIG. XXXII.—A SEVENTEENTH CENTURY IDEA FOR WALL GARDENING.



bay, some silvery foliage would have served, such as stachys, woundwort, gnaphalium, catsfoot or cerastium. The idea is well worthy of adoption in modern walled gardens, where the recesses could be arranged to suggest some device appropriate to the owner of the garden, whether heraldic in character or marking some hobby or special interest.

Fig. xxxiii. reminds us of the advantage of a wall backing a flower-border, but care needs to be taken lest the roots of the hedge should appropriate to themselves all the virtue of the manure provided for the flowers. This can be done by cutting back the hedge roots, so that they do not trespass on the border, or by building a rough underground wall to separate the two territories. In the example illustrated in Fig. xxxiii. the border might, with advantage, have been wider; it was, no doubt, made narrow in order that the path should go straight to the doorway at the end. It is one of the many cases in garden arrange-

ment where the that is course easiest is chosen rather than one that is more thoughtful and less obvious. Where neither wall nor hedge is suitable, there is the device of treillage, which takes the least room in point of width of any kind of planted fence. This may be either of the carefully designed and constructed kind as at Ravensbury (Fig. xxxiv.), where it fitly accompanies a



FIG. XXXIV.—TREILLAGE AT RAVENSBURY MANOR.

house of eighteenth century character, or it may be of simple oak posts and laths, as at Orchards (Fig. xxxvii.). Here it is in the walled kitchen garden. Espalier fruit trees are trained against it, and it forms the back on each side of a double flower-border that runs right through the middle of the garden. The posts, standing five feet out of the ground, are set seven and a-half feet apart, and are connected by a top rail, two by one and a-quarter inches, mortised into the posts. The end posts are four inches square; the intermediate ones three inches. The laths, one and a-half inches wide by half an inch thick, are set square at a distance apart of eleven inches from centre to centre.

Not the least merit of treillage is that it gives opportunity for the inexpensive construction of all sorts of architectural fancies. The garden shown in Figs. i., xxxv. and xxxvi. is an admirable example of its possibilities in this direction. Fig. xxxv. shows a broad, elliptical treillage arch, which forms a most attractive entrance to the



garden and frames its distant view. Seen through this arch, on which creepers have made an almost impenetrable roof, appears a lily pool surrounded by a treillage colonnade which follows its outlines. Although this screen brings to the place a hint of the grand manner of French garden design, and with it a sense of size and dignity, the actual area of the garden which it adorns is little more than half an acre. This is mentioned in order that it may not be supposed that the quality of dignity to be secured by the use of treillage is appropriate only to large gardens.

Where a rock garden forms part of a scheme it is best placed quite away from the house; but in many a small garden the only suitable place may



FIG. XXXVI.—A TREILLAGE COLONNADE.

be not far from it. When this is the case it can be effectively secluded by

banks planted with shrubs, as shown by the plan in Fig. xxxviii.

The owner of a small place often has the desire of making a good show of flowers—as an amiable form of cheerful welcome—immediately within the entrance. It is a kind thought, but not the most effective way of arranging the garden. It may be taken as a safe rule that the entrance should be kept quiet and, above all, unostentatious. A certain modest reserve is the best preparation for some good gardening on the sunny side of the house, for in most cases the way in will be on the north or east. Labour and horticultural effort are often wasted on flower-borders or summer bedding all along a short carriage-way, which would be much better with a wide grass verge and shrubs alone.




FIG. XXXVII.—TRELLIS AT ORCHARDS.




FIG. XXXVIII.—ROCK GARDEN NEAR BUT SCREENED FROM HOUSE.

In cases where a carriage-way is not an absolute necessity, the substitution of a flagged pathway is a great gain to the restfulness and beauty of the garden. A beautiful treatment of this kind is shown by Fig. xl., the entrance to Mr. Leonard Borwick's charming home in Sussex, where a flagged path passes through the quiet, unbroken green of well-kept grass. But there are many places where a means of driving to the door is required. Here the difficulty arises, in the case of quite a small house, of the disproportion between the space required for turning a motor or a pair-horsed carriage and the size of the house-front. A simple square forecourt always looks well as in Fig. xxxix., a design by Mr. Leopold S. Cole. The same kind of treatment, but with the angles rounded, is shown at Fig. xli., by Mr. Alick



FIG. XXXIX.—TREATMENT FOR THE FORECOURT OF A SMALL COTTAGE.

Horsnell. But in both these examples the expanse of gravel is rather large, nearly double the area of the block-plan of the house itself. Where the coach-house or garage stands beyond the house, and more or less parallel with the line of the main ridge, this difficulty may be overcome by some such arrangement as that shown on the plan Fig. xlii., which leaves only the width of a road at the front door. It is done by making a third piece of road, branching symmetrically with that to the carriage-house, and stopping short, as to its full width, when length enough has been given, and ending either in a narrower garden path or some small special garden. The carriage or motor would go forward, as shown by the single dotted line, would then back for a short distance as shown by the double dotted line, and then again go forward.




FIG. XL, -BROAD EFFECT OF SIMPLE FLAGGED PATH ACROSS LAWN.

A frequent example of waste of effort is where a narrow border at the foot of a house is filled with small plants—annuals or other summer flowers. The border itself is often poorly fussing dodging in and out among bays and slight projections. It is much better to carry > the border straight across, and to fill the spaces next the house with something of solid and shrubby character, such as laurustinus, choisya and escallonia, with a planting, in the narrower spaces and towards the path, of smaller shrubs, such as lavender. rosemary, phlomis. dwarf rhododendrons, olearias and hardy fuchsias; then, if front spaces still need filling there is nothing better than the leaved megaseas and the stately acanthus in combination with the dark-leaved shrubs, and of southernwood and santolina with the grey.

The title of this volume, "Gardens for Small Country Houses," needs, perhaps,





FIG. XLI.—ANOTHER FORECOURT TREATMENT.



some explanation, because a few of the pictures reproduced belong obviously to large gardens. Although some of the gardens described in the earlier "monograph" chapters (I. to VI.) are of fairly large extent, they mark the increasing tendency to be generous in the provision of garden space round country houses which may fairly be called small. We have not attempted to deal with the little plots which belong to little cottages, as they give scarcely any scope for invention or conscious design. Several scores of photographs have been taken specially for the purposes of the book, but it has not been found possible to rely solely on existing small gardens, known to us, for pictures that would elucidate the points we wished to make. It is fair to claim, however, that no feature has been illustrated which would not be fitting in a small garden when reduced in scale, or which it would be wrong so to reduce. In order that the range of illustration should be as wide as possible, we have been glad to avail ourselves of several sketches for pools, walls and the like, which Mr. Inigo Triggs has kindly placed at our disposal. To Mr. J. Maxwell Scott and Mr. Charles Yates,

among others whose names are given in the text, are due our thanks for the care with which they have made drawings of gardens and their features. The pleasant but not inconsiderable labours of visiting dozens of attractive gardens have been more than repaid by the courtesy and kindness shown by their makers and owners. We may hope that they will have a second harvest in an increased care to secure a right quality in garden design. It is impossible to compress within the limits of such a book more than a fraction of what may be told by pen and picture. but the endeavour has been made to ignore nothing that is essential.

oth your state of the season and the season are season as

GERTRUDE JEKYLL. LAWRENCE WEAVER.


CHAPTER I.-MILLMEAD, BRAMLEY, SURREY.

Site of Ancient Buildings—Shapeless Ground—Terraced in Successive Levels—Steps and Dry-walling—Summer-houses.

Some of ground in a lane leading westward out of Bramley, were condemned and demolished at the end of the nineteenth century. The ground remained unused for some years, and the part next to the lane, overgrown with docks and nettles, had become a place where neighbouring cottagers found it convenient to throw their household debris. In 1904 an old former inhabitant went over it, and found that from halfway down it looked over the wooded grounds of the old home and the half-distant hilly woodland that had been the scene of childish primrose-picking rambles, while the foot of the plot adjoined the green mill meadow, in view of some fine, near trees and the rushing millstream, and was within the soothing sound of the working water-mill. It was soon resolved that the land should be bought, and a house built upon it that should not only be worthy of the pretty site but that should also be the best small house in the whole neighbourhood, both for architectural merit and for



FIG. I.—THE FIRST SUMMER-HOUSE. POINT OF VIEW "A" ON GENERAL PLAN (FIG. 4) AND PLANTING PLAN (FIG. 5).



convenience and comfort. The ground is a little more than half an acre, seventyseven feet wide and something over four hundred feet deep, on a rather steep slope facing south - south - east. Except for the first hundred feet, which was fairly level, with an awkward lav but it was diagonal tilt, evident that this could easily be rectified by terracing in a series of levels. The area was not enough to allow of any space for kitchen garden; the whole is therefore given to flowers and shrubs, with one or two small grass plots.

The house, designed by Mr. Lutvens, is reminiscent of some of the small houses of good type built in England under Dutch influence in the early years of the eighteenth It is approached century. from the road by a door in a wall leading into a forecourt. A paved path of Portland stone leads through turf to a wide, flagged platform of the and to the wrought doorway. The planting of the forecourt is kept rather quiet, with plenty of good green foliage. On the left the wall of the office wing is nearly clothed by a vine, and on the right a rather high wall is covered with the of clematis, wilder kinds montana and vitalba, with arbutus, laurustinus and spiræa lindleyana treated as wall plants, and the borders at the foot have acanthus, megasea, Lent hellebore, Solomon's Seal and hardy The flowers are of the modest type, such as columbines and campanulas, the whole intention being to be

green and quiet in anticipation of a riot of bright blossom in the main garden on the sunny side of the house. A narrow way, only five feet wide, leads between the house and the western wall to the southern garden. It has been made interesting by the use of some old turned wooden columns that originally formed part of the decorative structure of the wooden ships of the late eighteenth and early nineteenth centuries. Heavy oak beams connect them in pairs across the path, which is paved, partly with the local Bargate stone and partly with a "pitching" of the black ironstones found in the district. A vine planted at the end will in time roof the whole. The garden front of the house, facing south a little east, has a wistaria growing strongly, with good prospect of covering as much of the front as can be allowed,




FIG. 3.—PLANTING OF RETAINING WALL AND BORDER.—POINT OF VIEW "B" ON GENERAL PLAN (FIG. 4) AND PLANTING PLAN (FIG. 2).

while for the further furnishing of the narrow border at the house foot there are

escallonia, choisya, rosemary, lavender and iris stylosa.

The garden ground, being in the form of a long strip, the task of the designer was the judicious management of each succeeding level, so that each should have some individuality and distinctive interest, and yet that there should be a comfortable sense of general cohesion. From the wide path in front of the house the ground begins to fall—only a little at first; three steps down are enough. A dwarf dry wall of Bargate stone retains the upper path with its border next the house, and another at the top of the wall; the latter is planted as a rosemary hedge, sweet to the touch







FIG. 4.—MILLMEAD: GENERAL PLAN.






FIG. 6.—PLANTING PLAN AT VIEW POINTS "C" (SEE FIG. 7), "D" (SEE FIG. 9), AND "E" (SEE FIG. 8).

from the path above and the grass below. The lower space is roughly a square, laid as a little rose garden, with grass paths and a central sundial. Here also is the first summer-house, illustrated in Fig. 1, the arrow and letter A on the general plan (Fig. 4) showing the point of view. It centres the sundial and the grass paths between the rose-beds, and has a pretty view of the church and distant hills, cut as an oval upright picture through the shrubs and further hedge. Outside the grass plot a path runs round three sides, with further borders of shrubs and flowers. A plan is given of the planting of the one on the shady side that contains the summerhouse (Fig. 5).

To the next division there is a drop of some feet—a flight of steps leading down to another level, also roughly square, with a central path dividing two large clumps of flower and The chinks of shrub. the steps and the returns of the dry-walling at their sides are bright with aubrietia in May, and the walls to right and left are planted with stonecrops, snapdragons, catmint (Nepeta) and other pretty things. At the foot of the steps, squares with flat stone



FIG. 7.—BORDER BY LOWER STEPS. POINT OF VIEW "C" ON GENERAL PLAN (FIG. 4) AND PLANTING PLAN (FIG. 6).



FIG. 8.—THE HOUSE FROM BOTTOM OF GARDEN. POINT OF VIEW "E" ON GENERAL PLAN (FIG. 4) AND PLANTING PLAN (FIG. 6).

edgings hold a pair of hydrangeas. At the western angle a half-round dipping tank is notched into the dry-walling; it is fed by an underground pipe from the pump in the forecourt against the wall to the road, where there is a well that formerly supplied the old cottages. Another retaining wall and flight of steps again lead downwards to a longer piece, the lower part sloping downhill, but levelled right and left. The level of the upper portion was fixed by the presence of a very fine old pear tree. It was given its own little grass plot, and a seat and laurel hedge to surround it on all sides but that of the flower-beds, where the hedge is of lavender. On the western side of the upper part is a little building grouping with, and shaded by, an old plum tree. It was originally intended for a tool-shed,



FIG. 9.—STEPS AND SUNDIAL. POINT OF VIEW "D" ON GENERAL PLAN (FIG. 4) AND PLANTING PLAN (FIG. 6).

but the tenant converted it into a charming little summer sitting-room, and it is now the second summer-house. It is built of oak timber and brick, with a tiled roof, and has the appearance of a miniature old Surrey cottage. On each side of the middle path is the main flower border, forming a continuation of the borders on the level next above. The planting of the retaining wall and border above is shown in the picture (Fig. 3) and plan (Fig. 2), the point of view being from the arrow and letter B on the general plan (Fig. 4). A small path, parallel to the middle one, passes down from the second summer-house between flowering shrubs. At the end of the flower border is another descent of four steps, with a low retaining wall and cross path. The wall is

nearly filled with rock pinks; just at the top is an irregular row of dwarf lavender, the short-stemmed, dark-flowered kind that blooms in July—nearly a month sooner than the larger ordinary lavender—and at the back of this is a hedge of hardy fuchsia. Further flights of steps, on the same middle line, lead down to the lowest level, which is some five feet above that of the meadow. In the narrow border next the meadow are only low

shrubs, the better to see the pleasant prospect of mead and millstream, though there are one or two posts for roses, and a wild clematis that forms garlands from post to post.

At the southern corner, where there is an odd angle. the third summer-house was built, a wooden structure on a brick foundation, weatherboarded outside and also elmboarded within. A wide window with casements and lead lights looks out on to the meadow. The little place is of a queer shape, and yet seems roomy. It is thickly roofed with straw thatch. In winter it is curiously comfortable—always feeling dry and warm. Near it outside is the dipping well, which was built to take advantage of a natural spring, one of the many that feed the stream. It is built up with a Bargate wall about three feet out of the ground. On this a pair of the old ship pillars supports a beam with a pulley for the rope that dips and pulls up the bucket. A little tiled roof is built over, now nearly hidden by the growth of a climbing rose



FIG. 10.—THE DIPPING WELL. POINT OF VIEW "F" ON GENERAL PLAN (FIG. 4).

and the wild clematis. Next to the bank and holly hedge which form the eastern boundary, a sloping path on a lower level runs the whole way down, forming a convenient barrow-way with access to each level.

CHAPTER II.-TWO GARDENS IN FOREST CLEARINGS.

Woodgate, Four Oaks—Virgin Woodland—Emerson and Reginald Blomfield on Design
—High Coxlease, Lyndhurst—Rock and Water.

THE building of houses and making of gardens on woodland sites raises problems of treatment and design that need careful thought. Where shall the axe play and when shall the wielding of it be stayed? Once the trees are down the outlines of the scheme cannot be altered. As example is more valuable than precept, we may in this chapter examine two fine gardens that have been stolen from the wild—Woodgate, Four Oaks, and High Coxlease, Lyndhurst. To few people is it given to build their homes in such an ideal setting as six acres of virgin woodland, as it was to Mr. W. H. Bidlake at Four Oaks. Woodgate stands in a triangle between two roads and once formed part of the great park which the statesmanlike Bishop Vesey caused Henry VIII. to grant to the Warden and Society of Sutton Coldfield.



FIG. 11.—WOODGATE: STEPS AND GARDEN-HOUSE.

About eighty years ago Sir E. Hartopp exchanged some land near the park gates for that part of the Corporation's forest land which was known as Ladywood, and the latter is now being built over, but the amenities are well preserved. It thus came about that Mr. Bidlake found himself the owner of a site that had never known the hand of man, a happy circumstance which, joined

with his skill both in planting and design, has brought into existence a veritable little garden paradise. The woodland had the unusual charm that most of its growth was indigenous—oak and holly and silver birch. These are varied by mountain ash, firs and Spanish chestnut. Beneath the trees the ground is carpeted in the spring with hyacinths, which are followed by bracken. When Mr. Bidlake went to Woodgate the soil had never been

disturbed. It consisted of red sand and gravel with scarcely any admixture either of clay or lime, and over it, separated by a sharp line of demarcation, was a top layer of black vegetable leaf-mould six inches thick, the spoil of unnumbered autumns. In the mixture of this mould with the sand rhododendrons grow with extreme freedom owing to the absence of lime, as a noble bank of flowers at the north-east corner of the garden testifies. For many garden denizens this mixture proved too vigorously acid, WOOD and for about vears it two killed almost everything that was planted, but time and lime have made it amenable. Even now very deep planting is necessary, as the top soil dries off very rapidly in hot weather. Lilies of various kinds, especially Lilium auratum, speciosum, monadelphum and the Canadian varieties, do very well, while every sort of campanula flourishes exceedingly. Those charming bulbs that we owe to South Africa, ixias and sparaxis, with hardy calochorti from North America, stand the winter well by being covered with a little bracken, which preserves them sufficiently from The Californian poppywort, delicate alike in the texture of its flowers and its

FIG. 12.-WOODGATE: GARDEN PLAN.

JAPANESE

home here, no little clay was imported, but, that done, they grow well, and delphiniums, in common with most herbaceous things, add the charms of their serried spikes in blues from lavender to indigo. Though Mr. Bidlake is skilful more than common with his planting, the garden owes

Needless to say,

fragrance, adds its stately beauty and spreads freely underground, but Asclepias tuberosa (better called Butterfly Silkweed) point blank

refuses to grow despite the sandy soil which

before roses could be induced to make their

text-books preach for it.



FIG. 13.—POOL IN WATER GARDEN.

well as a polite apologia for the effect of accidental charm which can bear no close examination, but is misleading nonsense when considered. Whatever may be the




FIG. 14.-WOODGATE: A LILY POND.

no less to design, and the more so because it seems to have come aboutso naturally. In this connection one cannot agree with Emerson, whose pronouncements on matters æsthetic must always be approached with some suspicion. "Our arts," he says, "are happy hits. We are like the musician on the lake, whose melody is sweeter than he knows." This would serve

merits of impressionism in painting, post or otherwise, it is a snare in architecture and in the daughter art of garden design. The truth is to be sought rather in the cogent phrases of Mr. Reginald Blomfield, when he said "There is no such thing as impressionism in architecture. Our art does not allow us to leave our conception sketched out. The idea must be thought out to the uttermost. The incomplete phrase, in our case, is no

phrase at all, and as far as it goes, our expression must be at least equal to our thought." The feeling that Woodgate inspires in its garden setting is that the thought has been careful and sustained, and the expression adequate. If the plan be examined, and it is worth careful study, it is clear that the clearing for the house was made in just the right spot. It affords a drive from the western road just long enough to give a pleasurable sense of anticipation. while it gives a short access for tradesmen from the eastern road. South of the house enough woodland was cleared to give an adequate lawn, surrounded by a belt of oaks through which there is a vista towards the small formal garden, occupying the southern angle of the site. Here is placed a large lily pond with Japanese iris at its corners, surrounded by a yew hedge. A small lawn has also been made on the west side of the house to prevent the undue darkening by overshadowing trees of the drawing-room bay window. East of the house is another little garden on geometrical lines, and in general the terrace and steps on the south front do homage to that element of formality which is the essence of good gardening near a house. As we leave from the building that quality dies away and the design is determined by the position of the big oaks and other trees which it was so desirable to retain. Northwards the garden has been subtly incorporated with the woodland that shelters the house from the cold winds, and the four acres covered by trees are threaded by many winding walks which lead us through a carpet of hyacinth and fern at their several seasons. It may be suggested that it would have been better to have laid down these paths on straighter and more formal lines. The intention was to create the feeling of those woodland paths that take their random windings from the feet of children, who follow the line of least resistance and walk where Nature has been less prodigal of growth. From the house porch there is a long avenue, straight save for one break, which hides the far garden until it bursts into view. After the shadow of the wood the sunlit lawn comes with that quality of surprise which is so valuable in garden design. avenue leads past a well-equipped kitchen garden on the right to the spacious tennis lawns and bowling green fringed at the north corner by a bank of purple heather, and free of the shade of the trees. From this upper garden a long flight of brick steps takes us down to another, six feet below. A retaining wall with pillars flanking the stairway divides the two, and at its north end is a tall two-storeyed summer-house which serves both levels, as a retiring-place for tea above, and as a house for garden

In this lower garden is a maze of formal walks separated by clipped beech hedges, crossed by rose arches luxuriantly clad and bordered by beds of herbaceous flowers. South of the rosery are a rock garden and a little lily pond, where the great white blooms of gladstoniana stand free above the water boldly until the autumn frosts, and red masses of gloriosa float fragrantly. Near by is a little place consecrated to spring bulbs. A good feature of the garden is the judicious use of seats, which are placed at all points of vantage, such as the upper lawn, the rose and rock gardens, the end of the herbaceous walk, etc.

The grounds at High Coxlease, Lyndhurst, are laid out with less wealth of detail, but are none the less a highly interesting example of a garden stolen from the wild. It would be difficult to find a more enticing site for a house than this little clearing in the heart of the New Forest. One used as a child to picture just such a setting for the cottage of Jacob Armitage, the pious old verderer in "The Children of the New Forest." Though High Coxlease is so near the town of Lyndhurst, it has the atmosphere of remoteness. It would not be surprising to meet there young Edward Beverly, the excellent prig of Marryat's story, answering that question which always



FIG. 15.—HIGH COXLEASE: ENTRANCE FRONT.



FIG. 16.—THE SOUTH SIDE.

enchanted at least one eager boy, "Can you tell the slot of a brocket from a stag?" Obviously it is the place for brockets. If, however, we must stand upon the letter of the law, High Coxlease, though in the world of the New Forest, is not of it. It is the freehold of the Crown, and leased to the owner of the house which the illustrations show embowered in its trees, but it has nothing to do with the true forest land. The planting of High Coxlease is also modern, as the forest goes, for it was done with the rest of the property somewhere about 1830. The plantation was made to some purpose, for it has a finely mature aspect, and no more clearing was allowed than

seemed absolutely needful for house and garden. The picture of the entrance front shows the drive fringed with bracken and the roof framed in foliage, and, indeed, it is impossible to make anything like a general survey of the house save through a foreground broken by trees. This setting of the wild has been respected in a wise spirit. As the ground slopes southward the lawn is bounded by a retaining wall, beyond which a delightful rock and water garden has been made. The water itself makes a home for many of the beautiful hybrid waterlilies evolved by the genius of M. Latour Marliac. introduction of these dainty flowers, embracing as they do a wide range of colours, has completely revolutionised the art of water-gardening in this country, and has given it fresh scope and purpose. The accompanying picture shows how well they thrive at Lyndhurst. In the rather flat rock garden which frames the pool, choice examples of interesting saxifrages



FIG. 17.—IN THE ROCK AND WATER GARDEN.

with encrusted leaves find a congenial place, and their silvery foliage makes an attractive feature during those winter months when other plants are at their worst. Many another pilgrim from the Upper Alps flourishes in this rockery, while elsewhere in the garden some rare sorts of daphne are obviously favourites. Such surroundings demand a house which has simplicity for its dominant note, and no less can be said of the building which Professor Lethaby set there in 1901. Plain white walls and chimneys, red roofs, a lead-covered porch of curiously interesting shape, and gables of moderate pitch—these are elements always

satisfying if rightly disposed. We leave High Coxlease with a glance at the garden flowers growing out of a sea of fern, the latter always beautiful, whether in its tender green of spring, its duller hue at midsummer, or its rich and rusty brown in winter, but most of all when the coming of the frost touches the green to

brilliant yellow and Nature carpets the forest with an undergrowth of gold.

The especial charm of making a flower garden in a forest clearing is that the wilful tribes of Nature can be absorbed into the new population, where they will still flaunt their wild and brilliant graces. In such gardens the outlying parts are likely never to be more brilliant than in autumn, when the gold of the furze is glittering everywhere among the darker hues of heather and the fading greens of bracken. Furze is a great ally to the garden colourist, for the large and early varieties are followed by others that are small and late. As the old and pleasant saying runs, gorse is out of bloom only when kissing's out of fashion.




FIG. 18.—LILIES AND GABLES AT HIGH COXLEASE.

CHAPTER III.—A GARDEN IN BERKSHIRE.


Roses Grown as "Fountains"—Brick Dry-walling—Stone-edged Water Garden—Refined Detail and Ornaments.

N the outskirts of the village, a high old wall, with massive buttresses and well-wrought coping, encloses a beautiful new house of moderate size, designed by Mr. Lutyens, and a piece of ground of something under three acres. The land, when taken in hand, was old garden and orchard, with a strong westerly slope; the soil a rich loam of calcareous character. The lower part had been the apple orchard, but the greater number of the trees were dead, and many of the remainder so much crippled that but little compunction stood in the way of the removal of a certain number to make way for the new garden design.

The house is approached directly by a door in the wall to the road; an arched passage and a paved court with a fountain leading to the main entrance. Another doorway, close to the eastern angle, leads straight into the garden by way of a paved, rose-covered pergola. Between this and the house is a small rose garden. The path is now intersected by the wider terrace running parallel with the south face of the house; but proceeding in the original direction the paved path leads to a further



FIG. 19.—THE GARLAND ROSE. POINT OF VIEW "B" ON GENERAL PLAN (FIG. 20).






FIG. 21.—THE TANK GARDEN. POINT OF VIEW "E" ON GENERAL PLAN (FIG. 20).

display of roses; for, where it descends by a flight of seven steps to the orchard-level, there are masses of the beautiful garland rose planted in the border above the retaining wall. They grow untrained in their own way, like natural





FIG. 22.—PLANTING PLAN. SEE
"A" ON GENERAL PLAN (FIG. 20)
AND PHOTOGRAPH (FIG. 25).

fountains. After rising for six or seven feet they arch over, and the masses of warm white blossoms hang down over the wall face to within a foot or so of the orchard-level. Some of the old apple trees, either



AND FIG.

21

FOR PHOTOGRAPHS SEE FIG.

23.--PLANTING PLAN OF TANK GARDEN.

dead stumps or with only a little life in them, serve as supports for rambling roses, showing one of the several ways in which they grow willingly and display their

beauty.

The locality having no stone suited for dry walling, the retaining walls of the different levels are built in brick with earth-joints for planting. In these, pinks and saxifrages, stonecrops, sandworts, rock-cresses and other small plants of mountain origin luxuriate, and, having been planted by a master hand, fall into groups of pleasant form that give enough at a time of one kind of interest. The old boundary wall, which was found covered with grass and weeds, was cleared of all undesirable growths and planted with wallflowers, Cheddar pinks, stonecrops and a few other such plants.

From a garden door in the middle of the house front a wide paved walk, joining with and crossing the terrace parallel with the house, leads straight forward to the



FIG. 24.—WEST END OF FLOWER BORDER. SEE "F" ON PLANTING PLAN (FIG. 23).

orchard, to which it descends by a bold flight of semi-circular steps on to a grassy platform following the same form. From this, three broad grass paths diverge into the orchard; the paths proceeding to certain points from which others again radiate. These grass paths, ten feet wide, are kept mown. In the spaces between, where the grass is let grow as it will, hosts of daffodils appear in spring, followed by fritillaries and meadow saffron in their seasons.

The water garden on the lower level of the house-front, reached by two angular flights of steps, is a long parallelogram. At each end is a circular tank, with a square one in the middle. They are finished with a flat stone kerb and connected in a straight line by a narrow sill having the same kerbing. It is a happy home for




FIG. 25.—THE GARLAND ROSE, HANGING OVER A DRY WALL. SEE "A" ON GENERAL PLAN (FIG. 20) AND ON PLANTING PLAN (FIG. 22).




FIG. 26.—STEPS AND DRY WALLING. VIEW POINT "D" ON GENERAL PLAN (FIG. 20).



FIG. 27.—PLANTED DRY WALL. VIEW POINT "G" ON GENERAL PLAN (FIG. 20) AND ON PLANTING PLAN (FIG. 31).



some good water-plants, the greater number of them being natives. river banks and in the shallow waters of marshy places we often pass these good plants by with but scant notice because they are so closely pressed by masses of other less interesting vegetation; but, brought into the garden, one is better able to appreciate their rare beauty. The water forget-me-not we all know, but the fine leaves and spreading lace-like flowers of the water plantain (Alisma plantago) and the almost tropical quality of the bloom of the flowering rush







FIG. 30.—FLOWER BORDER NEAR BACK GATE. VIEW POINT "H" ON GENERAL PLAN (FIG. 20) AND PLANTING PLAN (FIG. 29).



(Butomus umbellatus) require the comparative isolation of some such garden culture to show their value. The water garden is bounded on its two long sides by wide flower borders filled with a restricted choice of plants that is varied in some degree

from year to year but retains certain general features.

The garden is rich in delightful detail, notably some remarkably refined figures in bronze and stone; one in the entrance court fountain, another on a pedestal in the square tank of the water garden, and a bronze Mercury at the southern end of the detached octagonal pergola. The paved paths, with their several flights of steps of varied and always pure design, add greatly to refinement and also to a comfortable impression of permanence in this remarkably beautiful and charming garden.

CHAPTER IV.—WESTBROOK, GODALMING.

Situation—Special Compartments—Careful Planting Scheme—Winter Garden—Covered Seats—Flower Border Facing North.

WHEN an architect of ripe experience and keen sensibility plans a house and garden for his own home, one may look for something more than usually interesting, and in Westbrook one is not disappointed. The house, built by Mr. Thackeray Turner of the hard local sandstone, stands on a plateau of high

ground to the west of Godalming; the deep valley of the river Wey is to the north and the valley of a tributary stream a little way to the south. The upper trees of a steep hanger on the northern side rise protectingly, and on all the outskirts there are also trees, with here and there a distant view between their masses.


The garden fronts are nearly south and west. On the south side a low wall encloses a paved space with beds and border of flowers, an eastward flight of steps leading down to further flower-borders. Straight in front is a wide, quiet lawn, bounded on the right by a long paved path shaded

by pleached limes.

The garden to the west of the house abounds in charming surprises. Its various subdivisions are linked together in a simple general design. Each section shows some distinct way of making a garden picture, and each entices onwards to the next by the charm of mystery and the stimulus of pleasant anticipation of something still better to follow. The main design has a walling of vew hedges, now, after a growth of thirteen years, approaching maturity. Within their several compartments are a small sunk garden of summer flowers, a rose garden and one for late autumn. Between these, crossing and forming in both directions the axis of the design, are twelve-foot-wide grass paths with flower-borders on either hand; the bright blossom showing finely against the background of dark vew. Turning southward at the intersection of the two grassy ways, a double arch of yew comes in



FIG. 32.—THE PLEACHED LIME WALK, FROM THE STUDY WINDOW. VIEW POINT "B" ON GENERAL PLAN (FIG. 33).



sight. Through and beyond this is the principal feature of the design, a large circular sunk garden for flowers of the middle and later year—an amphitheatre of summer glory (Figs. 36 to 38). Four ways, twelve feet wide, with groups of steps and partly sloping, lead to the lower grassy level, where a large octagonal tank with a wide stone kerb has groups of many coloured water-lilies. The four ways are punctuated, just within




FIG. 34.—A ROOFED SEAT.

the borders, by evergreens of upright habit, Chinese junipers, golden junipers and Irish yews. Looking from the western side, the garden takes its place as an adjunct to the house, with which it is connected by a pergola. Looking north and south there is the double yew arch with the further green paths and borderings of flower and shrub. The scheme of planting of the circular garden is interesting and effective. The sections



FIG. 35.—THE LOGGIA. VIEW POINT "A" ON PLAN (FIG. 33).



that are in full blaze of the noonday and early afternoon sun are of strong, warm colouring, for the most part orange and scarlet; the colour-scheme working round both ways to the cool and tender tints that are more acceptable on the shadier sides. The plan, reproduced in Fig. 36, gives an idea of the general arrangement, lesser details being omitted.


Going southward from this garden there is again the broad path, but of the local sand, which binds well; here there is an orchard of apples, pears and plums on the right, and a thick shrubbery to the left. Concealed in the middle of the shrubbery



FIG. 37.—THE SUNK GARDEN FROM THE SOUTH. VIEW POINT "C" ON GENERAL PLAN (FIG. 33) AND PLANTING PLAN (FIG. 36).

is a fifty-foot circle of grass with a bed of heaths in the centre—a pleasantly secluded retreat. Five winding paths lead out of it through the shrubs and trees in different directions, giving access to various points, and also serving as unobtrusive means of escape when a tired worker desiring rest and solitude becomes aware of approaching intrusion.

From the western upper side of the circular garden a narrow path leads out, and, turning to the right, goes—whither? Another slight turn, between dry-walling to right and left, reveals a solid double arch of stone leading into an enclosed space about thirty-five feet each way (Fig. 40). It is the winter garden—a delightful invention!






FIG. 39.—THE WINTER GARDEN: PLANTING PLAN.

Walled on all sides, the walling not high enough to exclude the low winter sun, it is absolutely sheltered. Four beds are filled with heaths, daphne, Rhododendron præcox and a few other plants. These beds, in company with the surrounding borders and the well-planted wall joints, show a full clothing of plants and a fair proportion of bloom from November to April (for planting plan, see Fig. 39). The brick-paved




FIG. 40.—THE WINTER GARDEN. VIEW POINT "E" ON GENERAL PLAN (FIG. 33).




FIG. 41.—A SHELTERED SEAT.

paths are always dry, and a seat in a hooded recess is a veritable sun-trap. The garden is rich in such sheltered seats, built and roofed, for, besides this one in the winter garden, and the loggia adjoining the house, there are two others at distinctive points (Figs. 34 and 41). They are important in the garden design in addition to their practical purpose; moreover, even if in passing by they are not actually used, it is a comfort to the eye and mind both to see the well-designed structure bounding some garden picture and to know of the comfortable and refreshing refuge. There is an important summer-house on the eastern side of the lawn, with solid stone walls and a tiled roof. It is cool all day, for a slight air passes through, and the doorways, facing east and west, only admit the earliest and latest sun.

The experiment of placing one of the most important flower-borders on the north side of a high wall has answered admirably. The light soil of the garden soon dries up, and in all but the wettest summers the plants have evidently been benefited by

the protection from hot sunshine at the root.

The pleached lime walk (Fig. 32) leads straight to a pretty place in the further garden, a long, straight walk of turf bordered by masses of China roses and grey foliage. The further end abuts upon a field gate to a lane which is a public footpath. It was a kindly thought of Mr. Turner to leave this in full view of passers-by, who thankfully lean their arms upon the gate and enjoy the feast of roses.

CHAPTER V .-- A GARDEN IN WEST SURREY.

Poor Soil—No Definite Plan—Paved Court with Tank and Steps—Colour in Flower-borders—Woodland Paths—Thunder-house.

FIFTEEN acres of the poorest possible soil, sloping a little down towards the north, in the Surrey hills. A thin skin of peaty earth on the upper part, with a natural growth of heath, whortleberry and bracken, where a wood of Scotch fir had been cut some twelve years before; the middle part a chestnut plantation, the lower, a poor, sandy field with a hard plough-bed about eight inches down. These were the conditions that had to be considered and adapted as well as might be to the making of a garden. In the upper, heathy part, seedlings of many kinds of trees were springing up, now fair-sized examples of twenty-five years' growth. As time went on they had to be severely thinned and at the same time




FIG. 42.—THE TANK AND STEPS. VIEW POINT "B" ON GENERAL PLAN (FIG. 44).

thrown into carefully-considered groups, one kind of tree at a time being given pre-eminence. A clearing in chestnut copse gave space for the future lawn, house and near garden. The lower ground was deeply trenched and heavily manured for many years, and is now a productive kitchen garden. Much of the ground had to be laid out, in some kind of way, before it was known where the house was to stand, with the result that there are portions that meet at awkward angles. In fact, there was no definite planning at the beginning. Various parts were taken in hand at different times and treated on their individual merits, and the whole afterwards reconciled as might most suitably be contrived. The only portion with a definite plan is a small paved court between two wings of the house and a double flight of steps enclosing a tank, all forming one




FIG. 43.—THE PAVED COURT AND STEPS. VIEW POINT 6 YARDS BACK FROM "A" ON GENERAL PLAN (FIG. 44). THIS PHOTOGRAPH WAS TAKEN IN 1908. COMPARE WITH FIG. 45, WHICH SHOWS GROWTH OF CLEMATIS MONTANA IN 1912, AND WITH FIG. 42, WHICH SHOWS PRESENT STAGE OF CLIPPED BOX BALLS.






FIG. 45.—THE PAVED COURT. VIEW POINT "A" ON GENERAL PLAN (FIG. 44).



FIG. 46.—THE EAST END OF THE MAIN FLOWER-BORDER. VIEW POINT "C" ON GENERAL PLAN (FIG. 44).



FIG. 47.—YUCCAS IN THE FLOWER-BORDER. VIEW POINT "E" ON GENERAL PLAN (FIG. 44).




FIG. 48.—A SPECIAL BORDER OF GREY, WHITE, PINK AND PURPLE. (SEE FIG. 49 FOR PLANTING PLAN.)




FIG. 49.—A SPECIAL BORDER OF GREY, WHITE, PINK AND PURPLE. (FOR PHOTOGRAPH SEE FIG. 48.)

design (Figs. 43 and 45). The court has a circular pavement, partly between two box-edged beds and partly bounded by a raised step next the house. On the sides of the raised pavement stand pots of fern and funkia, forming a good green setting for potted plants in flower—lilies, bellflowers, hydrangeas, etc., according



FIG. 50.—THE GREEN WOOD-WALK. VIEW POINT "F" ON GENERAL PLAN (FIG. 44).

to their season. Clematis montana drapes one side wall and hangs as a garland from the lower moulded beam of the timber-framed overhang. The opposite wall is clothed with a vine. The stairways on each side of the tank are punctuated by eight balls of clipped box. The tank itself has a wealth of ferns growing out of its cool, north-facing wall, the water being let in by a finely-designed lion mask, the work of Mr. G. D. Leslie, R.A. (Fig. 42).

From the lawn a wide turfway leads to another at right angles, beyond which is the main border of hardy flowers, eighteen feet wide and about one hundred and





FIG. 51.—ONE OF THE WAYS FROM WOOD TO LAWN. VIEW POINT "G" ON GENERAL PLAN (FIG. 44).

eighty feet long (Fig. 46). It is backed by a narrow alley, not seen from the front, but serving conveniently to get at the plants in the back of the border, and those on the other side against a high wall of the local hard sandstone. border has a definite colour scheme; at the two ends blue, white and palest yellow, with grey foliage; and purple, white and pink, also with grey foliage, respectively; the colour then advancing from both ends by yellow and orange, to the middle glory of strongest reds. Bold groups of yucca are at the ends, and flank a crosspath that passes by a doorway through the wall (Fig. 47). A plan of the actual planting, and details of some uncommon ways of utilising some of the plants to gain unusual advantages, are given in Miss Jekyll's book, "Colour Schemes in the Flower Garden." A special border in the further part of the garden is given entirely to a colour scheme of purple, white and pink, with grey foliage (Figs. 48 and 49). It follows, from

there having been no exact design for the whole, that the garden falls into separate spaces—an accident that has been used to some advantage by devoting each space to a season.

The woodland closely adjoins the lawn and garden ground, and much care has been given to the regions where the one melts into the other. From a narrow lawn that is next to the south front of the house a wide grassy way runs straight up into the wood, to a point where, at some distance away, a fine old Scotch fir, double-stemmed and therefore spared when the rest of the wood was cut, ends the view, which is still



backed by more distant wood. This wide green walk (Fig. 50) is the most precious possession of the place, the bluish distance giving a sense of some extent and the bounding woodland one of repose and security, while in slightly misty weather the illusions of distance and mystery are endless and full of charm. Nearest the lawn are groups of rhododendron, very carefully chosen for colour, with hardy ferns and one of the smaller andromedas filling up nearest the grass on the shady side, and tufts of the natural wild heaths, intergrown with the blue-flowered Lithospermum prostratum, on the side where the sun shines for some hours of the day.

Of the lesser grassy ways into the wooded ground, one that passes under the shade of oaks and birches has groups of some of the beautiful wild ferns—male fern, lady fern and dilated shield fern, in the natural setting of mossy ground and whortle-berry,

and a complete backing of bracken, with here and there a flowery incident—a patch of trillium, and further a little bank of the lovely little trientalis and a bold back grouping of Solomon's seal and white foxglove (Fig. 51). Another passes from the lawn between banks of Gaultheria, alpenrose and the larger shrubby andromedas; it is shown from above at Fig. 53. Another passes up through a region of azalea The intention of all the paths from garden to wood is to lead by an and cistus. imperceptible gradation from one to the other by the simplest means that may be devised, showing on the way the beauty of some one or two good kinds of plant and placing them so that they look happy and at home.

One place where two of the paths join that lead up to the wood has been arranged with a larger number of kinds of plants as a bit of garden for winter and earliest spring, but here the restful feeling is preserved by keeping the colouring within a



FIG. 53.—AUTUMN-BLOOMING SHRUBS. VIEW POINT "J" ON GENERAL PLAN (FIG. 44).

restricted range of low-toned pinks and purples, with a fair amount of quiet, deepcoloured leafage. The planting plan (Fig. 52) shows the arrangement.

There are but comparatively few shrubs that bloom in autumn; two of them,

viz., Æsculus macrostachya and Olearia Haastii, have been grouped together by one

of the paths between the shrub-clumps.

At the far end of the kitchen garden, where the north and west walls join at an uneven angle, stands a little building—a raised gazebo. From inside the garden its floor-level is gained by a flight of steps that wind up with one or two turns. Its purpose is partly to give a fitting finish to a bare-looking piece of wall and partly to

provide a look-out place over the fields and the distant range of chalk hill to the north; for the region of the house and garden is so much encompassed by woodland that there is no view to the open country. The little place is most often used when there is thunder about, for watching the progress of the storm, and an incised stone on the garden side bears its name of "Thunder-house." Fig. 54 shows it as seen from the road outside. One of its four openings is blocked by weather-boarding because if left open it would have overlooked a neighbour's house and garden.




FIG. 54.--THE THUNDER-HOUSE.


CHAPTER VI.--HIGHMOUNT, GUILDFORD.

Site and Views—Excavation of Chalk—Rose Garden—Planted Walls—Garden-houses—Colour Schemes—Framing the Views.

IGHMOUNT is one of the new houses standing on the chalk ridge that rises immediately to the south-east of the town of Guildford. The ridge seems to stand clear up into the sky, open to all the winds of heaven. The views, embracing some of the finest points in West Surrey, are extremely extensive, and, with the exception of one short section, are panoramic for more than three-fifths of the horizon's circle. Eastward is St. Martha's Hill, church-crowned; the horizon is then cut by the bold promontory of the Chantry Woods on a spur of sandy hill. The view then opens to its full extent, passing over the southern portion of Surrey, then over the whole width of the wooded Weald of Sussex, to the dim, far line of the South Downs. A little way to the west are the fine outlines of Blackdown and Hindhead,



FIG. 55.—CIRCULAR TANK AND STEPS AT WEST END OF ROSE GARDEN. POINT OF VIEW "A" ON GENERAL PLAN (FIG. 56).



about fourteen miles away. Still more to the right Wolmer Forest appears as a bluish haze; nearer in the same direction are the woods in the region of Waverley Abbey, and, close at hand, the valley of the Wey, backed by the ruined Chapel of St. Catherine

on its steep hill of sand and rock.

The garden ground, all on the southern face of the hill, but so near the top that it is greatly exposed, had already been laid out to a certain degree when the garden designer took it in hand. Tennis lawn, croquet lawn and bowling green had been levelled and made; but the steepness of the remainder, composed of grassy slopes between clumps of shrubs and flowers of no particular design, was found to be incommodious, and great need was felt for




FIG. 57.—STEPS AND PAVEMENT AT THE EAST END OF ROSE GARDEN. VIEW POINT "B" ON GENERAL PLAN (FIG. 56).

something more restful and systematic. It was evident that nothing satisfactory could be done without a serious amount of moving of earth. The ground lay in humps and hollows too blunt and shapeless in form to be utilised as they were, and yet with sides so steep that foothold was precarious and all progression uncomfortable. Happily, the owners were willing to face the necessary outlay, by no means a slight one; for digging in pure chalk is almost as serious a matter as quarrying in stone, and in places it was necessary to go eight feet into the solid, and also to find means of disposal of the waste stuff excavated. This was tipped all along the lowest of the ground to form a firm embankment for the rose garden. It was found just possible to get a width of fifty-five feet and a length of two hundred and eighty feet, so that




FIG. 58.--PLANTING PLAN OF TOP OF CIRCULAR DRY WALL. VIEW POINT "H" ON GENERAL PLAN (FIG. 56).



FIG. 59.—FROM THE MIDDLE OF THE ROSE GARDEN. VIEW POINT "C" ON GENERAL PLAN (FIG. 56).

there should be the comfort of a space fairly large and quite level, where there had formerly been a kind of nightmare of confused and treacherous declivities. Therefore, with ground rising on all sides but the south, the whole rose garden appears to be sunk, the additional comfort being acquired of absolute shelter from the north and of lying open to the sun. At the western end bold segmental




FIG. 60.—SKETCH OF PLANTING AS SEEN FROM VIEW POINT "D" ON GENERAL PLAN (FIG. 56).



FIG. 61.—ANGLE OF DRY WALL FROM VIEW POINT "D" ON GENERAL PLAN (FIG. 56).

curve of high retaining wall also gives shelter from any wind coming from a westerly direction. As will be seen in the general plan (Fig. 56), this encloses a lily tank and encircling rose-beds (Fig. 55); the rose-beds are continued as straight borders on either side along the whole length; the quiet middle green space is broken only by the square tank midway of the whole (Fig. 59). The eastern end has a flight of circular steps



FIG. 62.—CAMPANULA ISOPIIYLLA ALBA, IN THE DRY WALL, FROM VIEW POINT "E" ON GENERAL PLAN (FIG. 56).

has a flight of circular steps with a bold half-round paving at the foot (Fig. 57). This, with the pergola, garden-houses and their accompanying flights of steps on some of the upper levels, is the work of Mr. Douglas Round. Thus the rose garden is a long, level green parallelogram, quiet and restful, where before was only tumbled and disordered futility.

At the western end, backing the lily tank and rosebeds, the circular retaining wall is from six to seven feet high. The top is rather boldly planted with yuccas, the great Euphorbia Wulfenii, cistus, tamarisk and tree lupine, and, further back, with tree box, white broom and red cedar (Fig. 58). Barely two years planted, the whole is as yet too immature to show anything like the ultimate intention. Facing uphill across the tank one looks up a series of steps, rising flight after flight (Fig. 55). The two lowest, with a landing between, rise to a broad turf path between flower borders, running eastward to the tennis lawn and giving a long green vista of over three hundred feet, with again the feeling of reposeful space and security that had formerly been wanting. The whole length of

the rose garden has its six-foot-high retaining wall planted; not planted all over, but enough to display a number of beautiful things in suitable groups, the same plants being carried up on the top of the wall, where there is a space of four feet between the wall top and the hedge of tree box that surrounds the tennis lawn at the eastern end. The same space is also between the top of the wall and the shrubs




FIG. 63.—PLANTING PLAN OF BORDERS OF WEST WALK. SEE GENERAL PLAN (FIG. 56).

and bush roses that approach it further to the west. The wall is in full sun, and the good plants and sub-shrubs that we have from the Mediterranean region—lavender, rosemary, santolina, othorna and so on, with pinks, stonecrops and several of the rock-loving campanulas of the Alps (to name only a few of the plants utilised)—rejoice in the full southern exposure and the brilliant, unveiled light of the high elevation.



FIG. 64.—THE GARDEN-HOUSES, FROM VIEW POINT "F" ON GENERAL PLAN (FIG. 56).

The strong calcareous loam is also favourable, and the position in the joints between the stones, giving shelter and protection from wet to the crown of the plant, made it possible to use plants that would otherwise not be hardy. Conspicuously beautiful at Highmount, though so lately planted, is the tender South Italian Campanula isophylla, usually grown in greenhouses and not hardy in the open, though here in rampant growth and fullest health and development. Looking up the double flight of steps from the rose garden across the square tank from C (Fig. 59), a patch of this fine campanula shows on the right; the same group comes to the left of the picture in the angle view from D (Fig. 61). A further view from E shows another patch on the



FIG. 65.—THE WEST END OF THE PERGOLA, FROM VIEW POINT "G" ON GENERAL PLAN (FIG. 56).

face of the wall, with a group of nepeta (the pretty purple catmint) above and the Algerian Iris stylosa at the wall foot (Fig. 62).

The garden-houses, standing on the north side of the tennis lawn, will, in time, be pleasantly framed by the vines planted on the pergolas which bound and roof the two flights of steps giving access to the tennis lawn from the end of the main pergola and the garden above (Fig. 64). The building on the right has a nearly flat roof of corrugated iron, whose unsightliness has been veiled by a coating of earth and a planting of stonecrops. Above the buildings is the garden of spring flowers, where, besides all the other good things, it is a yearly joy to see the wonderful vigour and bloom of the wall-flowers. All the *cruciferæ* rejoice in a limy soil—stocks, wallflowers, iberis, alyssum, æthionema, with others of the same large botanical family, on such a soil are seen at their best. The flower borders are carefully considered for colour arrangement; the long green walk has a massing of strong reds and yellows in the middle of the length, with the ends cooler coloured, in the way that seems to make the most satisfactory colour picture. A shorter upper double border, called the west walk, is mostly of yellows, with tender and brilliant blue (Fig. 63). These colour-schemes are not only highly satisfactory in themselves, but they serve to give individuality and a quality of dignity and distinction to various portions of a garden. Offering to the eye one clear picture at a time, they rescue the beholder from the distracting impression of general muddle and want of distinct intention that is so frequent in gardens and so wasteful—wasteful because a place may be full of fine plants, grandly grown, but if they are mixed up without thought or definite scheme they only produce an unsatisfactory effect, instead of composing together into a harmonious picture.

Although the view at Highmount is very extensive, it is from the pictorial point of view not as beautiful as it might be, and as it is confidently hoped it will be in a few years' time. The material is there for at least half-a-dozen beautiful scenes, but, just as a painted picture is comparatively of little effect without its frame, so in a much greater degree is the outdoor picture. Everyone has noticed how, coming suddenly on some perhaps quite tame garden scene through a doorway, it seems to be invested with a strange kind of beauty. So, in the case of a view that is overpanoramic, we plant so as to cut it up and frame it in different directions. A glance at the general plan (Fig. 56) will show how this is provided for, the more deeply-shaded masses of shrubs and trees comprising such as will rise high enough to come well above the horizon line and make of each opening a definite picture. In the

plan the chief points of view so separated are shown by the feathered arrows

CHAPTER VII.—THE TREATMENT OF SMALL SITES.

Some Gardens by Mr. Inigo Triggs—The Value of Historical Examples—Paved Parterres—The Use of Treillage—A Town Garden by Mr. Lutyens—A Seaside Garden by Mr. Mallows—Planting Scheme by Mr. H. Avray Tipping—Various Typical Examples.

THERE is no problem before the architect and garden designer more difficult, and at the same time more attractive, than is presented by small sites, and particularly by the long, narrow spaces that go with houses of small frontage. So important are the limitations of the latter that a separate chapter has been devoted to the treatment of a typical case, *i.e.*, Millmead, Bramley (pages I to 9). In this chapter will be described various examples of successful small gardens that owe their charm mainly to skilful design, however well that has been expressed and emphasised by right choice in planting. Where the area to be dealt with is a small rectangle and flat, there are few better ways of treating it than by laying out a paved garden with or without grass, but preferably with it. If grass be omitted altogether, winter, with its empty flower-beds, brings a grim and bare look. It is fitting to begin

the series with one devised by

Mr. H. Inigo Triggs.

The revival of the right principles of garden design in England during the last twenty years is due to a comparatively small band of people, who by word and deed have shown the right way. The first thing necessary was to go back to such old examples as had survived the onslaughts of the "landscape" school, to publish measured drawings and photographs of them, and to analyse the qualities that make their beauty. In this necessary work Mr. Inigo Triggs has taken a leading part. His great folio volumes, Formal Gardens in England and Scotland and The Art of Garden Craft in Italy, were pioneer works that did great service. The especial need of such historical research becomes obvious when it is realised how swiftly and sometimes irrevocably the aspects of gardens change. Mr. Triggs has emphasised the fact that





FIG. 66.—LITTLE BOARHUNT, LIPHOOK.



no examples are extant of the garden as it appeared in the Middle Ages. If it is desired to reconstruct its features, recourse must be made to illuminated MSS. and paintings of the period. From such sources we learn about such enchanting features as the Ladies' gardens, which usually consisted of a little square enclosure surrounded by high walls. Even when we turn to much later periods we cannot be certain that the formal gardens adjoining old houses at all faithfully represent their original form. Succeeding owners and gardeners have impressed their own ideas on the gardens under their control. It is indeed doubtful whether any garden of even so recent a period

as the beginning of the eighteenth century appears to-day as it did when first made. A gazebo here or a fountain there may occupy its original place, but such elements as parterres, paths and hedges are likely to have been altered beyond recognition. The student is often impressed by the divergence between the existing condition of historic gardens and their presentment in early prints. The outlines and main divisions may be the same, but with details such as the widths of borders and paths and the placing of statues so altered as to destroy the original proportions and quality of the complete scheme. The value of Mr. Triggs' work has been enhanced by the creative ability which he brought to his labours. It follows that the gardens which he has himself devised are based on a wide knowledge of what gave to the old gardens of England their peculiar attraction. In the many houses which are the fruit of his partnership with Mr. Unsworth we do not look in vain, therefore, for scholarship and original fancy. Of these, Little Boarhunt, which is his own home, is a good example. It shows how the qualities that



FIG. 68.—LITTLE BOARHUNT: STEPS, GATE AND WALL.

make the beauty of the historic formal gardens may be reproduced in little for houses of moderate size.

Whether or not it be true that King John ran a boar from Liphook to Southsea before killing, Boarhunt has been the name of a Liphook manor since the Middle Ages. The site of the house now illustrated has been called in turn Deadman's and Fry's Farm, but Mr. Inigo Triggs did wisely in reviving so pleasant a name as Little Boarhunt. Other monarchs than John have been identified with the place, which is easy to be explained, for the old road from London to Portsmouth once passed through

the garden. It is an odd commentary on the levels of roads before Macadam's day that the surface of this old highway is quite twenty feet below the surrounding ground, and now forms the bottom of a woodland dell in Mr. Triggs' garden. Common lands interspersed with patches of woodland—all that now remain of the great forest of Woolmer—stretch away from the house for many miles. It is not too fanciful to guess that the garden of Little Boarhunt was the scene of a charming incident recorded by Gilbert White in the History of Selborne. "As Queen Anne was journeying on the Portsmouth road, she did not think the forest of Wolmer beneath her royal regard. For she came out of the great road at Lippock, which is just by, and reposing herself on a bank smoothed for that purpose, saw with great complacency and satisfaction the whole herd of red deer brought by the keepers along the vale before



FIG. 69.—A SIMPLE BRICK-BUILT DOVECOTE.

her, consisting then of about five hundred head." Mr. Inigo Triggs has smoothed many banks in the making of his garden, but the red deer have given place to pigeons. As lately as June, 1910, Little Boarhunt was a small farmhouse of no especial merit, with a barn and yard, but no garden. All the building and the remodelling of the farmyard was done in six months; by the spring of 1911 the garden had grown up, and it now looks old-established.

The note of gaiety is struck at the entrance. Mr. Triggs has chosen to border the drive with broad beds full of herbaceous plants, instead of with the dull shrubs that too often find a place there. The farmyard to the south of the house was excavated to make a sunk rose garden. Its retaining walls of rough stone are brilliant with saxifrages, pinks and veronica. Herbaceous borders separate the surrounding paths from the low enclosing walls, which are carried up with square stone piers supporting timbers clothed with climbing roses. Particular attention is drawn to this wall treatment, which is as delightful as it is uncommon. reference is made to it in Chapter X. The wall is broken at its south corner by


a garden-house, inexpensively built a single brick thick, with its faces cemented. In the neighbouring wall is a small old wooden hand-gate of satisfactory construction (Fig. 68). The sunk garden itself is an admirable example of the wealth of interesting detail that can be employed in a small space without creating any feeling of overcrowding. It is divided by a little brick canal, served by rain-water collected from the roof. This rill widens at its middle into a dipping pool, of practical use in watering the garden, and from it rises a slender brick column surmounted by a little Italian figure of a boy with a fish. The four beds for standard roses are divided by narrow brick paths, set out to differing designs. Altogether the garden is as pretty as can be, and has a further pleasant feature in the brick dovecote, which comes at the end of the north enclosing wall. It must be explained that the plan of Little Boarhunt shows to the south-west

a green court and pool which have not yet been made, but on pages 150 and 151 are given plan and sketch of the interesting fountain treatment which Mr. Triggs has devised for it. The area covered by the sunk and walled garden now illustrated (by a comprehensive view in Fig. 67) is only ninety feet by sixty feet, and is justly described as small.

The paved garden at Island, Steep (Fig. 71), illustrates a practical point of importance. The beds are arranged in such a way that all work on the flowers can be done from the paved paths. This is useful in the many cases where ladies do not leave pruning, etc., to the gardener, and like to do the work dryshod. In this garden the parterre is sunk about eighteen inches below the general level, and there are bands of turf above and below the retaining wall, but not among the flower-beds.

Another example of a paved parterre without grass is illustrated in Fig. 72.

which shows the treatment by Mr. Baillie Scott of a forecourt at the entrance front of house at Sevenoaks. An attractive feature of it is the raised basin in the middle. which is built in coloured tiles. Other examples of like treatment are at The Platts, Petersfield, by Mr. Inigo Triggs (Fig. 74); Combe-lands, Pulborough, by Professor E. S. Prior (Fig. 73); and Cray, by Mr. Maberley Smith (Fig. 75). The photograph of the last of these was taken before planting was begun, and shows the garden in all the naked-



ness of its unclothed masonry, but it shows the levels all the better for that. It should be explained that great tubs with clipped trees are intended to be placed at the ends of the tongues of paving, which otherwise would be purposeless. More detailed reference to the laying of paved work and to suitable materials are given elsewhere (Chapter XV.), but it may be noted in connection with the sunk garden at Plewland, Haslemere, designed by Messrs. Read and Macdonald (Fig. 77), that the dry-built retaining walls make, with their rough stone, a strong-looking base to the house itself. In districts where the local stone is costly for house-building or unsuitable by reason of being porous or possessing other defects, it is good to use it for garden walls. It yields a contrast with the red brick of the house and gives an impression both of roughness and stability that is helpful.




FIG. 71.—ROSE GARDEN AT ISLAND, STEEP.

posed with reference to four Irish yews. In the corners there would be wooden seats, which have been omitted in the perspective sketch for the purpose of clearness. For the same reason no roses are shown clothing the trellis and no flowers in the beds. The treillage itself is intended to be made of split oak laths interwoven basket-fashion, and the framing would also be of oak with little balls on the tops of the posts. The general effect of a scheme like this, when in being, is well shown by the

FIG. 72.—PAVED FORECOURT AT SEAL HOLLOW, SEVENOAKS.

In the case of small garden spaces which are overlooked there is nothing more helpful to the designer than a treillage screen. In Figs. 78 and 79 is shown a scheme. devised by Mr. Inigo Triggs, for the treatment of a square plot, which measures seventy-four feet each way. There is a stepped pool in the middle, and the shaped beds of a parterre are geometrically dis-

photograph of a trellis garden, which is included among the illustrations of the Pergola

Chapter.

Although this volume is devoted in the main to the gardens of small country houses, the designing of a town garden does not demand the application of very principles different except in so far as more conscious architectural motifs may find a just place. The garden at 100, Cheyne Walk, Chelsea, the residence of Sir Hugh




FIG. 73.—AT COMBELANDS, PULBOROUGH.




FIG. 74.—PAVED GARDEN AT THE PLATTS, PETERSFIELD.



FIG 75.--SUNK GARDEN AT CRAY BEFORE PLANTING.




FIG. 76.—PLAN OF PLEWLAND GARDEN.


Lane, is a good example of what may be done in a limited space (Figs. 81 and 82). The garden is divided from the space at the back of the house by a simple colonnade of stone. Fortunately, there existed two fine trees, one a mulberry of noble growth, and these make brave features.


A sense of length is given to the garden by the wide parallel stone paths, the middle one of which is interrupted by a round pool. At the far end the old, uninteresting wall has been transformed by the building of two niches, which shelter statues in the classical manner. Reference to the plan (Fig. 80) shows a practical point in the provision of a narrow flagged path up the east side, which gives access to the flower-beds on either side. The whole scheme is simple and unlaboured. Too often the makers of



FIG. 77.—THE SUNK GARDEN AT PLEWLAND, HASLEMERE.

town gardens try to make up for the absence of a fine show of plants by an excess of sculpture, which raises visions of a monument mason's yard. Mr. Lutyens has shown a wise restraint, and the garden has a refined classical flavour without being stiff. When the borders are furnished at their proper seasons with such things as arabis, spreading its bloom and leafage over the paving, and later with carnations that will bring their brilliant array of colour, the garden will be complete. Carnations in particular are kindly to the town gardener, and in nowise turn against a soil that builders of many generations have salted with brick rubbish. Indeed. the lime of old mortar is often a beneficent aid.





From Chelsea to a windswept Norfolk shore is a far cry, but the conjunction is instructive, as it emphasises the great influence of wind on the design and planting of gardens. There is shown in Figs. 83 to 85 a scheme for remodelling a dilapidated little homestead at Happisburgh, designed and drawn by Mr. C. E. Mallows. The essence of the planning is the protection of the garden from the fierce and frequent winds that blow from north and east. This would be contrived by repairing an old barn on the east side to serve as a playroom or studio, and some cow hovels on the north to make a covered way, useful for summer meals or for a skittle alley. The house is on the west, and the garden is open only to the south or landward side, where additional




FIG. 80.—PLAN OF A TOWN GARDEN.

shelter would be provided by planting trees, as described later. On the house side, a hedged recess with some sort of seat or shelter is planned so as to continue the lines of the house and form a feature and a bulwark between the flower garden and the more open lawn. The flower garden is essentially the old farmyard converted. be cleared out, the central part sunk and fresh soil introduced, and laid out in flagged paths and steps surrounding the flower-beds and edging the borders which lie against the buildings. The planting of such a garden would depend upon two considerations. The first is whether it is to be merely a place of summer resort, or whether it is intended for inhabitance at other seasons of the year also. The second consideration takes in the questions of soil and climate, for on some knowledge of these will largely depend the choice of plants. There are enough and to spare that will flourish here, and care should be taken in making a selection not to stray beyond this quite adequate store. The following scheme of planting has been devised by Mr. H. Avray Tipping, and will give many helpful suggestions to the owners of seaside gardens. The soil resembles that of Holland, and the Dutch have now bulbgrowing competitors in East Anglia. bulbs should therefore be freely used, for the sheltering buildings will save even the brittle-stalked tulip from destruction by wind.

Short-stemmed species may be reserved to less protected areas. The formation of wind-breaks is the preliminary operation. A bank would be raised, behind which young trees can obtain early shelter. Sycamores, poplars and Austrian firs will prove the most successful. Near to the bank they should be set in serried ranks, affording mutual support, and be allowed to grow into a tangle. Further in, the planting should be more sparse, and thinning should be yearly attended to, so that the trees that are left may attain fine shape and good grouping. Where high trees are not desired, sea buckthorn will brave the gales and make a thicket. Close planting in this case also



FIG. 81.—AT 100, CHEYNE WALK, CHELSEA: POOL AND STATUES.



FIG. 82.—THE SCREEN.




FIG. 83.—SCHEME BY MR. C. E. MALLOWS FOR A SHELTERED GARDEN ON THE EAST COAST.

should be the rule, but for a further reason. Unlike our own species, that of Hippophaë rhamnoides seems to produce a majority of the male sex, and nine-tenths of them must be cut out, so that the yellow-berried Amazons of the tribe may have full scope to display their charms. Within these shelters, and even without them, the Japanese euonymus, both green and golden, will flourish, while Griselinia littoralis, Escallonia macrantha and Olearia Haastii are only a few of the other evergreens that have a friendly feeling towards the sea. But the subjects must be educated to rough usages. Let them be pot grown or yearly transplanted stuff. Plant late in spring. Use the local reed-screens against wind and sun. Be liberal with the water-pot and the syringe when the air is hot and dry. Thus treated, tamarisks, gorses and brooms will be thoroughly at home. None of these will mind a slight




FIG. 84.—PLAN FOR A SHELTERED SEASIDE GARDEN.

sprinkle of salt or a moderate buffeting of wind, and, if rightly arranged, they will frame an enclosure as thoroughly protected as the sunk garden itself. That, with its artificial bulwarks all ready, will offer an immediate harbourage. The tree-surrounded oasis will be a future outlet for gardening energy. The early bulbs already spoken of—not tulips merely, but daffodils and hyacinths, chionodoxas and squills, anemones and crocuses—should have an accompaniment of double arabis and varied aubrietias; of wallflowers, Alpine species as well as garden hybrids; of Blue-eyed Mary and rose-coloured Himalayan primrose. The last two will share the dampest spot with some of the mossy saxifrages, while the low dry wall, which sustains the wide walks that stretch out on a level from the loggia, will be the home of the encrusted section and of sedums and houseleeks. Of the last named there are

new varieties which are of a rich deep red when grown in seaside sun, and the poorest soil and driest place will suit them side by side with Zauschneria californica, which will bear its tubular scarlet blooms from July to frost. The great majority of alpines will do well here. The charm of many of them depends on their close and orderly growth and the delicate poise of their blooms. In the rich soil of enclosed and leafy




FIG. 85.—POOL AND PAVING.

valleys they are apt to take on a coarseness which renders them almost valueless. Their original deportment will, however, be well preserved in the light soil, the brisk air and the open character of the East Coast. The dry walling of the sunk garden should therefore be reserved for them, while a section of the suggested extension can be prepared for additional location. No rockwork should be attempted. Rocks adequate in size and number to create an effect would be costly to import, and would look quite alien to the environment. But miniature hills and dales, such as we often find among sand-dunes, can be created and covered with the largest sizes of the seashore pebbles. Such arrangement will exactly suit the rooting and growing habits of the plants, which will soon lay their leaves and stems over the stones. The slight acclivities may rendered more nounced by setting tall things on them. sea hollies (eryngium) would look admirable so placed. Their tough stalks withstand the wind, and that should be a consideration in making the selection. Very likely the wandflower (Sparaxis pulcherrima) might succeed here, for it will bear hard frost when other conditions are favourable. Its tall wing stems, headed by the pink cascades of bloom, sway easily in wind and never break. Sea lavenders and horn poppies would be thoroughly apt, and when we seek to accentuate the depressions by planting them with lowly growths, we should not forget such seaside subjects of sessile habit as the thrifts and Silene maritima.

While there is no reason for limiting the selection to shore plants, these should be well represented, and give the note to the whole arrangement. look awkward and unfriendly in such association should be excluded, for in the treegirt extension which we are now considering a somewhat natural lay-out should prevail, and the formal garden alone should contain florist flowers. Of these, carnations do well, and assume their most brilliant colouring by the sea. Roses flourish if adequate shelter, such as this garden possesses, is provided. The petals of many varieties, however, become spotted and decayed by the slightest tincture of salt borne in the rain driven by a sea wind. Such should be avoided, and stout-petalled kinds chosen, such as Caroline Testout, Marie d'Orleans, Frau Karl Druschki, Belle Siebrecht and George Nabonnand. Such is a meagre outline, with only very occasional filling in, of how this bare and derelict homestead could be converted into a charming home, surrounded by flourishing gardens. In preparing a list for planting the latter, it must not be forgotten that this Cromer country has been called poppyland, and that the great tribe of poppyworts, including romneya and argemone, must be duly honoured and housed. Of shrubby growths the hardy fuchsias will flourish, while to the evergreens already mentioned Choisya ternata, lavender and rosemary must certainly be added. Probably the delightful creeping form of rosemary will here survive the winters, for it is not frost but damp which is its enemy.

We may now leave this East Coast garden of a dream, for another that is in being. In nothing is there opportunity for greater skill than in the treatment of small sites of irregular shape, such as that shown in Fig. 86. Eastwood Cottage, Walberswick, stands on a narrow tongue formed by two converging roads, and Mr. A. Winter Rose has made the most of an awkwardly-shaped plot by breaking it up into several features of interest. Two are illustrated in Figs. 87 and 88. The east corner is laid out as a rock garden, to which access is given from the sunk wall that runs along




FIG. 86.—PLAN OF LITTLE GARDEN AT WALBERSWICK.






FIG. 87.—WALBERSWICK: MASONRY SEAT—

FIG. 88.—AND STEPPED PATH.

the north boundary. It is entered between a pair of masonry piers (Fig. 88), and the flagged path, broadly stepped, is in good accord with the rockwork. Its southern end is approached along a path, flanked by broad herbaceous borders, which skirts the angled seat shown in Fig. 87. Other good points about this garden are a little bird bath in the form of a circular canal and a pigeon-cote adapted from an old tool-shed.

It is not often that the laying-out of a garden suffers such interference as at Goodrich House, Hatfield, where Mr. Winter Rose had to deal with a very unusual situation. Across the length of the garden there was a right-of-way, which had to be respected, though it is rarely used. It was necessary, therefore, to divide the garden scheme into two parts. The little paved court at the back of the house is




FIG. 89.—PLAN OF GARDEN AT GOODRICH HOUSE.

enclosed by two buildings, which project on each side. This section. with its charming little pool, is illustrated in Fig. 92, and the letter A on the plan (Fig. 89) shows the point of view. The right-of-way has been masked to a large extent by carrying it through a little polygonal walled space with four gateways, two on the axial line between the house and the main garden, and two on the line of the right-of-way. When this "no man's




FIG. 90.—FOUNTAIN AT GOODRICH HOUSE.





FIG. 91.—GOODRICH HOUSE: FROM VIEW POINT "B" ON PLAN.



FIG. 92.—FROM VIEW POINT "A" ON PLAN (FIG. 89).



land" has been passed we reach the garden proper, and notice on the left a pretty masonry fountain, illustrated in Fig. 90. The setting-out of the rest of the garden is sufficiently indicated by the general plan

(Fig. 89).

A site almost square and flat without natural features offers a blank cheque in the matter of design. In Fig. 93 is illustrated such a garden laid out at Dorchester, Dorset, by Mr. Morley Horder, the architect of the house. It shows a useful division of the space into flower and kitchen gardens. As Horman wrote in his Vulgaria, "the knotte garden serveth for pleasure, the potte garden for profitte." Importance is given to the scheme by the wall in alternate bays, which divides the two main divisions and ties them both to the house. A photograph of a similar wall in another garden is reproduced in Chapter X. The two long pergolas which reach out from the house southwards serve a like purpose. A word must also be written about the very useful plan of a narrow suburban garden site shown in Fig. 95, and by sketch in Fig. 94. The ground treated measures only fifty by two hundred and ten feet. The garden on the entrance side is happily managed. It is divided by a tall yew hedge running east and west, so that a pretty little square garden, walled on the north and west sides, is provided for the sole pleasure of the servants. The entrance court adjoining it is left perfectly simple with grass margins to the paved walk. Flowers are concentrated on the low terrace, which is reached from the loggia. A hedge divides it from the tennis lawn, which is surrounded by lime trees, presently to be pleached. success of the scheme is the result in no small measure of not attempting too much, which is the usual fault in very limited gardens.




FIG. 95.-GOOD ARRANGEMENT OF NARROW PLOT.

CHAPTER VIII.—ON HILLSIDE GARDENS.

Lady Mary Wortley Montagu on Terraces—Stairways—Terraced Gardens—Inexpensive Materials—Various Examples.

Whether from the point of view of house or garden, it is a moot point whether it is better that the slope shall be *downwards* from north to south, or with an upward slope southwards. Assuming that the house is to face south, the former disposition means an open and the latter an enclosed view. Most people prefer an open outlook, but there is a feeling of comfort about seeing one's own boundaries that needs to be taken into account. Generally, however, an alternative is not available, and our site has to be accepted as Nature fashioned it. When a hillside is considered purely from the point of view of garden design, it is obvious that its chief merit is that it calls for the free use of terracing and steps, and no other two features of garden architecture give so great an opportunity for varied and striking treatment. Bacon said that a bay window was the place for conference, and one may pay equal heed to a more lightsome

author in her definition of a terrace. Writing from Hinchinbrook to her husband a few months after her marriage, Lady Mary Wortley Montagu tells him, "I walked yesterday two hours on the terrace," and again a few days later, "The terrace is my place consecrated to meditation, which I observe to be gay or grave, as the sun shows or hides his face." Solvitur ambulando is always a good rule, and a terrace walk, with its unchanging prospect and the sense of security given by its balustraded walls, is always friendly to quiet thought. It keeps the mind free from that hint of surprise which tickles the fancy of the true country lover in the turns even of the most quiet lane.

That the creation of artificial levels is not, however, the only way to deal with a hilly site is clear from the first illustration of this chapter. It shows the admirable effect of




FIG. 96.—TREATMENT OF SLOPING GROUND WITHOUT STAIRWAY




FIG. 97.—AT HURTWOOD, SURREY: A STEEP ASCENT.

a broad sloping grass path between two yew hedges at Hurtwood, Surrey. It will be noted that the size of this part of the garden is considerable, and it is precisely this element which makes its success. A like treatment on a small scale would tend to dulness, and we may turn therefore to the stepped treatment of another part of the same garden. The ground covered by the stairway shown in Fig. 97 is quite small in extent, and therefore serves as a guide for the treatment of other steep sites. No little of its charm is in the contrast between the formal masonry of the steps and landings and the luxuriant growths which border them. In Fig. 99, which shows a design by Mr. C. E. Mallows, a similar treatment is indicated, but for a site with a far gentler slope. This enables very broad steps to be used without "risers," and does away with the need for landings, which are essential in the case of steeper stairways. It should be borne in mind that it is rather troublesome to walk up and down easy stairways with broad treads of this type unless each tread is broad enough to make it comfortable to take two steps to each. This suitable width is indicated in Mr. Mallows' drawing, but no definite dimensions are given here, as everyone can easily

experiment for himself and fix on a width which he thinks most comfortable.

We may now consider the use that has been made of terracing by Mr. Thomas Young, who laid out the garden at Mr. G. Muntzer's house, Littleholme, Guildford, Surrey, in conjunction with Mr. Voysey, who was the architect for the house. plan and section (Fig. 100) show clearly to what good account the hillside has been put. When the construction of the approach from the road was in hand, the hill showed the defects of its qualities, for the slope on the north side was very awkward. On the south side of the house a wide paved terrace has been provided with a pleasant double staircase leading down to a small grass garden surrounded by yew hedges, and provided with a pond and sundial. The little plateau so formed is held up on its south side by a curved brick bastion, which appears in Fig. 102.




fig. 98.—Hurtwood: Plan of gardens near house.

Westward of this, the garden is laid out in gradual terracing with flights of steps of easy gradient, which lead to what is now being planted as an orchard. The setting of the house on its precipitous site is perhaps best appreciated by the view shown in Fig. 101, which was taken from the loggia looking out across the terrace to the magnificent view that reaches to Bramley and Ewhurst. The garden walls are of purple brick coped with Bargate stone, and some of the terrace retaining walls are of flints which were dug from the site. On the front of the big lower bastion is an interesting gargoyle in wrought lead, which is illustrated in Chapter XIV. The making of such a garden naturally involved considerable excavation, and its owner has wisely proceeded with the work slowly. Our photographs hardly do the designer justice, because the garden as yet lacks the luxuriant growth which will soften the outlines of wall and terrace. It is useful to add that work of this kind, involving very considerable excavation, is a costly matter. The mere work of digging and wall-building, the construction, in fact, of the carcass of the garden, cost over five




FIG. 99.—DESIGN BY MR. C E. MALLOWS FOR STAIRWAY ON GENTLE SLOPE.

hundred pounds, and this takes no account of planting, but the money has been

worthily spent.

Sometimes, as at Hurtwood Edge (Fig. 105), the obviously right placing of the house with reference to aspect and view brings it about that the slope is at an angle with the chief front. It is a dangerous enterprise to plan a terraced garden on irregular lines in order to follow an erratic contour, and a geometrical, or at least symmetrical, shape will almost always be the best. The perspective view reproduced in Fig. 105 represents the original design of the garden (not yet carried out entirely). It shows how delightful a feature may be made of the tall buttress with its pier at one corner of the terrace. The natural fall of the site gave an architectural opportunity which Mr. Arthur T. Bolton, who designed the house,




FIG 100.—LITTLEHOLME, GUILDFORD: PLAN AND SECTION SHOWING TREATMENT OF SLOPING SITE BY MR. THOMAS YOUNG.




FIG. 101, —LITTLEHOLME, GUILDFORD: VIEW FROM LOGGIA ACROSS FIRST AND SECOND TERRACES.




FIG. 102.—LITTLEHOLME, GUILDFORD: TERRACES AND STAIRS FROM SOUTH-WEST.

was not slow to grasp. The plan, shown in Fig. 108, elucidates the scheme, and the neighbouring views mark the happy effect of the upper terrace of the house and the balustrading built up of curved tiles. The stair in the foreground of Fig. 106 is part of a simpler scheme of treatment than that originally planned. An unpretentious




FIG. 103.—LITTLEHOLME: SHOWING OUTLINE OF UPPER TERRACE,—



FIG. 104.—AND THE TERRACE STAIRS.




FIG. 105.—HURTWOOD EDGE: SCHEME FOR GARDEN.



FIG. 106 —HURTWOOD EDGE: TERRACE FROM BELOW.




FIG. 107.—THE TERRACE.

but satisfactory way of dealing with a sloping site in a small garden is shown in Fig. 109, which illustrates the garden at The Barn, Witley, Reading. Mr. Frank Chesterton has done no





FIG. 108.—HURTWOOD EDGE: PLAN OF GARDEN SCHEME.

more than provide a short flight of steps, between dwarf walls, which leads to a little terrace. The materials deserve a word. In order to save cost the steps were built of rough purple



FIG. 109.—AT THE BARN, WITLEY, READING.

lumps of old burnt firebrick, which can sometimes be got from gasworks for a nominal sum, if not free. This must not be confounded with black gas clinker, which some misguided folk have used for rockeries. Clinker is as dismal and unpleasant a material as the old firebrick is attractive. The latter should not be used when the cost of good brick or tile or stone can be encompassed, but as a cheap alternative it is quite satisfactory. The view from the garden door at The Barn is a happy commentary on the pleasant air which a suburban garden can take on when some thought and very little money have gone to its making.



Another interesting treatment of a hillside site is shown in the photograph and plan (Figs. 110 and 111) of a garden at Steep, designed by Mr. Inigo Triggs. In the front of the house is a terrace twenty-five feet wide, with steps leading down to a semi-circular grass terrace bordered by yew hedges. The next lower level is occupied by two flower borders divided by a grass path. From the end of the latter another flight of steps leads down to a green walk, which is enclosed on each side by yew hedges. This slopes down to a round rose garden. The section which is printed below the plan (Fig. 110) shows clearly how admirably the slope has been employed to give a succession of interesting garden incidents.




FIG. III. - A HILLSIDE GARDEN AT STEEP.

CHAPTER IX.—STEPS AND STAIRWAYS.

Approach Steps from Road—Stairways in Children's Dramas—Stepped Treatment for Gentle Slopes—Straight and Curved Stairs—Terrace Steps—Unformal Stairs.

THE notes on the treatment of hillside gardens given in the last chapter necessarily included some references to stairways associated directly with terracing, but the question of steps and their design arises in every kind of site, and in many parts of it. It is usual for a long stairway to be built of the same width throughout its flight, but a very pleasant variety can be got by widening it as it descends. The example shown in Fig. 112 is at Ardkinglas. It was devised in this manner by Sir Robert Lorimer, and very attractive it looks. Where the site of a house stands well above the roadway an interesting and dignified approach is secured by broad steps,




FIG. II2.—WIDENING STAIRWAY AT ARDKINGLAS.




FIG. II3.—CURVED ENTRANCE STAIRWAY AT OWLPEN MANOR.




FIG. 114.—AN UNRAILED STAIR.




FIG. 115.—AN ANGLED STAIRWAY WITH LOW COPING.

semi-circular on plan, such as is seen at Owlpen Manor (Fig. 113). When a considerable difference in level between two parts of a garden is masked by a wall pierced with a communicating door, an interesting feature can be made of the necessary steps. gardens frequented by children—and it is a sad place that never knows their hurrying footsteps—unrailed stairs are not without danger. It is not difficult to see that, for young folk, the doorway illustrated in Fig. 114 demands to be made the scene for those swift comings and goings that belong to the search for treasure and the rescue of distressed maidens. The top step is obviously the place for the last stand of a devoted retainer, sworn to defend the brave lady of his absent lord. The shadow of the wall is no less clearly the place where conspirators will gather with hood and lantern, until the door flies open and the heroic knight leaps on them sword in hand. All this is right and proper, and it is one of the justifications of garden architecture that it provides a stage. But an unguarded stair in conjunction with a doorway that conceals its dangers is a trap that may break young heads, and this aspect of the matter needs to be remembered. There is more of safety in the provision even of a low coping that follows the line of the steps, as in the angled stairway shown in Fig. 115. In the case of broad stepping that leads down to terrace walks it is often pleasant to break its line by a little pool or other projection from the upper level, such as is indicated by the treatment which Mr. Walter Cave employed at Ewelme Down (Fig. 116).

Small gardens of gentle slope must usually be formed as a series of shallow terraces for reasons of economy, and the stepped scheme at Home Place, Holt, designed by Professor E. S. Prior, will be a counsel of perfection to most people. Still, it is illustrated in



FIG. 116.—TERRACE STAIRWAY DIVIDED BY SMALL POOL.



Figs. 117 and 118, because it is full of ideas that are capable of being interpreted on a smaller scale. The characteristic and beautiful house is built of flint and tile, and its south side is planned "sun-trap" fashion. A curved flight of steps leads down from the main terrace to a long stairway of gentle descent with wide, shallow treads. This



FIG. 118.—AT HOME PLACE, NORFOLK.

is divided down the middle by a long stepped pool, which is richly hospitable to freegrowing water plants (Fig. 117).

Returning, however, to strictly small gardens, it may be said that many of them lose in attractiveness by the careless treatment of the short stairways which lead from one level to another. It is not always realised how much additional charm is given by the well-conceived design of such details, or how great a variety lies open to the straying choice. Steps need to be considered in relation to the retaining walls, in which



FIG. 119.—ALTERNATION OF ROUND AND SQUARE STEPS.

they often make a break. They should have wide treads and low "risers" so that they are easy-going. Too great a regularity in their building is generally to be avoided. Rough rubble masonry is to be preferred to ashlar, where stone and not brick is the material, but the rustic character should not be overdone. Great variety is to be attained by a happy conjunction of straight with curved steps, as is seen in Fig. 119, which shows also the value of rough



FIG. 120.—STEPPED APPROACH TO PERGOLA.

piers to mark the break in the retaining wall. This example is chosen from Island, Steep, designed by Messrs. Unsworth and Triggs. A similar treatment is illustrated in Fig. 120, which shows the entrance to a walled garden at Ewelme Down. A terrace stair at the same house, half-round on plan, is also shown in Fig. 122. The plea for the wide treads that make an easy-going stairway only holds good when practical considerations of site and convenience make it possible. Where there is a great break in levels a steep flight may be inevitable, and Fig. 123 shows how very pleasant it may look. It is rare that an approach road is very greatly higher in level than the ground floor level of the house, but this



FIG. 122.—ROUND STAIR ON TERRACE.



FIG. 121.—DETACHED PORCH AND STAIR.

sometimes happens on a steep hillside. At Sullingstead, near Hascombe, Mr. Lutyens has contrived an interesting way out of the difficulty. At the upper road level has been built a detached porch with a tiled roof carried on pillars. From this a brick stair winds down to a narrow forecourt, which divides the entrance door from the foot of the porch stairway by no more than a few feet.

In the contriving of the stairs from house terrace to lawn it is desirable to avoid the common mistake of making them too narrow.




FIG. 123.—STEEP FLIGHT OF STEPS AT MATHERN.

Several examples are given which show stairs adequately designed in this respect. That illustrated in Fig. 124 is in the garden of a house in North - East Lanca-shire, designed by that able artist and attractive personality, the late Dan Gibson, who did so much to revive the type of architecture proper to the Lake District. The rough stone steps accord well with the drywalling. Attention may also be drawn



FIG. 124.—ROUGHLY BUILT STAIR FROM TERRACE TO LAWN.

to the pool set in an embrasure of the wall. Another example is in a more regular and finished manner (Fig. 125). It is at a house designed by Mr. Lutyens, and the variety in the steps descending two ways is in charming contrast to the massive bulk of the retaining walls of the terrace. Very often it produces an excellent




FIG. 125.—TERRACE STEPS BY MR. LUTYENS.




FIG. 126.—BROAD STAIRWAY FROM TERRACE TO LAWN

effect to provide a very broad flight of steps from the middle of the terrace to the lawn below, such as is suggested by the drawing by Mr. C. E. Mallows

(Fig. 126).

In the chapter on "Water in the Formal Garden" many of the diverse schemes shown by photograph or drawing depend for their success on the steps with which the pools compose. The design by Mr. Inigo Triggs, now illustrated in Figs. 127 and 128, gives a hint for the treatment of a double stairway connecting two levels, and has a shaped pool for its central feature. This scheme could be applied very appropriately




FIG. 127.—DOUBLE STAIRWAY WITH POOL.




FIG. 128,—PLAN OF ABOVE.



to the descent from house terrace to sunk garden, or as the ascent from such sunk

garden to a lawn beyond.

Although stairways are among the most useful elements in garden design, and give just opportunity for conscious architectural treatment, it is not always desirable to force the note of formality. In situations where Nature has been lavish with her wild charms the signs of the hand of man should be suppressed, so that nothing may appear to compete with effects of a kind that no designer can bring. Even in small gardens that are made on woodland sites there is often a green alley over-arched with trees which fleck the path with sunlit tracery. Of such a kind is the example illustrated in Fig. 129. The stone steps there are of the simplest, and show themselves to be perfectly right for their situation. The adding of flanking piers crowned by vase or statue would strike a note of artifice which would accord ill with the natural beauty of the scene.

CHAPTER X.—BALUSTRADES AND WALLS.

The Design of Balusters—The Imitation of Historical Examples—Walls and Parapets of Open Brickwork—Walls Surmounted by Beams—A Coronal Garden—Serpentine Walls—Building in Concrete.

TERRACE balustrading in stone of the sort shown in the picture below is a costly feature of garden architecture, and belongs rather to large schemes than to those which develop round a small house. Beyond illustrating as models this Jacobean example, and a modern application of the same treatment by Mr. Inigo Thomas at Rotherfield, in Figs. 132 and 133, it will, therefore, be enough to put in a claim for refinement in baluster design. In the terraces of great houses where






FIG. 130.—A JACOBEAN BALUSTRADE





the scale is big throughout, a certain heaviness of treatment is not only allowable but even necessary, but small schemes demand delicate handling. It is unsafe to rely upon historical examples for imitation merely because they look admirable in their own setting. We have to reckon with the glamour which age brings with weathering and lichen, and to beware. There are many features of old work which will not bear reproduction without looking garish to the point of vulgarity. It is difficult, moreover, in the case of an old house or church, to draw a line between the emotional appeal of history and the strictly architectural merits, the more so as Time's way with buildings, as with men, is to soften them. The student of such things may amuse himself by wondering what would be the verdict of the sightseer concerning Roslyn Chapel if he were to see it in all its luxuriance, but fresh from



FIG. 132.—TERRACE BALUSTRADE AT ROTHERFIELD.




FIG. 133.—ROTHERFIELD: DETAILS OF TERRACE WALLS.




FIG. 134.—IN MOULDED BRICK.

the chisel, and without the mist of sentiment which rises from the legend of the Prentice Pillar. In considering the value of old work as a model for imitation it is necessary to study the material to which has been given various forms. The balusters at Newton Ferrers (Fig. 131) have a coarseness of outline which amounts almost to brutality, and makes them very unsuitable as models. Yet in their own place, and against the austere background




FIG 135.—OPEN PARAPET OF CURVED TILES.

of an eighteenth century house, they are seen to be altogether admirable, because they are of Cornish granite. The form was determined by the intractable material and exactly suits it. From these notes it will be clear that it is impossible to lay down any rules for the design of terrace balustrades of stone; they form an integral part of the house, and are governed by the factors which determine its





FIG. 136.—OF HOLLOW HEXAGONAL TILES.

architectural treatment. Terrace walls of open brickwork make a simpler problem. Much can be done with tiles and bricks of ordinary forms in achieving interesting varieties of treatment. The wall illustrated in Fig. 134 shows bricks moulded after a Portuguese pattern, which give a light and lace-like effect. The short stretch of parapet which appears in Fig. 135 is of very pleasant appearance, but it is built up of ordinary elements. The rusticated piers are of thin red bricks, and the openwork of curved tiles, each made to a quarter of a circle. Fig. 136 shows a North Italian example of hollow hexagonal tiles with top rail and plinth. The expense of preparing moulds for a special size or shape of hand-made brick is trivial when it is spread over the making of a few thousands. Fig. 137 shows a design by Mr. Inigo Triggs for an attractive and unusual wall with tile capping and recurring panels filled with pierced and shaped bricks.

The walls of fruit gardens are best built in a straightforward way, but fancy may be let loose in designing the walls of a flower garden, especially if the treatment



contemplated lends changefulness to variety of growth. Very often the designer of a small garden is faced by the difficulty of giving it privacy, and shrinks from the uninteresting solution of building a plain high wall. In such a case the two schemes indicated in Figs. 138 and 139 suggest happy alternatives, the former of which appears in a modified form in the picture (Fig. 68) of Mr. Inigo Triggs' own garden at Liphook. It shows a stone wall eighteen inches thick, and it is desirable, where choice is possible, to build it of sandstone in order that it may weather to a pleasant colour. This type of garden masonry looks best when the joints are well raked out, so that each individual stone may show distinctly. The piers are spaced ten feet apart, and are connected by curves. Rough beams about four inches square, with cross-pieces about two inches square, are supported on the piers, and roses and other creeping plants are trained to intertwine amid the woodwork. In Fig. 139 a similar arrangement is shown for brick




FIG. 138.—STONE WALL WITH TIMBERED PIERS. FIG. 139.—THE SAME IN BRICK WITH FLOWER BOXES.

walls, with this interesting difference: the piers for a distance of two feet from the top and the boxes at their sides are of four and a-half inch brickwork filled with earth. In the illustration these receptacles are shown in broken section rather than with appropriate plants growing, in order that the method of construction may be clear. Each should be drained with a small pipe about one inch in diameter, which will throw the drainage-water clear of the wall on its far side. The spacing of the piers in this case, as in the last, should be about ten feet, and a good height for either type is eight feet, the walls thus being about five feet. Where bricks are used, red is the best colour. If only inferior bricks are available, the walls should be rough-cast or cemented (a finishing coat being laid very roughly), and should show the marks of the wooden float. Much more ambitious and very successful is the design of the wall that encircles a little round garden (called the Coronal) at Athelhampton, designed by Mr. Inigo Thomas. Its parapet dips in a series of half rounds, and the rising




FIG. 140.—THE CORONAL: ROUND-WALLED GARDEN AT ATHELHAMPTON.





FIG. 14I.—SERPENTINE WALL AT HEVENINGHAM HALL.

parts between are crowned with stone obelisks, round which climbing roses have wound their tender way. It is an admirable device for the treatment of a small space, and could be carried out in a simpler fashion in brick without undue

expenditure (Fig. 140).

Among the less usual forms of brick walls a high place must be given to those on a serpentine plan, and for several reasons. If built only about five feet high, they can be constructed a single brick thick. This is not safe with a straight wall of the same height, which should be two bricks thick. The extra length of single brickwork occasioned by the wavy plan only means an addition of about one-quarter to the cubic measurement. This means that a ribbon wall stretching a hundred feet would involve only five-eighths to three-quarters the cost of a straight wall covering the same distance. There are, moreover, cultural advantages. The concave faces on the south side of a serpentine wall serve in some sort as sun-traps, and are therefore kindly

to wall fruit. The example at Heveningham Hall (Fig. 141) is nearly ten feet high, and is therefore more than a single brick thick, but even tall walls can be built more cheaply serpentine fashion than straight. In laying out a flower border under such a wall it would be well to emphasise the unusual line by waving the outline of the border. The obvious method is a simple reversal of the wavy line.






FIG. 143.—AND A BETTER OUTLINE.

as shown in Fig. 142, but that gives a rather weak effect, and it is better to rely on a more geometrical setting-out, as indicated in Fig. 143. As such a flower border would work out very wide at the points where the convex curve is opposed to the concave recessing of the wall, the wise method with all wide borders under walls—viz., of providing a narrow path between wall and bed—is all the more valuable. This treatment is indicated in both plans. Eighteen inches is a sufficient width for such a path.

It is difficult to establish the date when serpentine walls first came into vogue, but it is unlikely that it was before the middle of the eighteenth century. Miss Phillimore, in her *Life of Wren*, when writing of Wroxall Abbey, Warwickshire, which was bought by the great architect in his old age, says, "Sir Christopher is said to have designed the kitchen garden wall, which is built in semi-circles." This wall (Fig. 146A) is not serpentine, but set out in half-circles with straight stretches connecting them: the idea is, however, the same. A device of this kind is just one of the things with which the inventiveness of Wren is likely to have played. As, however,



FIG. 144.—WALL WITH SQUARE BREAKS.



FIG. 145.—CONCRETE WALLS AT LAMBAY.



FIG. 146.—WALL MASKING KITCHEN QUARTERS.

1789 is on a stone of the wall, his authorship must be doubted. The writer of this has seen a serpentine wall at a Suffolk house of late in the eighteenth century. A good modern example, a brick single thick, designed by Mr. F. W. Troup, is illustrated in Small Country Houses of To-day. Built with the same purpose as serpentine wall, i.e., to give somewhat sheltered bays for fruit, is the straight wall with square breaks at a Buckinghamshire house designed by Mr. P. Morley Horder. It is the better, both practically and in appearance, for its tiled ridge. In districts where both stone and brick are more costly than concrete, the latter material is useful for garden walls. In Fig. 145 is illustrated a concrete wall of very good appearance, designed by Mr. Lutyens for the gardens of Lambay Castle. The terminal posts are given almost a Doric character by the marks left by the wood boxing set up temporarily, into which the half-liquid

concrete was poured. An admirable crown is given to the wall by dark grey Dutch pantiles. The building of garden walls to mask kitchen courts and other spaces, which are necessarily untidy at times, belongs rather to the design of the house than of the garden, but one example is illustrated in Fig. 146 because of its intrinsically garden treatment. A stout trellis is set penthouse-fashion from the ridged screen wall (in the foreground of the picture) to the wall of the house, and offers hospitality to such creepers as are light enough not to interfere too much with the usefulness of the windows beneath.



FIG. 146A.—WALL AT WROXALL ABBEY WITH SEMI-CIRCULAR BAYS.

CHAPTER XI.—CLIMBING AND OTHER PLANTS ON WALLS AND HOUSES.

Misuse of Ivy—Of Ampelopsis—Of Wistaria—Various Climbers—Shrubs Trained to Walls.

THE appearance of many a house is made or marred by the wise or injudicious use of climbing plants. A house of no special character may become a thing of beauty; one of architectural value may have that whole value obliterated and the structure greatly damaged. In the latter case the danger is so great and negligence so frequent that it will be well to offer some words of warning. Many a

fine old gateway of carefullybrickwork designed wrought stone has been allowed to become smothered with ivy. Ivy is of the nature of a true hard-wooded tree. When the mortar has fallen out of the joints of old masonry, these open joints are just the places seized upon by the fast-growing ivy shoots. The shoot, at first a bare eighth of an inch thick, quickly swells, hardening as it grows. Soon it fills the joint, and, ever increasing, acts as a wedge with irresistible power, and eventually forces the stones apart. Ancient buildings and ruins that are of historical and archæological interest are the easiest and most usual prey of the devastating ivy, but many fine old houses throughout the land are even now suffering from its dangerous overgrowth. In some cases, from the pictorial point of view, the need for abolishing the ivy is something of a misfortune, especially in the case of old ruins; but its removal is a necessity if the evil is not to be aggravated. In the case of a new bare wall where the joints are sound, and level with the face of the



FIG. 147.—OVERGROWTH OF IVY ON SCULPTURED GATEWAY.



FIG. 148.—OVERGROWTH OF IVY ON GATE-PIER AND GARDEN-HOUSE.



FIG. 149.—OVERGROWTH OF IVY ON GATE-PIER AND WALL.



FIG. 150.—STONE GATEWAY MODERATELY CLOTHED.

brickwork, there is no danger, and the ivy is even protective, the leaves throwing off the wet. But the plant is quick to detect and occupy any opening, when danger

and damage may quickly follow.

The fine and boldly-treated brick piers to wrought-iron gates shewn in Figs. 148 and 140 have been smothered with ivy, and not the piers only, but also the rather important point where the pier rises from the wall. This is specially deplorable in the picture from the outside of one of the entrances to the walled garden, with the

flight of uncommon circular brick steps (Fig. 149). It may be noted incidentally that this illustration shows another defect very common in gardens where there is no critical eve ever on the watch for such The level of the blemishes. path has shrunk away several inches, leaving the under-course of brickwork exposed, and making the whole step inconveniently high as well as entirely out of proportion. In the case of the inner view, where one of the brick piers is, happily, free, the summer-house with arched doorway is also over-smothered with ivy (Fig. 148). We believe that the overgrowth of ivy on this fine example of gateway treatment has been removed, but are glad that the piers were photographed in their overdone state as a useful warning. The beautiful eighteenth century gateway shewn in Fig. 147, photographed in 1903, but now, we hope, cleared, shows ivy obliterating architrave and entablature of an ornate design. There is no harm in the slight encroachment of a leaf or two of the flanking magnolias; nobility




FIG. 151.-WISTARIA MISPLACED.

of form in foliage is a desirable accompaniment to good architecture, but it should

only be allowed to accompany, not to oppress-still less to overwhelm.

It is not the fault of the ivy, a precious and beautiful climbing plant—it is the misuse of ivy and the neglect of due control that we desire to emphasise. Ivy was largely used in decorative schemes by the French in the eighteenth century and later, and to this day is cleverly employed as screening walls of greenery on railings and treillage. It deserves to be much more used as a screen plant, and if a large unbroken surface should appear monotonous, the want of variety can be remedied by training over it a tracery of some other climber, such as Clematis Flammula or Virginia creeper. Another stone gateway (Fig. 150) is reasonably clothed with rose and vine foliage; but their growth is already quite enough—a little more and it would be overdone. The popular and, in its place, valuable Ampelopsis Veitchii has much to answer



FIG. 152.—RAMBLING ROSES, VINE AND IVY ON ROUGH BUILDINGS.

for. It has perceptibly harmed the fine brickwork of some of the old Tudor buildings at Hampton Court not only smothering the architecture but actually damaging the surface. The plant clings by little roundish suckers: in time these become dry and as hard as wire. When the harmful growth was at last recognised on some of the portions of the palace built by Cardinal Wolsey, and it was cleared away, the dry suckers held so tightly that they could not be dislodged without bringing away some of the face of the brick.

In the case of the wistaria forming an outer curtain to a pointed-arched window one may easily guess how such an odd misuse of a fine plant may have occurred

(Fig. 151). It is evident that it was forbidden to drive supporting nails or staples into the joints of the stonework, and that the only apparent alternative was to fasten the plant to the iron bars of the window itself. The still simpler alternative was overlooked, namely, that of refraining from the use of a plant requiring nailing on a wall where it could not be nailed. The same picture shows an error only too common

in gardens—that of having a bed of small plants in immediate connection with important masonry. The wistaria, with its probable ultimate fate, is the more to be regretted because the plant itself is in fine, young vigour, having got over the earlier stage of standing still for the first few years, as is the way of its kind. This fine plant may

be used in many ways—on garden and house walls, on pergolas and arbours. The newer Japanese kind (W. multijuga) is as easily grown as the older W. Chinensis, but although the racemes of flower are much longer, it is hardly a more attractive plant than the better-known kind.

Besides the walls where climbing plants are grown for their own beauty there are places in nearly every garden where it is desirable to clothe some rough building or to cover or screen something unsightly (Fig. 152). For this the rougher of the rambling roses and the wilder of the clematises are invaluable. The native C. Vitalba covers very large spaces, and grows fast. Clematis montana is eager




FIG. 153.—CLEMATIS MONTANA.

to rush up to a considerable height and then to tumble over with sheets of graceful foliage and cataracts of pure white bloom (Fig. 153). Clematis Flammula rambles widely among other growths, flowering in September; it is followed closely by C. paniculata in October. Space only allows of the barest mention of other good climbing plants—clematis species such as the yellow-bloomed C. graveolens; in

choicest gardening the splendid varieties of the Japanese *C. patens* and the Chinese *C. lanuginosa*, and the many pretty hybrids of *C. viticella*. Then we have *Bignonia radicans* with its ash-like leaves and trumpet flowers of orange and scarlet; *Solanum crispum* and *S. jasminoides*. Grape vines of the Chasselas class form perhaps the most beautiful of all wall covering, especially for sheltered, quiet places where bright flowers are not absolutely needed; but among vines, where colour is wanted, there is the crimson-foliaged claret vine and *Vitis Coignetiæ*, brilliant-hued in autumn. Roses one can but barely touch upon except

Then there are the numbers of shrubs, which, though not of a climbing habit, are thoroughly satisfactory when trained to walls. Figs for important foliage; Pyrus japonica and the winter-sweet (Chimonanthus) for winter bloom; Abutilon vitifolium, of extreme beauty and strangely little planted; ceanothus of several kinds; Buddleia variabilis Veitchii, choisya, the brittle Robinia hispida, with flower-clusters something like wistaria, but of a charming pink colour. Then for cold exposures the common guelder rose makes a capital wall plant, and is well accompanied by Clematis montana running through it, flowering at the same time, and adding to the pretty picture of copious white bloom. Another happy mixture for a cool wall is the handsome shrubby spiræa, S. lindleyana, with its cream-coloured bloom and fine pinnate leaves. Clematis Flammula trained through this forms another desirable combination. Laurustinus, not only the common but also the black, and the later-blooming L. lucidus are all excellent for training to cool walls.




FIG. 154.—AMPELOPSIS VEITCHII RESTRICTED IN GROWTH SO THAT THE WHOLE WALL FACE IS NOT COVERED.


CHAPTER XII.—RETAINING WALLS AND THEIR PLANTING.

Hillside Sites—Turf Banks—Dry Walling—Grouping in Planted Dry Walls in Sun and Shade—Construction—Importance of Ramming—Steps.

ANY gardens that are on hillsides are of necessity arranged in a succession of terraces needing retaining walls to support each succeeding level. In the case of gardens made fifty years ago, before better influences prevailed, the difficulty was got over by making turf banks. But it is very rarely that a turf bank is a desirable feature in a garden; more often it is distinctly ugly, or, at the best, quite uninteresting, while it is always difficult to mow and burns badly if on a southern slope. Where such a turf bank remains, it would, in nearly every case, be better to convert it into a wall; the line of the wall being taken at halfway down the slope and carried to the lower level, the earth excavated at the bottom filling up above. When this is done space is gained both above and below, while the wall itself becomes precious gardening ground; for if built as a "dry wall," that is to say, with earth joints instead of mortar, the joints, and the chinks in the case of uneven stones, are the happiest possible places for the growing of nearly all alpines, or if the wall



FIG. 155.—THIN SLATE STONES LAID LEVEL.



SNAPDRAGONS, LONDON PRIDE AND OTHER SAXIFRAGES, WITH TUFTED PANSIES AT THE FOOT. FIG. 156.—BRICK DRY WALLING, PLANTED WITH PANSIES,

is of some size and height, for a number of our best garden plants. Then the fact of the plants being raised some feet above the ground brings them into the most convenient range of sight. Some lovely little alpines at easy eye-level can be much more comfortably and leisurely examined than in the ordinary rock garden; all their little beauties of form, colour and scent can be enjoyed and appreciated to the full. Many of them grow naturally in rocky clefts, hanging down in sheets of loveliness, so that the wall shows, in a better way than any other kind of gardening, the real habit and character of the plant—its own method of growing, enjoying life and

In the case of such planted walls it is best to have no flower-border at the foot, but to have a border above, occupying, in the case of a converted grass bank, what would represent the upper half of the bank. It is well to fill it with a good proportion of things of bushy habit, such as bush roses, Scotch briars, lavender, rosemary, olearias, phlomis and so on. In this way the border forms a protecting parapet, while the whole wall-face is free for use. It also allows of combining the upper planting with that of the wall in a way that always proves satisfactory; some of the plants of the top being also placed in the upper joints. But in a garden where there are many planted walls monotony of treatment is avoided by having in some part rambling roses at the top to tumble over, with a thinner growth of tea roses at the foot, and but little

planted in the wall-joints.

As in arranging flower-borders, it is well to place the plants in groups of a fair quantity of one thing at a time; and, in the case of small plants, such as thrift or London Pride, to put them fairly close together. If they are spaced apart at even distances they look like buttons; but even when this has been done, either inadvertently or by an unpractised hand, it is easily remedied by adding a few plants to make the group hang together. Though it is advised that there should be no border at the foot of a planted dry wall, yet it looks well to have its junction with the grass or gravel broken here and there by some plant that enjoys such a place, as, for example, Iris stylosa or Plumbago larpentæ in a sunny aspect, or hardy ferns and Welsh poppy and small pansies in a shady one. It is well also to make careful combinations of colour, for they not only give the prettiest pictures, but also that restful feeling of some one idea completely presented that is so desirable, so easy to accomplish, and yet so rarely seen in gardens. As an example, on a sunny wall there may be a colour-scheme of grey with purple of various shades, white and pale pink, composed of dwarf lavender, nepeta, aubrietia, cerastium, Helianthemums of the kinds that have grey leaves and white and pale pink bloom, rock pinks, stachys, the dwarf artemisias and Achillea umbellata, and in the border above, yuccas, lavender, rosemary, the larger euphorbias, China roses, phlomis and santolina with white and pink snapdragons. Phlomis and santolina both have yellow flowers, but a slight break of yellow would harm the effect but little during their time of bloom, while both are of year-long value for their good grey foliage; moreover, it is easy to remove the santolina bloom, which comes on shoots that are quite separate from the foliage. If it were quite a high wall, larger plants could be used, especially in the upper half. Yuccas are grand coming out of rocky chinks high up, and gypsophila in great clouds, and centranthus (the red valerian) in big bushy masses.

On a shady wall there would be a preponderance of good greenery of hardy ferns, male fern and hart's-tongue, with the smaller ferns, woodsia, cheilanthes, adiantum and allosorus, with Welsh poppies, corydalis, mimulus and the smaller alpine bell-flowers, such as the lovely little Campanula pusilla, both blue and white, and the rather larger carpatica and eriocarpa. Then if the shady wall was of good

size there would be columbines in quantity, white foxgloves and mulleins growing

with splendid vigour and enjoying the cool root-run among the stones.

The way the walls are put up is of the utmost importance, for on the way it is done depends not only the appearance but the stability. Dry walling made rightly may be carried up twelve feet or more, even in recently disturbed soil, while if wrongly or negligently done a wall only three feet high will come down with the first heavy storm of rain. The following description will help those who wish to build their own walls, and to an intelligent amateur there is hardly a department of garden work that is more interesting and even delightful, especially where there is good local stone. Where there is no stone a dry wall can be built of brick, but this is duller work and is best done by a trained bricklayer. In some cases, in brick retaining walls a brick or half-brick is left out to give more space for inserting plants, or the whole is built in mortar, leaving such spaces only for planting; but the earth joint throughout is rather more satisfactory, giving more freedom for the shaping of the groups.

The wall should lie back a little—"batter back" is the technical word, derived, no doubt, as are so many of our words for tools and building, from the French. It



FIG. 157.—A TEN-FOOT WALL PLANTED WITH GYPSOPHILA, VALERIAN, SANTOLINA, ROCK PINKS AND CERASTIUM, LUPINES AND ROSEMARY AT TOP.

suggests a near relationship to abattre, to beat down or beat back. As a good general rule it may batter back in the proportion of one foot in six of height. Every stone, lying on its natural bed at right angles to the sloped-back face, has the back a little lower than the front. It follows that every drop of rain that falls on the face of the wall runs into the next joint, to the benefit of the plants. If a dry wall is built on solid ground it needs but little foundation. Two thin courses under ground will be enough. The tilting back of the stones is begun under ground, then the upper courses follow naturally. A bed of earth is laid between each course and the ends of the stones, as if it was mortar. As the work comes out of the ground, and, indeed, from the very beginning, the loose soil is rammed in behind and between all the stones that project backward. It is upon firm and quite conscientious ramming that the stability of the wall depends. Labourers are apt to scamp it; even experienced builders and foremen, unless they have had special experience in dry walling, do not give it the unremitting attention that it requires. This tight ramming cannot be too strongly insisted on or the absolute need of it too often repeated. Ram as tightly




FIG. 158.—BRICK DRY WALLING PLANTED WITH RAMBLING ROSES ABOVE AND TEA ROSES BELOW.




FIG. 159 -- COLOUR SCHEME IN DRY WALL OF PURPLISH-GREY BRICK. CERASTIUM, WHITE AND LILAC TUFTED PANSY AT FOOT; CHINA ROSES ABOVE.




FIG. 160.—PALE PINK ROSE, VALERIAN, CERASTIUM AND ROCK PINK IN A ROUGH STONE WALL.

as possible and on every part of the back of the walling. If the whole thing is in "made ground" it must all be rammed, but the part just behind the stones is the vulnerable point. If the ramming is neglected or is insufficient the wall will either come down in heavy rain or will bulge at various points in a manner that

is very unsightly.

It is always best to lay the stones level as to right and left and on their natural bed, that is, the same way up as they lay in the quarry; they both look better and stand better. They can be either sorted into those approximately the thickness for separate courses, or the thinner stones laid to come level with the thicker. All "random" walling is ugly and unrestful, giving the impression of a wilful violation of simple laws of structure. When there are pieces of small broken stone to be disposed of, they can be rammed in with the earth at the back of the wall, making quite sure that no cavities are left. The roots of the wall plants



FIG. 161.—WHITE FOXGLOVE IN DRY WALLING OF LARGE STONES.

like nothing better than to cling to the cool and always moist stone surfaces. A dry wall cannot be built against a scarp of hard sand or chalk. Enough must be taken out at the back to allow for fresh filling and ramming. Builders often think they can build against a solid scarp, but the experiment always results in disaster.



FIG. 162.—BRICK WALL WITH SPACES LEFT FOR PLANTS.





FIG. 163.—STEPS WITH FRONT EDGES ONLY OF STONE.



The steps that accompany dry walling

surface.

can be made in a very simple way, if it is desired to save the expense, both of stone and labour, of paving the whole surface. The front edge only need be stone. shown in Figs. 163 and 165;




FIG. 165.—STEP WITH FRONT EDGES ONLY OF STONE.

If the scarp is of actual rock there is no need for the wall except in cases where the strata tip down forward, when plants could not be comfortably grown. But in such a case it would be better to have some of the wilder clematis or roses planted at the top to wreathe and trail over the rocky

SECTION

FIG. 166.—DRY WALL (SECTION) SHOWING PLANTING OF TOP AND FACE.





FIG. 164. -- DRY WALLING (SECTION). TIGHTLY RAMMED EARTH SHOWN BY VERTICAL HATCHING.



ELEVATION

FIG. 167.—ELEVATION OF PLANTED WALL, SHOWING GROUPING.

the stones chosen or trimmed so that they have fairly good front edges and so that they come together at the joints for at least a part of their depth. To give better cohesion at the back a triangular piece can easily be fitted, as shown in Fig. 163. The joints are then cemented, the cement joint being kept down low and as much out of sight as possible. Then the whole thing will hold together and little mosses will grow in the upper parts of the joints. On the sides and even towards the earthy back of the step tiny things like the smaller stonecrops and the smallest bell-flowers can be grown. Other near plants will also seed over the space, and in a few years the problem will be how to repress rather than encourage the quantity of plants that are only too willing to invade the steps. The wider and shallower the steps the pleasanter they are to go up and down—the extreme of comfort being a step from four to five inches high and twenty-two to twenty-four inches from front to back; such steps as one may run up and down.

The planting of the joints of pavements gives scope for much judicious work, but needs great care and restraint. There should be no inconvenient invasion of plants. The idea of such planting has so greatly attracted garden enthusiasts that in many cases it has been carried too far. It should be remembered that the first purpose of a paved space is to provide a dry, level place for easy progression. If nearly every joint is filled with plants, those who pass along will either be obliged to keep their eyes on the ground or they will frequently feel, with a pang of regret, that some pretty thing has either been trodden under foot or inadvertently kicked against and dislodged. It is better to keep all the middle space free, or to attempt to do so, for small plants like these joints so well that they are apt both to run and seed

freely within their welcome shelter.

CHAPTER XIII.—YEW AND OTHER HEDGES.

Yew Hedges in Ancient Gardens—In Modern Use—Other Trees for Hedges—Box—Holly—Privet—Laurel—Beech—Hornbeam—Thorough Planting—Topiary Work.

WHEN the great English houses were built that no longer needed to be fortresses; when their windows might safely look abroad into the open country instead of giving on to an inner court; then also the pleasure garden, which had hitherto been necessarily restricted, was greatly enlarged and its many possibilities were developed. Whether it was that the tradition of the old need of walled protection was still in every man's mind, or whether the wonderful sense of fitness that characterised the work of our Tudor and Jacobean ancestors was the impelling agency we know not, but it is clear that they at once adopted the system of surrounding and subdividing their gardens with hedges of living greenery. They rightly chose the



FIG. 168.—LAWN ENCLOSED BY ANCIENT TRIMMED YEWS.




FIG. 169.—CLEEVE PRIOR: THE TWELVE APOSTLES.

English yew as the tree that should conform to their will as green walls and ornaments in their gardens of formal design. Some actual examples remain, while traces of the use of green yew, clipped and regulated, as important portions of the garden plan, are so frequent as to point to its general use. In some cases of remaining examples the original design is distorted or entirely lost, and yet a mysterious and strangely attractive charm remains; while in others some kind of symmetry has been maintained (Fig. 168). There are examples of noble use from old times in gardens of quite moderate size. The ancient yews at Cleeve Prior (Fig. 169), known as the Twelve Apostles, stand in six stately pairs flanking the paved walk to a modest manor house. At a little more than halfway of their height each pair stretches out branches to the next, forming a connecting arch, so that a framed garden scene, five times repeated, is visible from right and left. Hedges of yew with turf alone have an




FIG. 170.—AN ANCIENT BOWLING GREEN.

extraordinary quality of repose—of inspiring a sentiment of refreshing contentment. One thinks, with abounding satisfaction of many an ancient bowling green, with its bright, short turf underfoot, its deep green sides of yew, or yew and quiet wall, and nothing more but the sky above and perhaps some masses of encompassing trees (Figs. 170 and 171). Compared with the yew no tree is so patient of coercion, so protective in its close growth, or so effective as a background to the bright bloom of parterre or flower-border (Fig. 172). Its docility to shaping into wall, niche, arch and column is so complete and convenient that it comes first among growing things as a means of expression in that domain of design that lies between architecture and gardening. Our architects and garden designers are well aware of its value. A drawing by Mr. Mallows (Fig. 173) shows, next below a raised terrace, two square garden courts, the terrace steps between them descending to a long green

walk, with flower-borders backed by yew hedges, leading to a circular fountain court paved and brick-walled. The perspective and plan of a garden by Mr. Inigo Triggs (Figs. 174 and 175) show the same need and good use of yew hedges for enclosing and protecting rectangular gardens. At Bulwick (Fig. 176) some old yews are clipped only where their lateral advance threatens the closing of a green path. Yew hedges have much use besides for securing privacy. Fig. 177 shows a young hedge that will be allowed to grow some feet higher to screen the offices and their possibly unsightly adjuncts from the pleasure garden. Such hedges are usually carried up to a height of from six to seven feet. For finishing the top the best-looking and most practical form is that of a very low-pitched roof; this also presents the most easily accessible shape for clipping.



FIG. 171.—A QUIET BOWLING GREEN.

Though yew is undoubtedly the best tree for garden hedges, it is by no means the only one. Where the soil contains lime, or, in fact, in any good loam, the green tree box makes a fine hedge and clips well. But it is slow to grow—slower than yew—and both are costly. Ilex can be trained and clipped into tall hedges; there are fine examples at the remarkably beautiful and successful Italian gardens at Brockenhurst. Green holly is also a fine hedge plant, but wants more width if it is to be carried up any height. For a quicker hedge at less cost there is the Lawson cypress, growing fast and clipping well. The humbler privet we all know; it is quite cheap and soon grows into a neat hedge. We are so well used to seeing it bearing green leaves all the year that we forget that it is really deciduous. When it grows wild as a small twiggy tree it is leafless in winter. It is the trimming that induces



FIG. 172.—YEW HEDGE AS A BACKGROUND TO FLOWERS.




FIG. 173.—YEW HEDGES IN A DESIGN BY MR. MALLOWS.




FIG. 174.—YEW-HEDGED GARDEN BY MR. INIGO TRIGGS: PERSPECTIVE.

growth the fresh and leafing at an unusual Quite a pictorial season. effect is often seen of welltrimmed privet forming a sheltering entrance arch over a cottage door. Hedges of common laurel are so easily grown and so often misused that unthinkingly one has come to hold them cheap in estimation and to undervalue their real merit; but a laurel hedge twelve feet high is a splendid thing; the size of leaf telling well in proportion to the height. It must be cut by hand; never mutilated with shears, which would cut across the leaves. A tall hedge of bay is also a most satisfying sight, for the leaf itself and the whole growth are of a beauty and dignity that are




FIG. 175.—PLAN OF ABOVE.




FIG. 176.—YEWS AT BULWICK




FIG. 177.—YEW HEDGE SCREENING OFFICES FROM GARDEN.




FIG. 178.—HEDGE OF PORTUGAL LAUREL BACKING A POOL GARDEN.




FIG. 179.—HEDGE CUT INTO LITTLE GABLES.

quite unequalled. This also must be cut by hand and the surface allowed a little freedom. Fig. 178 shows a hedge of Portugal laurel backing a lily pool in a good piece of rectangular gardening, and Fig. 180 a clever way of using pollarded and clipped limes for greatly heightening a garden wall abutting on a road.

For commoner purposes, such as a hedge to a kitchen garden, beech and hornbeam are both excellent. They serve also, especially hornbeam, for training over

FIG. 180.—POLLARDED LIMES USED TO HEIGHTEN A WALL.

arbours and covered ways; growing close and twiggy when regularly clipped.

All such green hedges must be well planted, the ground deeply dug and liberally enriched and, if possible, further encouraged during the next few years by additions of manure just under the surface. They cannot be hurried. Nothing is more frequent or more fatal than compliance with the wish of the impatient client who desires to have an effect at once. It can only be successfully done by special and unusual means and at great cost. For yew and holly, three feet is the limit of height for prudent planting. Beech can be planted four feet to five feet high at once; hornbeam, privet and whitethorn should be cut down to within a few inches of the ground

the year after they are established, when they soon throw up a number of strong shoots.

Besides the green things used as actual hedges, fine effects are gained by the use of upright trees bounding grassy walks. Fig. 182 shows Lombardy poplars so used by Mr. Reginald Blomfield. Irish yews, the upright cypresses and their near relations, the junipers, can be so employed. Of the junipers, the neat




FIG. 181.—TOPIARY WORK AT MATHERN: TEN YEARS' GROWTH.

The corner yews trimmed as birds were about five feet high when planted, but entirely untrained and uncut.

The hedge yews were two feet six inches high and cost about three pounds a hundred.

Chinese and the much larger Virginian—commonly called red cedar—are the best. Topiary work, to which the yew is so submissive, is receiving attention in modern gardens. As in the case of other toy-like tricks in gardening, it may in some cases be satisfactorily employed, but if followed merely as a fashion, and not because the design of the garden would be bettered by a certain form, it may easily give an impression of silliness or wanton frivolity. But fine effects are sometimes gained, where there is need for distinct punctuation, by carrying up a square plinth some six inches or eight inches above the level of the top of the hedge and growing a well-formed ball upon that. Fig. 181 shows yew hedges at Mathern with the trees, at important points, trained up in the form of swollen cones surmounted by bird forms. In unpractised hands such treatment might be dangerous, but in that of Mathern's owner we know that his skill and fine taste will bring them into right and fitting garden ornaments.



FIG. 182.—A GARDEN AVENUE OF LOMBARDY POPLARS.

CHAPTER XIV.-WATER IN THE FORMAL GARDEN.

"The Soul of Gardens"—Reflections—Pools and their Water-levels—Varied Shapes— Lily Ponds and their Depth—Separate Pool Gardens—Water Parterres—Fountains and their Sculpture—Leadwork—Well-heads—Pumps.

FOUNTAINS and waters are the soul of gardens; they make their chief ornament and enliven and revive them. How often it is that a garden, beautiful though it be, will seem sad and dreary and lacking in one of its most gracious features, if it has no water." So wrote Pierre Husson in La Theorie et la Pratique du Jardinage in 1711, and set down a truth that is coming into its own again. This chapter is called "Water in the Formal Garden" because it is concerned with water as a factor in design, rather than as the element which makes possible all the enchanting growths proper to the water garden in its technical meaning. Husson, who published his book in Holland, had all the French devotion to rather theatrical uses of water. He extols "eaux jaillissantes, celles qui s'élevent en l'air au milieu des bassins, forment des jets, des gerbes, des bouillons d'eaux." Appropriate as such features are in great gardens, water needs to be employed very simply in small ones. Little pools and rills and fountains, with their waters not too vigorously "jaillissantes," need to be disposed with a sparing hand.

Although the gardens at Hurtwood, Surrey, are of large extent when taken together, the great variation in levels necessitated their division into several gardens, some quite small, which are complete in themselves, and therefore useful to illustrate our argument. Even in the great fan garden, the features at the radial point from



FIG. 183.—FAN-SHAPED LILY POOL AT HURTWOOD.







FIG. 184.—HURTWOOD: RELATION OF STEPS AND POOL.



which it starts, *i.e.*, the fanshaped pool and paved work, give suggestions for the treatment of quite small gardens. The result of the delightful design made by Mr. Christopher Turnor for Major - General Sartorius, V.C., appears in Figs. 183 and 184. The chief pool is fan-shaped, and thus leaves between the water and



FIG. 187.—HURTWOOD: LOOKING DOWN ON FOUNTAIN.

the open parapet a half-round space which gives hospitality to flowers. The paving is well managed. The stones which edge the water are of regular shape, while the rest of the space has random flagging. Near by is another pool, which, by throwing out a curved edge to meet the chief flight of steps, marks a




FIG. 186.—AT GREAT BADDOW: REFLECTIONS.




FIG. 188.—PARAPETTED POOL AT BLYTHBURGH.




FIG. 189.—POOL IN PAVED COURT.




FIG. 190.—AT MORTON HOUSE, HATFIELD.

happy relationship in design between itself and the stairways from the higher ground. No less ingenious is the treatment of the garden on the west side of the house (Figs. 185 and 187, and for plan see Fig. 98). Water here also takes a prominent place. A round basin is set on a square base built of tiles with a stone coping. From the basin rises a fountain with its figure spouting freshness. On each side of this central feature is an oblong lily pool, and the whole design is bound together by a broad frame of paving.

Simple pools, with the water brought up nearly to the ground-level, give a pleasant variety to a paved court when it is enclosed by the wings of a house built on




FIG. 191.—SHAPED POOL AT ATHELHAMPTON.

an H plan. This is well shown in a design by Mr. C. E. Mallows (Fig. 189). His drawing suggests what is one of the chief charms of pools, however small. Since Narcissus first espied his face in a fountain, wise designers of gardens have been mindful of the beauty of reflections. Whether it be a window, as in Mr. Mallows' drawing, or vase, yew and dovecote, as in the parapetted pool at Blythburgh in the garden of Mr. Seymour Lucas, R.A., or the little boy's figure and the garden-house at The Vineyards, Great Baddow (see Figs. 186 and 188),




FIG. 192.—AT WOOTTON LODGE, STAFFORDSHIRE.




FIG. 193.—SMALL POOL AND NICHE AT ATHELHAMPTON.

there is a changeful beauty in the dim outlines and fleeting colours of reflected things that no other element in garden design can give. In order to ensure these effects it is important that the water should be kept at its proper level, which is as high as is possible. The nearer it is to the kerb of the pool, the wider and more beautiful will be the reflections. Nothing looks more dreary



FIG. 194.—IN A PETERSFIELD GARDEN.







FIG. 195.—AT ISLAND, STEEP.



than a tank of three or four feet in depth with only a few inches of water in the bottom, the more so as its walls are apt to be slimy. When water is scarce in rainless seasons this may be unavoidable, but there is little excuse for a permanently low level, which is



excuse for a permanently low SCALE OFFIG. 198.—A SIMPLE SHAPE.






FIG. 200 .-- WITH JET AND CASCADE.





FIG. 199.—WITH RAISED INLET.

OF 111 1 1 1 1 1 1

usually the result of placing the inlet and outlet too low in the wall of the pool. At Morton House, Hatfield, Mr. A. Winter Rose has set in a paved court a round pool which groups pleasantly with the loggia and a statue in its niche (Fig. 190). The shapes which garden pools can take are almost endless in their possible variety, but it is usually well to be satisfied with simple forms. The illustrations of this chapter show rectangles in various proportions, which are generally dictated by the paved court or grass plat in which they are set. Two types of oblongs with curved ends are illustrated, from the gardens of Wootton Lodge, Staffordshire, and







FIG. 203.—POOL AND FOUNTAIN DESIGN BY MR. H. INIGO TRIGGS.

Athelhampton Hall, Dorset. Of the two the former (Fig. 192) has a slightly more broken outline, and is given an increased architectural emphasis by the moulding of the raised kerb. The latter (Fig. 191) is as simply made as can be, save that a rounded moulding overhangs the side of the pool a little. It should be noted that the axial line of this feature cuts through the middle of the gate to the walled garden in which it is, and the full effect of water treatment in helping an interesting vista is thus secured.

Another little pool, fan-shaped, in the same garden is illustrated in Fig. 193 to show how well it groups with the niche in the wall above it. The possible



combinations of pools with other features are well-nigh endless, and it is not possible to show more than a few typical examples. A very attractive treatment is shown in Fig. 194, where the drop in level from one terrace to another is made the occasion for an amusing little stepped bridge of masonry. This was designed by Mr. W. F. Unsworth and Mr. Inigo Triggs for a garden at Petersfield, and very successful it is. To the same architects is due the manipulation of simple elements in a garden at Island, Steep (Fig. 195). A double flight of steps leads down from a long upper terrace to a lower one, which juts out over the hillside with a semi-circular bastion-like front. The curve of the stairs determined the outline of one end of the pool, and the similar




FIG.205. —CROSS AND LONGITUDINAL SECTIONS THROUGH LILY POND, MILLFIELD.



FIG. 206.—LILY POND AT MILLFIELD, BRENTWOOD.





FIG. 207.—SMALL POOLS INTERSPERSED IN PAVING.


shape of the other end marches with the plan of the lower terrace. The chief purpose of this pool, as of most of its kind, was to find a home for water-lilies. Surrounding the basin, and less than a foot below the normal water-level, is a shelf about fifteen inches wide, on which may be set pans or baskets containing lily plants. There are varieties which, on account of their intrinsic value, or for the purpose of ensuring better growth, it is desirable to place in this way. It may be added that some of the more robust water-lilies will grow in from six to ten feet of water, but such a shelf as is now described need never be more than two feet below the ordinary level,



FIG. 208.—SUNK POOL GARDEN AT MARSH COURT.


and is more convenient if only about six inches below. A practical point worth remembering in the construction of such pools is the risk they bring to those gardens that are made the more gracious by the presence of little children. If they are built with broad, shallow steps which drop by gentle degrees towards the middle of the pool, an over-venturesome child is not likely to come to very serious harm. The gradually receding levels of the stone or brick, moreover, add to the appearance of the pool, when the water is clear enough to reveal its floor. In Figs. 196 to 202 are shown seven pool shapes drawn by Mr. J. Maxwell Scott from sketch designs by







Mr. Inigo Triggs. Four are simple outlines, and one of them is devised to leave suitable spaces for the placing of pots of shrubs. Fig. 196 provides a quartette of connected pools grouped round a baluster sundial. Another is furnished with a jet and a little stepped cascade. The example shown in Fig. 199 is designed to come at the end of a path, and has a little raised basin from which the water spouts into the pool.

Although very simple forms are the safest for pools, there is room for an occasional burst of gaiety in outline, especially when the rest of the garden plan is of necessity treated in a severe fashion. The brick-edged pool shown by plan and perspective in Figs. 203 and 204 was designed by Mr. Inigo Triggs, and is reminiscent of the wealth of fancy that enlivens the gardens of the East. The jets are very happily placed; they would make a garden so







adorned a little Paradise of freshness, and musical with the tinkle of falling spray. In Figs. 205 and 206 are illustrated by sectional drawings and photograph an attractive stepped lily pond at Millfield, Brentwood, designed by Mr. A. Winter Rose. The parapetted walls add considerably to its The interspersing of many little pools tied together by a coherent geometrical design in a long stretch of paving is another treatment of water which is of large interest, as is shown by Fig. 207. There is a suggestion of patches of enamel set in ivory.

Water takes its highest place in garden architecture when it determines the complete design of an enclosed space, such as the pool garden at Marsh Court, devised by Mr. Lutyens, and illustrated in Figs. 208 and 209. No scheme contrived within so small a compass could exceed in richness of effect this combination of steps, paving, pool and balustrade. A note of gaiety is added by the lead hippocampi, to the modelling of which reference is made later (see Fig. 221). In the same manner, but on a smaller scale, is the delightful pool at Papillon Hall (Fig. 210), where




FIG. 213.—WALLED POOL WITH ANGLE FOUNTAINS, SHEWING MOORISH INFLUENCE.

the contrast between the curves of the descending steps and the lines of the margin of the pool is altogether successful.

Another scheme of design, eminently suited to gardens of limited area, is the water parterre, such as is shown by plan and perspective by Mr. Inigo Triggs (Figs. 211 and 212). The design, made by the same hand, for a walled pool and fountains, reproduced in Fig. 213, is unusual and interesting. The water is carried to shaped basins on the top of brick piers at the four corners, whence it falls into tanks built in the corners of the dwarf walls. From here it circulates round a tiny canal and ultimately finds its way to the lowest pool. This treatment is intended for a flat site, so that the level of the topmost kerb




FIG. 214.—EXTENDED POOL AT CHELWOOD VETCHERY.

would be the same as the surrounding garden. The plan and section explain the design in detail, the total space occupied being only a square seventeen feet six inches each way. It should be added that tall fountains of this type can only be worked in connection with a supply cistern placed at a higher level than the basins. The whole idea is based on some of the delightful little patio gardens in Southern Spain, and nowhere can better lessons be learnt of the use of water in small gardens.

The shaped pool at Chelwood Vetchery, designed by Mr. Rome Guthrie (Fig. 214), is part of a large and imposing scheme of garden design; but it is instructive as showing an idea equally applicable on a smaller scale. The pool is placed below the retaining



FIG. 215.—TILE-BUILT FOUNTAIN BY MR. LUTYENS.

wall of the terrace (the curved projections of which are also worthy of attention), and the sense of length is emphasised by the extension of the pool as a narrow canal. This is an interesting variation of the canal or rill treatment, which is also shown

in the Berkshire garden (Fig. 21) and at

Little Boarhunt (Fig. 67).

The design of standing fountains is generally the outcome of combining two elements—a basin and some sculptured fancy that discharges the water. The various types of pools illustrated in this chapter are capable of being supplemented by little spouting figures, such as are illustrated in Chapter XIX., which is concerned with statues. The Boy and Dolphin shown there would look well, for example, in a pool like that of Fig. 191. Smaller conceits, however, take an attractive place on tanks of limited size. In Fig. 217 is shown the section of a simple round basin, for which Lady Chance modelled a very attractive tortoise, cast in lead (Fig. 218), and some toads. Other examples of fountain sculpture by the same



FIG 216.—LION MASK FOR FOUNTAIN.

skilful hand are the hippocampus of Fig. 221 and the lion mask of Fig. 216. The latter is for a wall fountain discharging into a bowl built up in tilework




FIG. 217.—SECTION OF BASIN WITH LEAD TORTOISES ON RIM.

(Fig. 215), designed by Mr. Lutyens. The hippocampus is a delightful beast, spouting from his muzzle, and was used in a group of four disposed symmetrically on the




FIG. 218.—LEAD TORTOISE BY LADY CHANCE.

outer margin of the outer margin of the rectangular tank at Marsh Court (Figs. 208 and 209). In all these examples the sculptor has shown her felicitous sense of the right treatment of animal forms. She has shown, for example, not an exact representation of a tortoise, but an interpretation of one,



FIG. 219.—LEAD DOLPHIN.



FIG. 220.—GARGOYLE FOR GARDEN WALL.

bringing to her work that just quality of convention which makes it art instead of naturalistic imitation. Another pleasant lead spout for a garden fountain is the



FIG. 221.—HIPPOCAMPUS IN LEAD.

dolphin modelled by Mr. Cashmore, and illustrated in Fig. 219. The gargoyle designed by Mr. Voysey, and built up in sheet lead, serves a rather different purpose (Fig. 220). It is fixed to the front of a big brick retaining wall at Littleholme, Guildford (see also Fig. 102), and has a delightfully grotesque quality that is suggestive of the mediæval craftsman. Its purpose is to throw clear of the wall the surface water drained from the terrace above.

A combination of pool with wall fountain which is singularly attractive is to be seen at Hampton Court (Fig. 223). The entwined dolphins spouting freshness into a big shell owe no little to their intrinsic charm as sculpture, and modern replicas would, no doubt, be of greater cost than the owners of most small gardens could encompass, but their placing with reference to the twin pools below is very happy and Though the atmosphere of suggestive. gardens does not demand that their ornaments shall be great sculpture, it occasionally happens that a master hand models a figure that finds its way into a garden setting. The slender fountain at Wych Cross Place, illustrated in Fig. 222, is a case in point, for it is the work of that great but erratic sculptor, Alfred Gilbert. bronze stem was modelled for some altogether different purpose. Upon it has been set a simple old Dutch bowl of stone, and to crown the composition, the exquisite statuette by Gilbert of a Dancing Boy, stung by a fly and holding a tragic mask in his hand. It is very successful, and the figure has that enchanting vitality which makes it reasonable to call Gilbert the English Carpeaux. It is characteristic of the casual, fragmentary career of this great artist that the bronze stem should have lain unheeded in a dealer's shop until the owner of Wych Cross Place found for it a use so admirable.

Among modern fountains made wholly of lead a high place must be given to the composition shown in Fig. 224. It consists of an octagonal tank, decorated in flat relief with grapes and vine leaves, combined with a tall fountain, in which its designer and maker, Mr. George P. Bankart, has gone for inspiration to a late mediæval example in the South Kensington Museum. The treatment of the metal is exactly right; the modelling is softly done, and the corona at the top of the fountain is in openwork of lace-like effect to which lead lends itself so well. Simpler and smaller tanks than this are very helpful in the water equipment of any garden. Eighteenth century tanks, such as that illustrated in Fig. 229, are




FIG. 222.-BY ALFRED GILBERT.




FIG. 223.—WALL FOUNTAIN AT HAMPTON COURT.



FIG. 224.—LEAD TANK AND FOUNTAIN.

not difficult to acquire. The areas of old London houses continually disgorge examples with panelled fronts that bear dates and initials and little classical devices of all kinds. The modern craftsman, however, should not be forgotten in the ruling passion for "antiques." Two examples by Mr. Bankart are illustrated in Figs. 225 and 226. One of them, with its stout swag of fruit and flowers, has a definite garden character, and the other has delicate ornament in slight relief which suits well the nature of the material. When cisterns like these for convenience in watering, the garden are remembered.

watering the garden are remembered, the needs of the birds must not be



FIG. 225.—LEAD CISTERN.



FIG. 226.—BY MR. GEORGE BANKART.



FIG. 227.—CHALICE BIRD BATH.

forgotten. Fig. 228 shows a shallow bird bath made of lead, and Fig. 227 a chalice-shaped vessel of terracotta, both admirable in their different fashions.

There are few small gardens that can boast a stream or an old moat, but either is a welcome feature, for it gives opportunity for a bridge. Illustrations elsewhere in this book (e.g., Figs. 21 and 194),



FIG. 228.—SHALLOW BIRD BATH OF LEAD.

show how effectively bridges can be contrived in connection with pools, and the problem of a little stream is not greatly different in kind. In the little garden at Kelsale Manor, Saxmundham, there is an old and narrow moat, over which Mr. A. Winter Rose has thrown a little oak bridge, which is shown in Fig. 230. Over a continuation of this moat is a small stone bridge by a curved stairway (Fig. 231). It forms a connecting link between the lawn and the parkland beyond.

Most of the pools illustrated in this chapter are designed on definitely formal lines, and it is only rarely that naturalistic treatment produces satisfactory results.

When, however, a cottage has been set on a rough hillside and the heather reaches to the door, a conscious garden scheme may be undesirable or even impossible. Such is the case at Stoneywell Cottage in Charnwood Forest (Fig. 232), where the margin of the bathing-pool has been made to follow the natural contour of the ground. Mr. Ernest Gimson has shown a just




FIG. 229.—A GOOD XVIII. CENTURY TANK.



FIG. 230.—A LITTLE WOODEN BRIDGE.

appreciation of the character of the site by making the pool accord in its rough simplicity with the attractive, roughly-built cottage which it serves, and with the pump-house, which also appears in the picture.

On the subject of well-heads a note of warning may be sounded. Where an actual well exists it is very desirable that its head should be made an



FIG. 231.—AT KELSALE MANOR.



FIG. 232.—BATHING POOL AT STONEYWELL COTTAGE.

attractive thing. The modern example illustrated in Fig. 234 has a simple stone wall and coping with a wrought-iron " overthrow" of neat design. Most people, however, who are set on possessing a wellhead look for an old one. There seems no end to the stream of them, old or "antique," which does not necessarily mean the same thing in these days of skilful reproduction. They come, or are said to come, from Italian courtyards and gardens, some complete with the old arching that iron

holds the pail-hook and supports a pulley. Heads which are carved of grey and other dark-hued stones are more suitable for English gardens than those of white marble, which are apt to look harsh and staring. Many of them are adorned with the arms of families represented now in Italy by nothing but the memory of their names



FIG. 234.—A MODERN WELL-HEAD.

and the bravely-carved heraldic achievements on a well-head. One of the two old examples in Istrian stone illustrated in Figs. 233 and 235 once belonged to the Marcello family, now extinct. The other is ornamented with simple and appropriate representations of a water vessel. Such



FIG. 233.—OF ISTRIAN STONE.



FIG. 235.—ITALIAN WELL-HEAD WITH "OVERTHROW."

memorials of a grandiose world which has not survived the clash of modern life may be well enough in a great English garden. For the smaller schemes of design, for which we are now considering the appropriate type of ornament, they are less fitted than a well-head built of brick or stone. It is, however, in their placing that most care is needed. The example at Sutton Courtenay (Fig. 238) stands well on its broad spread of paving, but very often one is seen set down on a grass plat without any suitable base, and looking lonely and useless. There is no reason why a well-head should not be used as a dipping-well or fitted with a jet and used for a fountain in a pool. Such a use renews its connection with water, but to employ it as a flower-pot is an indiscretion. Not to employ it at all, but to regard it merely as an ornament, seems justified only when it has marked merits as a piece of sculpture. The fact remains that Italian well-heads are appropriate in Italy and sometimes look awkward in an English garden, especially when they are not used in connection with a well, which rarely exists in a place where decorative emphasis is possible or desirable.



FIG. 237.—LEAD PUMP-HEAD.



FIG. 236.—A WOODEN PUMP CASING.

Figures 236, 237 and 239 are concerned with the more typical English water engine, the pump. In the eighteenth century pump - heads were commonly made of lead and

decorated with little lion masks, rosettes and dates. Fig. 237 shows a good example, but placed as it is it lacks meaning and looks uncomfortable. difficult but possible to adjust such a pump-head to the mechanism of a modern pump, and that method seems the only reasonable one to adopt. An interesting alternative is suggested by the foreign pump casing of wood (Fig. 236), panelled and carved, now preserved in the South Kensington Museum. The iron handle is delightfully wrought, and the general effect suggests that here is a field for decorative effort. There are many gardens which rely for their watering on roof water, bath wastes, etc., carefully gathered and conducted to an underground cistern which needs to be pumped for garden use. In such a case it is good to have an attractive rather than a merely utilitarian pump. This wood-cased example may therefore be helpful in suggesting a covering treatment for the modern pump of commerce.

It sometimes happens that the well is close to the house, and occupies a prominent place in the garden. In such a case it is good to make a virtue of a necessity and use the well as an opportunity for an interesting architectural feature. In Fig. 239 is shown a well and pump-house at Pitsford, which Mr. Morley Horder has treated attractively. The roof space serves as a pigeon-cote.

It is hoped that this chapter may give a stimulus to the use of water in the formal garden. Its employment as a decorative element fell into great neglect during the Victorian period, and is even now imperfectly understood. It is true that it took an important place in some of the big gardens which owed their design to such men



FIG. 238.—AT SUTTON COURTENAY.

as Sir Joseph Paxton, but it was not very wisely employed. As early as 1821 Paxton made a large lake at Battlesden Park, where he was employed as gardener, and he was responsible for the great fountains at Chatsworth. The work of his school, however, showed no sound appreciation of the possibilities of water. The lessons of Versailles and Hampton Court had been wasted as far as the nineteenth century was concerned. Especially was this the case in the use of water as an element in the design of small gardens. The qualities that make for successful treatment of limited spaces are the same in principle as in the case of big areas; the differences are only in detail.

We need not be so dogmatic as Bernard Palissy, the great French potter of the sixteenth century, who wrote: "It is impossible to have a spot proper for a garden unless there be some fountain or stream passing through it." Nevertheless, our illustrations show how great an aid water brings to the designer of gardens, and with water companies spreading their mains far into country districts, much can be done without the ideal means of a natural stream.



FIG. 239.—PUMP-HOUSE AT PITSFORD.

CHAPTER XV.—METHODS OF PAVING.

Rectangular Jointing—Random Jointing—Local Methods—Pitched Paving—Paving of Shingle—of Brick and Tile.

In some portions of the garden, and especially near the house, some kind of paving is sure to be wanted. Where a suitable local stone exists, it is, of course, the best thing that can be used, although the style of the house may be a determining influence in the choice of the material. Thus, a house of eighteenth century character or a garden of formal design seems to demand a pavement of squared flags of York or Portland stone (Fig. 243), while a house of the cottage class may be content with random-jointed stone, or even with a few rough-edged flat slabs laid like stepping-stones through grass and flowers, to give a dry footway to a modest entrance (Fig. 242). Stones of the Yorkshire class, and also those related to slate, present smooth surfaces

by natural cleavage, and are the most suitable for using as rectangular flags—there is something distasteful about laying them with "random" joints. It is sometimes done, but always has a displeasing appearance, whereas such treatment is unobjectionable in the rougher-surfaced sandstones.

Some of the most interesting methods of paving are those that are peculiar to a district—that grow directly out of the employment of some local product that has stimulated inventive use from past ages. There are a few square miles in West Surrey where the hard sandstone called Bargate stone is quarried. A quite different kind of stone, largely composed of iron, also occurs in small pieces close to the ground-level. Many of these, weather-washed for ages, are of a form that presents one or two sides or ends with a flat surface. A typical stone would be three to four inches




FIG. 240.—A SUMMER-HOUSE PAVING OF IRONSTONE AND BARGATE STONE.



FIG. 241.—PAVING SIMPLY TREATED WITH STONES OF NATURAL SHAPE.



FIG. 242.—ROUGH-EDGED SLABS.

in length, an inch wide and three inches deep. For hundreds of years they have been used by the country people, set on edge, as a "pitched" paving, often with a deeper kerb of the hard sandstone. Whole inn-yards may be found of such pavement. Sometimes they were set in patterns and are so used now, with guiding lines of the yellowish sandstone and a filling of the purplish black ironstone. Fig. 240 shows such a




FIG. 243.—PAVEMENT OF RECTANGULAR FLAGS OF PORTLAND STONE.



FIG. 244.—STONE PAVING WITH "RANDOM" JOINTS.






FIG. 246.—PAVING JOINTED TO FOLLOW THE TERRACE PLAN.






FIG. 248.—PAVEMENT OF RECTANGULAR FLAGS IN A ROSE GARDEN BY MR. GILBERT FRASER AND MR. T. H. MAWSON.




FIG. 249.—AN OLD SUSSEX CHURCH PAVING OF BRICK.



FIG. 250.—PAVEMENT RATHER OVER-PLANTED IN THE MIDDLE.

pavement as the floor of a summer-house.

In the case of places near the sea, pretty pavings can be made by collecting stones of different colours from among banks of shingle. There is hardly a shingle beach that does not contain stones that are nearly black and nearly white, and others with several shades of buff and brown, only waiting for the invention and ingenuity that will work them into patterned pavements.

When it is not convenient or desirable to use stone there is the alternative of brick and tile, materials which also offer a wide field for thoughtful and clever treatment. The circular paving round the sundial (Fig. 245) shows how ordinary paving bricks may be laid, without any shaping of the bricks, in a way that is extremely simple and yet full of dignity. A radiating pavement of tile and brick can also be made of roofing tile on edge forming the rays with a herring-bone filling of brick. A pavement under




FIG. 251.—BRICK AND TILE PAVING.

FIG. 252.—BRICK AND TILE PAVING.

the pergola at Marsh Court (Fig. 263) of large stone flags, with filling of brick, is simple and stately. In more than one old church in Sussex there is a paving of red brick set in a pattern that suggests interwoven ribbons (Fig. 249). The small dark squares were specially prepared by bricks of the usual size, having the surface deeply channelled in the mould so as to form eight divisions. These bricks were then "flare-burnt," the surface acquiring a purple colour and half vitrified quality, while the deep scoring made them easy to cut into the small squares. Paving bricks are also moulded to special patterns, as with one end diamond-pointed for the fitting of four ends together, as in Fig. 254, the square inter-spaces being filled with nine-inch tiles. Fig. 253 shows an example of a tracery of sections of half-round tile connected with small pieces of roofing tile, with filling of another material, and Figs. 251 and 252 illustrate various ways of using pieces of roofing tile and brick on edge with paving tiles of square and octagonal form.




FIG. 253.—BRICK AND TILE PAVING.

FIG. 254.—BRICK AND TILE PAVING.

Any person of inventive capacity and some skill in handicraft can make delightful pavements with tesseræ of pieces of broken roofing tiles. The tesseræ are prepared by cutting the pieces of tile into small cubes of approximately the same size with a cold chisel and hammer; they are then set to the pattern desired in mortar or cement on a concrete bed prepared beforehand, and brought up to a suitable level.

CHAPTER XVI.—THE PERGOLA.

Italian Pergolas—English, of Oak—Of Larch Poles—With Stone, Brick and Tile Piers— Proportions—Garlands on Chains—Suitable Plants—Covered Alleys—Treillage.

HEN one considers how commonly some kind of pergola is used in Italy, it would seem a matter for wonder that it has taken so long to reach us in England, for twenty years ago it had hardly been thought of. But now it is a familiar garden feature, and, translating its original use as a convenient means of growing vines and ripening grapes into our English way of having it for the display of beautiful climbing plants, as well as for its comfort as a shady way in summer, its development for our needs has of late years been surprisingly rapid. In fact, so popular has it become that there is scarcely an example of modern garden

design in which it does not find a place. It is true that it is often injudiciously placed. There are many gardens that have not had the benefit of experienced advice, where a poorly - constructed pergola stands in some open place where it has no obvious beginning or end; whereas it should always lead from one definite point to another; one at least being some kind of full-stop, either of summer-house or arbour, or, at any rate, something of definite value in the garden design.

As to construction, we follow in the main the Italian prototypes. In many cases the pergola is a mere framework of poles (as shown in Fig. 255), replaced from year to year, either wholly or in part as the need arises, or it has posts of solid masonry. These are commonly built of rubble, thickly covered with that lime plaster of coarse texture that is so well used by Italian masons. These columns are sometimes square, but more often round in



FIG. 255.—A PERGOLA OF POLES IN VENICE.



FIG. 256.—PIERS OF RUBBLE, PLASTERED, AT AMALFI.

section (Fig. 256). In some cases even, marble pillars from some ruined ancient building are brought into use—always with a satisfying effect of solidity and

permanence.

When in our British gardens there can be no question of such solid treatment and only rough wood is available, the posts of the pergola are best made of oak trunks of anything from eight inches to ten inches diameter. Their lifetime can be lengthened by stripping the bark off the butts for a length of three feet and coating the stripped part with gas-tar. Charring in the fire is even better, but is less convenient to do in the case of heavy posts. It is important that the tarring or charring should be carried to a height of quite a foot clear of the ground, the danger-spot being at the ground-line and just above it. The oak posts being set up, a rather slighter log, adzed at the ends on what is to be the under side (so as to lie flat and steady), is spiked to each pair of posts across the path, any slight curvature of the




FIG. 257.—LARCH PERGOLA OF TOO SLIGHT A CONSTRUCTION.

log being taken advantage of to show some degree of upward camber. Nothing looks weaker or less satisfactory than a cross-beam that swags downwards, as it does naturally when of weak stuff, or if not adzed at the ends to give a firm seat. This weak effect shows in the larch pergola illustrated in Fig. 257, which is altogether too slight in construction. Pergolas of this class often show such cross-beams of weak, drooping form, and stiff, straight braces cut out of the larch tops. The braces are better when shaped as in the picture of the pergola with a paved path and fir trees at the end (Fig. 258), where they are cut out of branches that have a little upward curve.

The example built of larch poles supporting gourds is cleverly done, the braces of alternate posts taking a wide angle, and, after passing and being spiked to the beam, joining at a ridge point; the wider angle helps to give more rigidity to a

flimsy structure and the prolongation affords more spacious support to the shoots of the gourds (Fig. 259). Often a house and garden are occupied on a short tenancy, such as three years; in this case such a pergola of short lifetime would form a delightful feature.

When it is possible to build with solid piers, we see how thoroughly our architects



FIG. 258.—OF LARCH POLES WITH WELL-SHAPED BRACES.

and garden designers have assimilated the pergola idea, and the many and various ways in which they are working it out and adapting it for combination with other structures. In the example at St. Clere, Kemsing (Fig. 260), designed by Mr. Godfrey Pinkerton, it covers a wide flagged terrace adjoining one side of the racquet court. The piers are built of large, flat paving tiles resting on a stone step, and have stone caps and bases. They carry a heavy, continuous beam: lesser beams, with one end resting on this, have their other ends treated putlog and built fashion into the house wall. A singularly satisfactory pergola by Mr. Inigo Triggs (Fig. 261) is built of ordinary brick with wide mortar joint, on short plinths of rough local stone, with steps of the same. Oak timbers

from an old building form the roof. Chains hang from post to post for the future training of roses as garlands. In a very beautiful open pergola at Marsh Court, designed by Mr. Lutyens (Fig. 263), the piers are built of tiles with wide joints; they have stone plinths and moulded stone caps, the section being square and concave square alternately. This fine example also shows the value of the solid,

slightly cambered beam. In some cases a good effect is gained by building the piers round and square alternately (Fig. 264). It is not difficult to have bricks specially moulded for building in the circular form. Home Place, Norfolk (Fig. 265), a clever use is made of cobble stones by Mr. E. S. Prior, where four round cobble piers are set four-square on a circular platform raised on two steps, which forms the centre of wide. flagged, radiating paths. A good effect is gained, and might be more often obtained in build-



FIG. 259.—GOURDS ON LARCH FRAMEWORK.

ing generally, by not filling up the putlog holes. A fruit-room at Chelwood Vetchery, five sides of an octagon in plan, is happily treated by Mr. Rome




FIG. 260.—A WELL-BUILT PERGOLA ADJOINING RACQUET COURT AT ST. CLERE.




FIG. 261.—PIERS OF BRICK AND STONE.



FIG. 262. A PERGOLA WITH PIERS, SOME ROUND, SOME SQUARE.

Guthrie, with a surrounding pergola following the same plan (Fig. 266). The piers are circular in section, of a light-coloured brick, and stand upon a flagged platform.

The whole is planted with vines, the most beautiful of all pergola plants.

Brick piers at the ends, with wooden ones between, and a roofing of trellis over a brick pavement, form a pergola at Sandhouse, Sandhills, Witley (Fig. 267), from the design of Mr. F. W. Troup. This pergola is unusually high in proportion to its width. It is in general more agreeable to let the width across the path be greater than the height, as in the example by Mr. Walter Cave at Ewelme Down, where some specimens of topiary work in tubs are placed at the ends of paths (Fig. 268).






FIG. 263.—PIERS OF TILES, WIDE-JOINTED.

A pergola of open structure by Mr. J. P. White at Garston Park gives partial shelter to a garden door. Under it is a wide, flagged terrace, slightly sloping away from the house to throw off rain, the joints near the planted piers being left open for the benefit of the climbers. Against the house is an interesting reproduction of the old-fashioned perspective treillage (Fig. 269).

For a general guide as to dimensions, it may be taken that the piers may be anything from seven feet two inches to eight feet out of the ground, eight feet to nine feet apart across the paths, and nine feet to twelve feet apart in the length of








FIG. 265.—A MEETING-PLACE OF RADIATING PATHS.



FIG. 266.—A PERGOLA SURROUNDING A FRUIT-ROOM.

the path. It is often a convenience, especially in the case of wooden posts, to have the roofing of flat iron arches; but in this case it is well to fasten some kind of wooden rods or slight trellis to the iron, the contact with cold iron in winter tending to check and damage some plants. When chains hang from post to post to form garlands, it is also well to wind a tarred cord rather closely round the chain, so that the shoots rest on the cord and not on the chain. But a better way is to have two chains spread apart about six inches with rigid iron ties, for the training to this is more

FIG. 267.—AT SANDHOUSE.

under control. All gardeners who have had to do with rose garlands know the trouble of the whole thing swinging round to the under side, like a saddle

turning on a horse.

In some large gardens iron pergolas have been adapted for the growing of pears and apples trained as cordons (Figs. 270 and 271). They are formed of successive arches, all in one piece, of thick iron rod, with wires fastened longitudinally. They form a pleasant as well as interesting shady path, and, as the trees are necessarily pruned to short spurs, the quantity of bloom is a wonderful sight in proportion to the space.

As a general rule, the pergola is most satisfactory when on level ground, and when it is straight from end to end; but it is sometimes convenient for it to follow flights of steps and landings leading from one level to another. Such a case has been cleverly treated at Acremead in Kent (Figs. 272 and 273), to the design of Mr. Dunbar Smith and Mr. Cecil Brewer, where it goes straight downhill, with solid square piers of local stone. Easy flights of steps and landings give access

to paths at right angles. As to the best plants for pergolas, there is nothing more delightful than grape vines, or for other good foliage aristolochia and Virginia creeper. Where flowering plants are desired, there are wistaria, clematis, and preferably the kinds near the species such as montana, Flammula and Vitalba, white jasmine, Japan honeysuckle, Dutch honeysuckle (both of the early and late kinds), Bignonia radicans and climbing roses. But roses on pergolas need great care in regulating by pruning and training, their inclination being to run up to the top,



FIG. 268.—AT EWELME DOWN.



FIG. 269.—A PERGOLA SHELTERING A GARDEN DOOR.




FIG. 270.—A PERGOLA OF CORDON FRUIT TREES.



FIG. 271.—OUTER VIEW OF THE FRUIT PERGOLA.

so that unless the pergola is on a lower terrace and is seen from above, the beauty of the mass of bloom is lost. There are also a number of shrubs and small trees that can be adapted for pergola use, one of the best being laburnum. At West Dean in Sussex there is a complete tunnel of laburnum with an ivy arch at the two ends (Fig. 275). Among other shrubs that can be trained to the same use are

guelder roses, Pyrus Malus floribunda, snowy mespilus, laurustinus, common laurel, Solanum crispum and Robinia hispida.

The pleached allevs of our Tudor ancestors have much in common with pergola. Columns, arches and whole galleries of shady verdure, trained on a foundation of wooden treillage, are described by Bacon. They were commonly planted with hornbeam or wych elm. Treillage was also used to a large extent in French gardens in the eighteenth century, but it is only now that it is being revived in England. In Fig. 274 is shown an example by Mr. J. P. White with walls, arbours and rose temples.

There is still earlier record of something of the pergola kind in England, for in




FIG. 272.—AT ACREMEAD: PLAN AND SECTION





FIG. 273. - STEPPED PERGOLA AT ACREMEAD.



William Horman's "Vulgaria," published in 1519, nearly a century earlier than the works of Bacon, these passages occur: "Aleys in gardens covered with Vynes and railed up with wythe stakis vaute wyse do great pleasure with the shadowe in parchynge heat." And further: "A vyne clevynge to his railes with his twyndynge stringis and lette hangynge down his clusters of grapis maketh a plesaunt walkynge aley."




FIG. 275.—A GREEN TUNNEL OF LABURNUM.

CHAPTER XVII.—GATES AND GATEWAYS.

Entrance Stairways—Gates to Forecourts—Carriage Gates—Notes on Eighteenth Century Smiths—Gateways and Vistas—In Walled Gardens—Wooden Gates.

BOTH before and since Robinson Crusoe "made up the Entrance, which till now I had left open," the treatment of the way into house and garden has been fruitful of varied opportunity. Crusoe was concerned for the safety of his house and gear, and had an eye to those same needs of defence that find such delightful architectural expression in moat and bridge, gatehouse and portcullis. The small house and garden, however, raise no such military problems, and the possibilities are limited to the treatment of archways in high walls, gates that break the line of low walls and sometimes the provision of steps. In Fig. 276 is shown an



FIG. 276.---GATE AND MOUNTING BLOCK AT CLEEVE PRIOR.




FIG. 277.—AT BIDDESTONE MANOR.

attractive pair of wooden gates approached by two curved steps. Beyond them a mounting block witnesses to the days before petrol had all but supplanted horsemanship. The entrance to Biddestone Manor (Fig. 277) shows the good effect of a simple and well-designed pair of stone piers and a longer flight of steps. The battery of Time and lichen have left their tender marks on this typical Cotswold ashlar-When the house is close to a frequented road it ensures a larger privacy if the wall is carried high and the doorway made in an arched opening, as in the example designed by Mr. Walter Brierley, and shown in Fig. 279. A sense of security s given by filling the tympanum of the




FIG. 279.—ENTRANCE FROM ROAD TO SMALL GARDEN.



FIG. 278.—GATEWAY TO A COURTYARD.

arch with wrought-iron work, and the gate is the easier to open from not being the full width of the opening. A similar treatment is shown in Fig. 278, where an iron gate gives entrance to a paved courtyard.

The steady increase in the use of motor-cars by people of moderate means tends to make a carriage entrance necessary for houses of quite modest size. Many are content with the provision of a simple field gate; but when something more ambitious is contemplated, the design of the gates themselves and of

the adjoining walls is a serious factor in the artistic success of the house and its approach. The disposition of the entrance to a Berkshire house designed by Mr. W. J. Parker is somewhat ambitious in scale, but its plan shows a treatment appropriate to small houses if carried out on smaller lines. From the brick piers at the ends of the boundary walls the line of the wall curves inwards to the piers of the carriage gates (Fig. 280). In these curved wings on



FIG. 280.—TREATMENT OF WALL AND GATES.

either side of the main carriage gates (Fig. 281) are set two foot-gates and two round grilles (Figs. 282 and 283), all of which gave pleasant opportunity for the art of the modern smith. The wise choice of iron gates of good design has considerable bearing on the successful appearance of an entrance. So many eighteenth century houses in towns are now being demolished that old gates can often be acquired at reasonable prices, and the chance of finding one is worth enquiry and some little trouble; but caution is necessary. Old gates are not worth buying unless they are in a satisfactory condition, because repairs to them are apt to cost almost as much as new gates. Moreover, it is a mistake to be led into buying a gate, however pleasant its




FIG. 281.—THE CARRIAGE GATES.

design, if it is not of the right size and proportion for the opening that needs to be filled. The writer of this bears in mind an unhappy friend. Ten years ago he bought a gate and stretch of railing of admirable design and in good repair, in the hope that it would "fit in somewhere," but he has never contrived a place for it. The methods of the "bargain sale" do not apply conveniently to architecture. It may be helpful, however, to set down notes on some typical work of the old smiths, in order to show the sort of work which is good and pleasant, whether it be old or new. Fig. 285 shows a delightful gate of the size suitable for the entrance of a small country house. It is fixed in a wall between two gardens, and never served as a carriage gate, for there is insufficient head-room under the "overthrow," but in character of treatment it is very instructive. It was made in 1720,

and is traditionally believed to be the work of the Brothers Roberts. The character of the work supports the tradition. The year 1719 is the earliest that can be associated with the independent

FIG. 282.—GRILLE IN SCREENWALL.




FIG. 283.—FOOT-GATE.

can be associated with the independent activities of the Roberts, for they then did the very elaborate gates at Chirk Castle. They do not seem to have worked much outside Shropshire, Cheshire and Wales.




FIG. 284.—VISTA BETWEEN TWO GATES IN WALLED GARDEN.

Leeswood, near Mold, Emral, Eaton Hall and Shrewsbury were among the places that boasted notable examples from their smithy. The design of the gate illustrated in Fig. 285 is the best guide to its attribution. No one could have made it in 1720 who had

not fallen under the spell of Tijou or at least of his book of designs. The horizontal lines are heavily emphasised and the embossed shells at the top of the side panels are unusually prominent. The "overthrow" of the gate is very marked by the range of embossed acanthus leaves (derived apparently from Tijou's gadroon and acanthus border) which connect the two stout horizontals supporting the pyramid of scrollwork, etc. A rather unusual feature is the trio of oval rings at the base of each side panel. The embossed leaves are well executed, though without the natural swirl that characterises them in Tijou's work and connects them organically with the iron tendrils to which they are fixed. For all that, their placing in the design is very happily managed, and could not have been

done by a smith who knew nothing of Tijou's pioneer work. The execution is very good, and the repairs which Mr. C. G. Hare has lately superintended fortunately did not need to be extensive. No doubt the succeeding owners of the gate have been careful to keep the ironwork painted. Without such attention the slight substance of the embossed work would long since have rusted away. Modern craftsmen doing similar leafwork commonly use sheet copper or sheet bronze, which defies the weather and can be blacked as easily as sheet iron.

The history of English wrought-iron gates can hardly be said to have begun until the advent of Jean Tijou in 1689. Further particulars of the career of this great artist are given in a chapter (by Mr. J. Starkie Gardner) in The House and




FIG. 285.—GARDEN GATE MADE BY THE BROTHERS ROBERTS.

Tijou's influence was not, howits Equipment. Without him English smiths ever, universal. would probably have continued to make strong gates and railings of straightforward design, with little fancy; but it is unlikely that they would have adopted the repoussé work which is so characteristic of Tijou. His influence is clearly shown in the delightful gate at Wotton House (Fig. 287). Despite the obvious attractions of the new methods, the national liking for a large restraint in craftsmanship persisted even under the very eye of Tijou. While he was working at St. Paul's some less important commissions in the Cathedral were entrusted to Thomas Robinson, who was evidently an individualist, for he did not follow at all closely




FIG. 287.—AT WOTTON HOUSE.



FIG. 286.—AT WYCH CROSS PLACE.

in Tijou's steps. Where he used embossing it was with imperfect understanding of its possibilities. When he was free from the master's influence and began working at New College, Oxford, about 1711, he discarded the Tijou style and developed a simpler manner of his own which is markedly English. Warren and (despite his Dutch - sounding name) Buncker did work of a similar kind during the first quarter of the eighteenth century. The gates at Packwood House, Birmingham (Fig. 288), and at Norton Convers (Fig. 289), show this more restrained note in design, the latter in a marked degree.

The majority of the gates of the first half of the eighteenth



century—the golden age of the English smith—are of this simple type. Embossed work is used sparingly, and the basis of their designs is scrolled work taking the form of lyres and G's, variously combined and enriched by water-leaves. Occasionally there is a diversion into naturalesque forms, when terminals spread



FIG. 289.—AT NORTON CONYERS.

out as bunches of laurel leaves. What may be called the London type was essentially sober, though rich in treatment, and it is this type which should be followed in the entrance and garden gates of the small modern house. They should be built of stout bars. Satisfactory results cannot be got from flimsy sections, and the temptation to use light material to save cost is to be resisted. Far better a simple gate of adequate sections than one bedecked with acanthus but lacking strength.

Where there is a garden-house approached by a long walk with an opening in the wall at the end of it, as at Norton Convers (Fig. 289), it is permissible that the gate should be of less sturdy build, so that the full value of the distant picture be not lessened. Another example of this is seen in the

very light gate in a wall that divides two long paths at Wych Cross Place (Fig. 286). Considerable space has been given to historical notes on the design of iron gates because so many garden pictures are spoiled by ugly examples, but the placing of the gates is an even more important question. When Fleming wrote in 1576: "It



FIG. 290.—AT WITTERSHAM HOUSE.

was my happy chance to have entrance into a goodly gardene plotte," he unfortunately did not say what manner of gate let him in, but we may imagine it was at the end of a long alley such as the Elizabethans loved. In the planning of gardens the gates of walled enclosures can often be placed on axial lines, so that the full value of a vista may be secured. The gateways illustrated in Fig. 284 show this well.

Walled gardens are especially favourable to



FIG. 201.—AT GREAT MAYTHAM: MAIN GATE TO WALLED GARDEN.

interesting gate treatment, as may be seen in Figs. 291 and 292, which show examples at Great Maytham designed by Mr. Lutyens. The larger gate is the chief, and the smaller a subsidiary entrance to the same garden. By the same hand, but on a much smaller scale, is a little gateway in the garden of Wittersham House (Fig. 290). The outlines of the ironwork are of the simplest, but the gate has the quiet distinction which follows good design even on the smallest scale and in the humblest materials.

Although the chief place of gates will always be at the entrance to carriage-ways and in walled gardens, a long terrace sometimes gives opportunity, as at Chelwood Vetchery, the seat of Sir Stuart Samuel, Bart., M.P. Mr. Rome Guthrie has here marked a drop in terrace level by an iron gate between brick piers at the head of a flight of steps curved on plan.

In Fig. 284 is shown a good pattern of wooden garden gate, made of stout




FIG. 292.—IN THE WALLED GARDEN AT GREAT MAYTHAM.



FIG. 293.—AT CHELWOOD VETCHERY.




FIG. 294.—WOODEN DOOR WITH POSTERN.

oak bars. Though itself modern, it is of earlier type than those of wrought iron which have been described. Sometimes for the sake of greater privacy a solid wooden door is desirable, as in the attractive old Tudor example with a postern which is illustrated in Fig. 294. Always satisfactory and with the added merit of being very inexpensive are doors of simple wood trellis, such as Mr. Lutyens has

employed at Great Maytham (Fig. 295).

Not less important than the gates themselves are their posts. The Packwood House example (Fig. 288) is built in rusticated brickwork with a simple stepped top, but the eighteenth century was much addicted to ball finials, as at Norton Conyers (Fig. 289), and no better finish can be devised. For smaller gates the treatment shown in Fig. 287 is admirable; the steps in the wall make the upper part of the opening wide, and give opportunity for an overthrow of more imposing design than the width of the gate itself would allow. It is a happy compromise between a simple narrow gate and one with a pair of side panels running the full height, as at Norton Conyers (Fig. 289).

A word on the undue growth of creepers is never out of season. The wanton growth of ivy on the left gatepost in Fig. 288 shows how this noxious weed veils cornice mouldings and destroys architectural proportion and balance. In addition, there is to be remembered the deadly injury done by ivy shoots in penetrating and loosening the joints, until in an evil day it pulls down the fabric which has endured

its baleful embrace.

Stairways of all kinds are considered in their proper chapter, but reference may be made here to the curved steps, built of brick on edge, which add so greatly to the charm of the gate at Packwood House (Fig. 288).



FIG. 295.—A TRELLIS DOOR.

CHAPTER XVIII. -GARDEN-HOUSES.

The Place of Summer-houses in General Scheme—Building in Vernacular Manners— Thatched Roofs—Cob—Use of Old Materials—In Walled Gardens—Shelters and Tool-houses.

THE success of summer-houses and pavilions, considered as elements of garden design, depends as much upon their skilful placing as upon their form and materials. It may be laid down that, in cases where the pavilion is near the main house and related to it by path or pergola, it should have the same architectural treatment. By way of example we may refer to Fig. 296, which shows a design by Mr. H. Inigo Triggs. In this case the pavilion serves as a focus for the other elements of the design. It is connected with the house by a pergola, and its four windows overlook the lawn, the sunk garden, etc. It is proper, therefore, that it should be of the same half-timber construction as the house, to which it stands in a definite relation. It is an outpost where the amenities of the house and its more gentle employments can be enjoyed in a garden atmosphere. From the architectural point of view it is an added value in such a pavilion that it gives dignity and scale to the main building. This is notably the case at




FIG. 296. —A GARDEN-HOUSE DESIGNED BY MR. INIGO TRIGGS



FIG. 298.—AT HURTWOOD: GARDEN-HOUSE ABOVE LILY POOL.

Hurtwood (Fig. 298), where the simple gazebo at the corner of the terrace emphasises the height of the house behind, and serves as a pleasant resting-place whence the beauties of the outlook may be enjoyed. Its situation above the lily pool helps to mark the charms arising from the wise treatment of a site that slopes




FIG. 297.—GARDEN-HOUSE AT ATHEL-HAMPTON.

sharply. Similar advantage has been taken of a difference in level between two important sections of a garden at Athelhampton (Fig. 297), where the windows of the pavilion command both an upper lawn and a long vista of path and border on the low side of a clipped hedge. Where a forecourt or terrace

has been built up on a hillside, a corner gazebo, like that shown in Fig. 299, designed by Mr. Walter Cave, seems to buttress the terrace. while it serves as a delightful vantage-point whence the country round may be espied. The quality to be aimed at in all garden architecture is coherence in the relationship of parts. A pavilion should not stand alone, but be tied to the rest of the scheme by orderly design. Where the house is of definitely classic form, it is permissible that the summer-houses shall take on the aspect of a little temple. In Mr. Arnold Mitchell's garden at Great Baddow, illustrated in Fig. 300, the vista made by path and borders is



FIG. 300. -- AT THE END OF A LONG WALK.




FIG. 299.—GAZEBO AT CORNER OF TERRACED FORECOURT.

closed by a pleasant little classical conceit in stone. In the case of houses of no marked style, it is better for the design of pavilions to follow the vernacular traditions of simple building proper to various districts.

A garden at Liphook shows the pleasant results of rough masonry and tiles employed in two summer-houses designed by Mr. W. T. A. T. Carter (Figs. 301 and 302). One has a hexagonal roof in the corner of the wall; the other is of L plan, which marks the end of




FIG. 301.—AN ANGLE SUMMER-HOUSE NEAR LIPHOOK—




FIG 302.—AND ANOTHER OF UNUSUAL PLAN.

the wall, and has a delightful little conical roof rising at the angle. This unusual and interesting plan has the practical advantage that the occupants of the pavilion have two views, one down the path to the first summer-house, the other across the lawn. Reference must also be made to the treatment of the wall. The stepping in its parapet is emphasised by the crowning of the piers by simple ornaments of obelisk type which have quite a Jacobean flavour. But they are no more than old rick-stones, and their mushroom-shaped tops have been placed under the stalks to serve as bases. It was an ingenious thought to give these old features of the farmyard a new lease of life as garden decorations. At The Grove, Mill Hill, Mr. Stanley Hamp has designed a pleasant garden - house (Fig. 303) in brick and timber, which is the more interesting for





FIG. 304.—THATCHED HOUSE IN NORFOLK.



FIG. 303. -- AT THE GROVE, MILL HILL.

being set on the side of a sharp slope. Rising as it does from a well-grown herbaceous border, it dominates its surroundings in very agreeable fashion, and looks across a wide stretch of garden to the house, with which it accords well.

The thatched pavilion at Happisburgh, Norfolk, designed by Mr. Detmar Blow, is in a vernacular manner (Fig. 304). The house which it adjoins is also thatched. In general this roof treatment needs to be employed with discretion. Sometimes a rustic pavilion, log-built and thatched, will be placed in relation to a house



of some definite architectural period, such as Georgian, and only succeeds in creating the idea that its builder is playing at rusticity. When, however, a summer-house is placed in a remote corner of a garden and bears no definite relation to the main house, some latitude is permissible. Nothing could be more attractive than the Devonshire example illustrated in Fig. 305, where a thatched summer-house shelters in the corner of a walled garden. In this case the walls are built of "cob," i.e., of earth rammed




FIG. 307.—BUILT OF OLD MATERIALS.



FIG. 306.—AT LITTLE BOARHUNT, LIPHOOK.

in the local fashion, which has prevailed for centuries. A cob wall (or pisé, as it used to be called early in the nineteenth century) will last almost for ever, if it is built on a stout foundation of stone or brick or concrete, and if it is soundly roofed with thatch, so that the wet is kept from its sole and its head. Where the natural treatment of the adjoining wall is thatching, it is wholly fitting that the summer-house should be roofed in the same fashion. The solecism to be avoided is the importation into a part of the country, where thatch is unknown, of a ready-made thatched pavilion framed in barked logs, which are too often made garish and ridiculous by yellow varnish.

The use of old materials—of the disjecta membra of demolished buildings—is a piece of amateur antiquarianism which needs to be approached with some reserve. There are cases, however, where an old set of columns will take their places faithfully and naturally as the supports of a new-built garden-house. Such a use is illustrated in Fig. 307. It is the more appropriate because this



FIG. 309.—ROUND GARDEN-HOUSE AT LITTLE RIDGE.



FIG. 308.—OF TWO STOREYS.

delightful curved pavilion, with the tiles well "swept" in the making of its conical roof, adorns the garden of an old house in Broadway, where a ripe age gives the prevailing atmosphere. A pavilion built up of illassorted Elizabethan fragments may, however, look very uncomfortable in a garden which owes its design wholly to the eighteenth century. In the gardens of small new houses it is far safer to accept modernity as the governing factor, and to build a garden-house that frankly expresses the age to which it belongs. That is not to say that the teachings of historical design should be neglected. The garden-house at Little Boarhunt (Fig. 306) shows how satisfactory can be a pavilion which is not a copy of any particular old example, though it owes its pleasant aspect to a knowledge of what was

done by the old builders. The round pavilion, shown in Fig. 309, stands at the corner of the formal garden at Little Ridge, laid out by Mr. Detmar Blow and Mr. Fernand Billerev. and is of characteristic and interesting design. Elliptical arches rest on its stout piers, and above the cornice the roof. ogee in section, rises to a pretty ball finial. A simple and attractive round summer-house at the end of a grass walk at Wittersham is shown in Fig. 312.

A good treatment of a garden-house in the




FIG. 310.—IN CORNER OF WALLED GARDEN.

corner of a walled garden is seen at Great Maytham, designed by Mr. Lutyens (Fig. 310). Though the scale is small, the little pavilion is given an air of comely

dignity by the few steps which lead up to its door and there is a practical thought in this provision. It gives a view over the outer garden from the windows on the far side. Yet another idea for a pavilion in the corner of a walled garden is afforded




FIG. 311.—AT ST. CLERE.




FIG. 312.—AT WITTERSHAM HOUSE.

by the example designed by Mr. W. F. Unsworth and illustrated in Fig. 308. The house is of two storeys, and the upper floor is carried on stout oak posts. The undercroft serves as a store for garden implements, and the room above is reached by an outside staircase on the other side of the wall. Such a little apartment makes a

FIG. 313.—AT STAPLEFIELD GRANGE.

quiet retreat for a writer, or admirable room for a bachelor when the normal sleeping accommodation of the house has reached its elastic limit. A very important detail in the design of any gardenhouse, which is to serve as an outdoor room for reading and writing, is the window. It is not enough to rely on the light that comes through the opening of access. One window at least should be provided, and so placed that the light comes over the left shoulder of the If such a window writer. chances to face south-west or south, a light curtain over it will prevent the sunlight falling directly on book or manuscript. Attractive open summer-houses can often be contrived with little cost of building taking advantage of an existing corner formed by a garden wall. The example at St. Clere (Fig. 311), designed by Mr. Godfrey Pinkerton, gives a hint as to how such a little restingplace may be contrived. dwarf wall with two columns. side wall and pent-house roof make up an attractive place. The low front wall has an advantage over columns running to the ground-level; or it helps to temper the cold airs of spring and autumn to the occupant. An architect has his greatest opportunity when the

garden-house is an integral part of the design of a broad terrace adjoining the house, but this does not often arise in the case of small garden schemes.

In Fig. 316 is illustrated a modern terrace pavilion with a roof of ogee outline which is typically Scottish. It was designed by Sir Rowand Anderson, and groups delightfully with a house designed by William Adam, father of the famous brothers.

Fig. 316A shows an old example at Kinross House, designed by Sir William Bruce.

Another attractive little garden house is at Staplefield Grange, Sussex. the home of Mr. Percy Macquoid (Fig. 313). It dates from the time of Robert Adam, and was built as an adiunct to a late eighteenth century villa at Twickenham. When the house suffered great damage by fire



FIG. 314.—A TRELLIS GARDEN SHELTER.

not long ago, the remaining materials were sold, and Mr. Macquoid has made very apt use of the prize he secured. Although its design suggests masonry, it is, in fact, built of wood. Seen across a lily pool at the top of a steep flight of steps it gives a charming architectural flavour to a beautiful garden.




FIG. 315.—THATCHED GARDEN SHELTERS AT CHARLTON, OXON.

Though this chapter deals chiefly with garden-houses of solid construction, one picture is given of a garden shelter designed by Mr. Basil Oliver on lines which slightly recall Chippendale's trellis manner (Fig. 314), and another of two thatched shelters at Mr. F. E. Smith's cottage, designed by Mr. Alan James (Fig. 315). It is as well to bear in mind that the outlying parts of the garden devoted to its purely working hours should not be made unseemly by toolhouses roofed with





FIGS. 316 AND 316A.—TWO TYPICAL SCOTTISH GARDEN PAVILIONS.

corrugated iron. In Fig. 317 is illustrated a good building for this purpose with weather-boarded walls and tiled roof, designed by Mr. A. Winter Rose.



FIG. 317.—A SEEMLY TOOL-HOUSE.

CHAPTER XIX.—STATUES AND VASES.

Their Especial Value in Small Gardens—Scarcity of Good Models—Professor Lethaby on Leaden Figures—On Gate-piers—Cupids—Pan—The Right Placing of Ornaments.

It seems to be thought rather generally that ornaments, such as statues and fountains, find their just place only in great formal gardens like those of Wilton, Drayton, Melbourne or Wrest Park. Probably this feeling is a survival from the day when the formal garden itself was held in small esteem, or tolerated only when it helped to frame some great historic house. It may be admitted that ornaments need to be employed sparingly in small gardens, and that an undue liberality in their

use calls up visions of the mason's yard, but therein is no reason for their neglect. Another cause that has made designers of gardens, whether amateur or professional, rather chary of resorting to them is the scarcity of good models small enough to be in scale with a little garden. It is the fact that small figures which are genuinely old are rarely met with in salerooms. Many of the available examples that pose, not very plausibly, as "antiques" are copies of very poor models, and are rejected as soon as seen. Present taste has accepted the principle of formality in garden design. So far from formal treatment being suitable for great gardens only, it




FIG. 319.—BOY FIGURE IN NICHE AT END OF GRASS WALK.

seems to be peculiarly applicable to little spaces. Where a garden scheme extends over several acres a designer can afford to be severely simple in the details of his conception. A broad grass walk which runs a hundred yards between her-baceous borders



FIG. 318.—ON GATE-PIER.

of, say, fifteen feet in width is a thing so delightful in itself that its charm is self-contained. The absence of a statue framed in clipped yews to close the vista is forgotten in the beauty of the wide sweeps of turf and blossom. Variety of growth and changeful schemes of colour provide the necessary incident. A little garden, however,

if too simply treated, soon exhausts our curiosity. more the designer lacks space, the apter should he be in making us forget his garden's limitations. Ingenious pleasantries of treatment here and there arrest the interest. By concentrating it they make the visitor oblivious of the smallness of the theatre which vields so much diversion. This is not a plea for many ornaments, still less for any one that stands out markedly from its surroundings; no more is claimed than that ornament of the right kind is even more welcome in small gardens than in big. It is admittedly difficult to get anything small enough in scale that is at the same time pleasant as sculpture in its own right. are always available little reproductions in bronze of the exquisite Narcissus at Naples.



FIGS. 320 AND 321.—ON GATE-PIERS AT PAPILLON HALL.



FIG. 322.—BOY AND DOLPHIN IN POOL.

It figures in a score of gardens, and always looks well. It is, however, unreasonable always to demand of a garden figure that it should be fine as sculpture.

Professor Lethaby wrote years ago of garden figures: 'Lead is homely and ordinary and not too good to receive the graffiti of lovers' knots. red letter dates and initials." This theory must be withheld from such younger sons of the house as own pen-knives, but it shows a right attitude to such pleasant unheroic subjects as may properly find their being enshrined in lead. It is an insult to submit a finely - modelled bronze or marble figure to the changing assaults of the English climate and to the slow invasion of lichen. In a little garden the *motif* of the sporting child is always fresh. Fortunately, there are many skilful artists who have turned their hands to modelling boys, winged and wingless, busy with every sort of merry employment. A few are illustrated here, some old, some new. The youngster at Temple Dinsley (Fig. 318) who surveys us, shield in hand and rather soberly, raises a question as to the placing of statues. Nowhere do they look better or more reasonable than on the top of gate-piers. Their size seems less than when they are nearer to the eye-level, and from a practical point of view they are better than large open vases, which it may be difficult to keep supplied



FIG. 324. - MODELLED BY JAN VAN NOST.




FIG. 323.—A PIPING BOY.

with growing flowers. Best of all, they give a human welcoming quality to the forecourt over which they seem to preside. A very attractive pair is the leaden Youth and Maiden eighteenth dressed in century costume that nod and beckon to each other from neighbouring gate-piers at Papillon Hall (Figs. 320-1). They are only about four feet








FIG. 326.—AT MELBOURNE, DERBYSHIRE.

high, and of a type suitable for comparatively small, though not for very small, gardens. They will be recognised as little cousins to the well-known Watteau-like Shepherd and Shepherdess who simper at each other in the solemn atmosphere of the

South Kensington Museum.

Very serious students of art are urgent to tell us that sculpture has no right to represent violent action; but even austere critics are inclined to relax these rules in the case of amorini. There is just the right degree of movement in the chubby boy who rides a dolphin (Fig. 322) and spreads a sail to the favouring breeze. Very pretty and thoughtful is the little piper (Fig. 323) who surveys his garden world from the low pier at the end of a dwarf wall. Both these are of to-day, modelled by the craftsmen of the Bromsgrove Guild, very much in the spirit of the figures at Wilton (Fig. 324) and Melbourne, Derbyshire (Figs. 325-6). These were made in lead at the beginning of the eighteenth century by Jan Van Nost, a Dutchman who came to England after William III. became King, and helped to establish here the Dutch manner of formal gardening. The Melbourne amorini form a dramatic sequence. The chubby pair fight for the possession of a garland, mishandle each other severely, but in the fourth group (not illustrated) seal their reconciliation with a kiss. Sir George Sitwell has written that "a pleasure-ground, however small, should have its presiding genius, its Nymph of flower-garden or grove or woodland or Naiad of the well . . . to give a personal interpretation to the forces of Nature . . . for this reason sculpture in a garden is to be regarded not as an ornament, but almost

as a necessity, as like that last touch of colour in a picture which sets the whole canvas in a flame." Figures look well in wall niches, as in the garden, designed by Mr. A. Winter Rose, which appears in Fig. 319. The kneeling Boy with Dolphin, which serves as a fountain in the pool at Wych Cross Place (Fig. 329) has beauty in its own right, for it was modelled by Puech, an artist who has added no little to the beauty of Paris by his monuments. None the less, it is in the reflections it casts on the still water, and in its judicious placing by Mr. Thomas Mawson in relation to the terrace steps, that no little of its charm resides. A like fancy is the Cupid and Swan of Fig. 328, which makes an ideal ornament for a pool.

Among the many subjects with which the old designers chose to people their gardens there is none which is so steadily successful as Pan. The Romans used his bust chiefly as a *Term* set on a diminishing pedestal, and it is in this form and from a modern model that Fig. 327 shows him. Lead holds indisputably first place as the material for garden ornaments in England; but it is apt to be expensive, and cement, if rightly used and coloured, makes a satisfactory substitute. There remains terra-cotta, which can be admirable if of quiet colouring and attractive texture; but the shiny red of some clays is hard and unpleasant. Some delightful garden pottery


FIG. 328.—CUPID AND SWAN RISING FROM POOL.



of subdued reds and greys is made by the Potter's Arts Guild at Compton, Surrey, the enterprise of

Mrs. G. F. Watts. The bird bath, illustrated in another chapter, is a good example of the service ceramics can do to the garden, and there are many satisfactory bowls to be had in the same material, modelled on simple lines and sparingly decorated with swags of fruit and the like simple devices.

The right placing of statues and vases is of as much importance as their intrinsic merit. What, for example, could be pleasanter than the flower-pot on an old millstone which ends a stone-flagged path (Fig. 330). In the background is seen the always welcome figure of Gian di Bologna's Flying Mercury, who seems here to have alighted on a sea of bloom. Both vases and statues are very well employed in adorning balustrades and stairways, as in the example illustrated in Fig. 331. at Sandhouse Witley,



designed by Mr. F. W. Troup, where two leaden gods make music from vantage points afforded by the staircase piers.

Of the many types of vases that are available, it is impossible within the limits of this book to illustrate a series: but we can at least show some differing examples, each good in its own way and appropriate to various surroundings. The stately pot that is seen in Fig. 332 is one of the brilliant works ascribed to Jan Van Nost. It stands on a terrace at Hampton Court Palace, but is of moderate dimensions. It is suitable. therefore, to serve as



FIG. 330.—FLOWER-POT ON MILLSTONE AND MERCURY IN BACKGROUND.

the chief feature of a small garden of formal design, that frames a house of early eighteenth century character. Fortunately, it has been well reproduced and can be obtained. As Mr. Lethaby has written of it: "The little sitting figures (which form the handles), slight as they are, are charming in their pose; the folded arms and prettily-arranged hair give us a suggestion of life, which most of these things supposed to be in the classic taste lack." In quite another manner is the lead pot (Fig. 333) with a band of open ornament traced in bright



FIG. 331.—STATUES GUARDING STAIRWAY.

tinning, made by Mr. George P. Bankart. Two other lead tubs by the same hand are illustrated in Figs. 334 and 335. In one a hen and her chicken stand against a background of corn, and in the other the little



FIG. 332.—AT HAMPTON COURT.

panels made by a network of rope moulding are filled by the inhabitants of a Noah's Ark. All three have the character of simple and straightforward craftsmanship, which marks them as fitting for the garden of a cottage.



FIG. 333.—WITH TINNED ORNAMENT.



FIG. 334.—BY GEORGE BANKART.



FIG. 335.—FROM NOAH'S ARK.

CHAPTER XX.—SUNDIALS AND SEATS.

The Placing of Sundials—Various Simple Types—The Game of "Clocks"—Stone Seats and Their Setting—Wooden Chairs and Tables.

SUNDIALS, like other ornaments, depend more for their decorative success on their right placing than on their intrinsic merit as garden sculpture. A common fault is the lack of a suitable base. In Mr. W. Robinson's garden at Gravetye Manor there is a sundial of twisted baluster pattern designed by Sir Ernest George. It is set on a moulded square base, which rises from an octagonal platform (Fig. 336). Simple and slender as it is, it has an air of dignity by reason of being properly set. By way of contrast there is illustrated in Fig. 337 a sundial of pleasant and sturdy design, which looks lonely and neglected on a lawn, and bears no relation

to the rest of the garden. It needs a stepped base of some sort to detach it from its surroundings. No little of the value of a sundial is the opportunity it affords to emphasise the central point at the junction of converging paths, as at Ditton Place, Balcombe (Fig. 338). The octagonal base makes a pleasant break between the round of the baluster and the shallow circular step which lifts it above the paving. It was designed by Mr. Horatio Porter. The more imposing the sundial itself, the more need is there for a dignified base. Of the many examples of the lead Blackamoor that English gardens can show, none is better supported than the example illustrated in Fig. 339. The four steps are adequate for the importance of this very interesting figure, which was sold freely in the beginning of the eighteenth century by Jan Van Nost. Anyone who is interested in the history of this famous garden ornament may be referred for a full




FIG. 336.—SIMPLE SUNDIAL ON ADEQUATE BASE.

account of it to English Leadwork: Its Art and History. The next illustration (Fig. 341) shows an eighteenth century variation of the simple baluster treatment, with women's masks connected by festoons of drapery. This, again, is an example of an interesting pillar, which loses much of its possible effect by its lack of a proper base or platform and a margin of paving. At Marsh Court there is an example of to-day, designed by Mr. Lutyens, which is admirable for many reasons.

FIG. 337.—A GOOD SUNDIAL BADLY PLACED.

The octagonal stone seat from which it rises provides a dignified base, and the stone pillar, which carries the most modern and scientific form of dial, has a charming entasis. Recourse was made for its decoration to a byway of the leadworker's craft, viz., inlay. It was popular enough in the Middle Ages, but has since been neglected, save for the dreary purpose of making imperishable the lettering on tombstones. Bands of simple conventional ornament wind spirally up the column between diamonds, all of lead inlaid in matrices cut in the stone. The whole composition is interesting and unusual. Wholly of lead, except for the iron gnomon, is the sundial illustrated in Fig. 343. Made by Mr. George Bankart, it is a good example of what can be done with the most typically English metal (in the Middle Ages and later the Continent got much of its lead from us). Good use has been made of a simple device which has pleased many generations of plumbers since the Roman occupation of Britain—the rope-moulding—and the leafwork round the base is pleasantly modelled. Round the top is cast one of those

many legends about the flight of time which have exercised the ingenuity of rhymesters since sundials were first made. Another, and more delicately adjusted, kind of outdoor timepiece is illustrated in Fig. 344. Its combination of slender hoops is pretty in itself, and the column which carries it did more active garden service once. It is a stone roller retired from work in favour of the more manageable





FIG. 338.—AT DITTON PLACE, BALCOMBE.



sort that the ironfoundry supplies. Of markedly rustic type, yet successful, is the mushroom-like example at Plewland, Haslemere. It is made of two rough-dressed stones, that formed one of the posts of an old farm "rick-settle,"



FIG. 341.—AN EIGHTEENTH CENTURY TYPE.




FIG. 340.—MODERN SUNDIAL AT MARSH COURT.

set on an old millstone, which rises a little above the surrounding paving (Fig. 342). Of the dials themselves in their manifold forms, and of the gentle art of dialling, which used to be a needful part of a gentleman's education, this is no place to write. Nor need we fill a page with any of the hundreds of sundial mottoes, which have been printed often enough in scores of gossiping books about gardens. It may be added, however, that some garden-lovers think it wise to be content with a plain brick pillar and concentrate the interest on the dial and gnomon. In Fig. 345 is illustrated an example of bronze, in which a girl with daintily-modelled figure leans over and plays "clocks" with a dandelion. It is a pretty fancy



FIG. 342.—TWO ROUGH-DRESSED STONES.




FIG. 344.—AN OLD GARDEN ROLLER IN A NEW EMPLOYMENT.

to set upon a sundial, and none the less fitting to be used because the game seems to have come with the modern child. It is at least much less than a century since the first reference to the game of "clocks" appears in literature. There is no better




FIG. 343.—A LEAD SUNDIAL.

place for a sundial than in a rose garden, as at Marrowells, Walton-on-Thames (Fig. 346), designed by Mr. A. Winter Rose. In the middle stands the stone figure of a man. His head is bent over the sundial, which he holds to

catch the rays of the westering sun. The hour of sunset is the time which chiefly brings out the beauties of a rose garden, and very admirable this statue looks as the late glow emphasises the strong modelling of the face, and an almost archaic simplicity in the heavy folds of the robe. The garden at The Vineyards, Great Baddow, shows a good example of a sundial placed on a circle paved with mingled brick and stone, radially set, which breaks a long gravel walk (Fig. 347). Another sundial which owes much of its charm to its setting on a broad expanse of circular brick paving is at Saighton Grange (See Chapter XV).

There is a certain reasonableness in grouping in one chapter "Sundials and Seats." In days of universal watches the function of the sundial is to be decorative



FIG. 345.—THE GAME OF "CLOCKS."

and to stimulate gentle moralising. For the latter employment the best authorities are agreed that it is well to be comfortable in body, not always an easy thing to be contrived in a garden. For sheer comfort there is no doubt that something of flimsy appearance, made of canvas and a few sticks or of basket-work, is best; but both



FIG. 346.—STATUE HOLDING DIAL IN ROSE GARDEN.




FIG. 347.—PLACED AT INTERSECTING PATHS.



FIG. 348.—AT SEDGWICK HALL, HORSHAM.



FIG. 349.—AT DANBY HALL, YORKSHIRE.








FIG. 352.—SEATS AND TABLE IN APPROPRIATE SETTING.

kinds have the disadvantage of suffering in the weather. The seat that will defy the rain is therefore a necessity, but it is more—it is a decorative aid. In Fig. 350 is illustrated a carved stone seat designed by Mr. Peto. It comes at the end of a terrace, and with its gay little flanking figures closes the vista in delightful fashion. A stone seat never looks better than against a background of yew. This may be seen in a simple example at Sedgwick Hall (Fig. 348), and in another, of imposing

classical aspect, at Danby Hall (Fig. 349.) It is always desirable for the builder of a stone seat to provide an adequate stretch of paving in front of it, which is the better, both practically and in appearance, for being raised step-height above the adjoining grass or gravel. It is not a good thing to place a seat in an isolated position, as in the example, well designed in itself, which appears in Fig. 351. A bench




FIG. 353.—DESIGNED BY MR. LUTYENS.

should give the impression of being there to be sat on, and that is not likely to be very convincing if there is no path to give access to it. In the majority of small gardens, however, it will be found more practicable to rely on movable wooden seats of stout build. Teak or oak are the best materials, but well-seasoned deals, of a sort that does not tend to split on





FIG. 354.—BY MR. J. P. WHITE.

exposure to rain and sun, are good enough if carefully and regularly painted. Green is a doubtful colour for a seat, as it is likely to quarrel with the varied natural greens which are near it. White is safe, but looks rather staring during the seasons when there is no brilliant colour in the flower garden to relieve it. Oak untreated and allowed to take on the silvery hues which weather will bring to it is, on the whole, the best








FIG. 355.—BY MR. J. P. WHITE.

material for the garden seat; teak, though good, because almost everlasting, is not of so pleasant a colour.

It is well to provide a paved space for such heavy wooden furniture as is not likely to be moved about. Gravel is not comfortable for the feet, and the disadvantages of grass are obvious. An admirable arrangement at Wittersham House is shown in



FIG. 356.—DESIGNED BY MR. MAURICE WEBB.

Fig. 352. seats. two chairs and a table are arranged on a paved floor, and the wall behind is treated with niches holding basketbearing lead boys between pilasters crowned by trophies of fruit. Flower vases standing at the corners of the paving complete a very pretty







FIG. 358.

scheme of an open-air room that must be a pleasant place for the discussion of tea. In Fig. 356 are shown a well-devised table curved on plan, and a pair of armchairs, designed by Mr. Maurice Webb, for the tea pavilion at Chislehurst, illustrated in the last chapter (Figs. 313 and 314). The remaining pictures in this chapter illustrate good and simple pieces of furniture in various manners for differing types of garden design.



FIG. 358A.—SMALL STONE SEAT AT MARKYATE CELL, WITH LEAD FIGURES AT ENDS.

CHAPTER XXI.—ROCK GARDENS.

(CONTRIBUTED BY RAYMOND E. NEGUS.)

Modern Rock Gardening—Principles of Design—Stratification—Formation of the Rock Garden—Kinds of Rock—Likes and Dislikes of Alpines—Planting—Shrubs—Situation of the Rock Garden—Uses of Rockwork—Pools—Bog Gardens—Paths—Steps—Moraines.

THE charms of rock gardening are so many and so varied that no owner of a garden should fail to devote some small portion of the space at his disposal to the culture of alpines and rock plants if the site lends itself to such treatment. In spite of the mass of literature upon the topic the true principles upon which practice



FIG. 359.—OUTCROP OF STRATIFIED ROCK AT CORNERS.

should be based are little appreciated to-day. The rock garden, unlike many other forms of horticulture, is a deliberate imitation of Nature; nine-tenths of our rock gardens, if they imitate Nature at all, imitate her in her least pleasing moods, for they represent formless heaps of rubble. Every stone in the garden should bear the semblance of having been in its place from time immemorial. The first principle of rock gardening is, "Adopt a definite scheme of stratification and carry it out uniformly throughout your garden." Nature, it is true, a few kinds of rock, such as granite, are unstratified; but they are rarely suitable for rock, garden-The stones used should be of the largest possible size compatible with

convenience of handling. It is of the utmost importance that a stone once placed in position should never be moved; moreover, large, well-placed rocks are a joy

in and for themselves (see Fig. 361), whereas small ones almost invariably look scrappy. Large rocks afford a firm foothold by which you may hop nimbly from ledge to ledge and use deft fingers to advantage without leaving a footmark, and without inflicting injury on tender growths.

Fig. 362 affords an example of the errors into which neglect of right principles leads the maker of a rock garden. In the foreground are several



FIG. 360.—ROCKS PROPERLY STRATIFIED AND SKILFULLY LAID.




FIG. 361.—BOLD STRATIFIED ROCKWORK AND MASS-PLANTING.






FIG. 363.—TREATMENT OF AN ODD CORNER.

simple rules be obeyed, the rock garden will appear to be something inherent in the soil, and not a mere fortuitous medley of stones. It is desirable that all the rocks should dip the same way. It used to be thought that it was necessary to have all stones dipping backward into the soil, but experience has shown that this is not so. The reverse slope shown in Fig. 367 at A will conserve moisture quite as effectually as the slopes indicated at C and E. The formation shown also in Fig. 367 by B and D has been found successful from every point of view. The actual appearance of rocks laid as shown by C and E is seen in Figs. 359 and 360 respectively. The whole of the soil underlying the rock garden must be thoroughly trenched and worked to a depth of at least two and a half feet, and deeper still if possible. Plenty of leaf mould, or thoroughly rotten manure, should be incorporated in the soil.

dozen clumps of choice silvery and mossy saxifrages, but the rocks, though large and good, are so placed that not only do they fail to please, but they do not readily permit of proper planting. Stones properly stratified, on the other hand, are admirably adapted to the needs of the plants. best all-round kind of rock to employ is weather-worn limestone, which is beautiful in itself. Natural stone should be used wherever it occurs in the district. stone crumbles somewhat rapidly, but the grit thus produced is a valuable rooting Avoid, as you would the plague, all manner of brickbats, clinkers, concrete and tree trunks. Always lay the stones with their broadest face downwards. If these




FIG. 364.—ALPINE PRIMULAS GROWING IN VERTICAL FISSURE.



FIG. 365.—ALPINE PRIMULAS GROWING IN HORIZONTAL FISSURE.

Alpines, almost without exception, revel in a deep, rich, cool soil. No trouble should be spared to ensure thorough preparation. The great enemies of the dainty mountain plants are damp and drought. A deep, well-worked, porous soil will do more towards preventing fatalities than any amount of artificial drainage and superficial watering. Practically the whole of the alpine flora has an intense dislike of a stiff or retentive soil. All soil used for planting should contain a goodly admixture of sharp sand or grit. For the lime-lovers, such as the encrusted saxifrages, lime, if possible in the form of old mortar rubble, should be incorporated in the compost. All alpines dislike wet about the collar. A top-dressing one inch in thickness of small granite chips will do much to save them from this danger, and will




FIG. 366.—A ROUGH RETAINING WALL.

also prevent undue evaporation in hot weather. The greatest care must be taken in planting. Some alpines are extremely fastidious during the early days of their career, and trouble taken at this stage is well bestowed. Many disappointments are due to the unsatisfactory condition in which plants are received. It is worth while to pay a slightly higher price and make sure of getting plants in good condition and well packed. Other failures are due to planting too late in the autumn. Experience shows that the best of all times for planting is the late spring, unless it can be done early in a wet September, due regard being had to peculiar conditions. What is best in one county may be disastrous in another. Void spaces left behind rocks are fatal to the well-being of any plants whose roots penetrate into them. For this reason light, friable, porous soil should be used, since it can be




FIG. 367.—ROCK FORMATIONS.

well rammed between and behind the stones without fear of its caking. If the stock of plants is ready to hand, so that planting and building can be done at the same time, so much the better. The smaller and younger the plants the more likely they are to take kindly to their new surroundings. Old, well-established clumps are a snare, while the rapidity with which even notoriously difficult subjects increase if once they




FIG. 368.—THE KEYNOTE OF SUCCESS IN PLANTING IS SIMPLICITY.



FIG. 369.—"PLANT IN BOLD MASSES."



FIG. 370.—LARGE CLUMPS GIVE AN APPEARANCE OF SOLIDITY.




FIG. 371.—BOLD MASSES OF ROCK AND PLANTS.

be persuaded to settle down when quite young is amazing. Not a chink in the rockwork but should be filled with vegetation. Alpine primulas make splendid crevice plants for the cool side of the garden.

In all rock gardens, whether great or small, the keynote of success in planting, as in building, is simplicity. The majority of rock gardens are mere botanical collections, interesting but not beautiful. If means are limited, fewer kinds of plants may be acquired, but many examples of those kinds, or, better still, seedlings may be raised and then planted in bold masses. In a small rock garden ambitious schemes, unless they be faultless in every detail, are doomed to failure. An intelligent reproduction of some corner which has struck



FIG. 372.—A JUDICIOUS USE OF COMPACT SHRUBS.



FIG. 373.—RETAINING OR BOUNDARY WALL OF ROUGH UNHEWN BLOCKS.



FIG. 374.—BOUNDARY WALL WITH ITS TOP PLANTED WITH SHRUBS.

the eye with pleasure may well result in the creation of a delightful effect. A judicious use of compact shrubs will add greatly to that appearance of solidity which every rock garden should present. In a well-planned rockery the eve should not see too much at a time, but should be gently led from one prospect to another. Suitable shrubs further this purpose. The larger heaths are useful, and Japanese maples are indispensable, providing rich colour in autumn. The cistuses and their lesser brethren, the helianthemums, are good but rampant, the cistuses requiring plenty of headroom. The prostrate cotoneasters and dwarf kinds of cytisus are among the best, as are Gaultheria procumbens and Pernettva mucronata. One of the most charming of all small shrubs is Daphne Cneorum, with its innumerable fragrant pink blossoms. The lesser genistas and veronicas, especially V. Hectori, are useful. Skimmia japonica is decorative in winter with its red berries, and at all seasons valuable for its excellent foliage. The shrubby spiræas, such as arguta multiflora and prunifolia, are splendid in every way. The list of suitable shrubs is a long one, but there should in every case be a goodly number of dwarf conifers of the Savin class, such as Juniperus compressus nanus and the ordinary J. Sabina. Very choice, delicate plants should be grown in a portion of the garden specially allotted to them, in order to avoid risk of their becoming overwhelmed and lost. Very many of the choicest species succeed best in the moraine. It is a common but misguided practice to plant yuccas in the rock gardens. No plants are more hopelessly out of keeping with the general character. These and any plant or shrub which has anything of a tropical aspect must be rigidly excluded.




FIG. 375.—BOUNDARY WALLS.

No difficulty should be experienced in respect of the situation of the rock garden, for there are numberless species to suit every aspect. The shade, and even the

proximity, of trees must be carefully avoided. Generally speaking, the more open and exposed the situation the better, provided some sort of shelter can be furnished against cutting or excessively boisterous winds. In every case the rock garden should be as far as possible from the dwelling-house, and the transition to it should be gradual. It is a great mistake to cramp the rock garden unless the space available is very circumscribed, for the greater the freedom the greater will be the illusion of reality. Furthermore, nearly all alpines love light and air.

There are various forms of rock garden, such as the dell, the ravine, the miniature cliff, the knoll. Many different types will be found in the illustrations. Even in the smallest back-yard there is scope for a square yard or two of such construction as is seen in Figs. 359, 360 and 363. The mere fact of its being an odd corner should not



FIG 376.—BOG AND WATER GARDEN




FIG. 377.—A GOOD ROCK POOL.

be an excuse for hasty workmanship. There is a use to which rockwork is seldom put, namely, as a boundary wall. It is true considerable trouble and expense are entailed, because such a wall must ordinarily be double, with at least two feet of good soil between the faces. The second face should be of rock or brick or concrete, according as it is or is not visible from the garden. The method of construction is illustrated in Fig. 375, and examples are to be seen in Figs. 366, 373 and 374. A perforated pipe led along the top of the wall will make it a suitable home for the choicest subjects. Failing that expedient, the soil should consist largely of peat, sand and leafmould, with but a small proportion of Water properly employed forms a charming feature in any rock garden. Few things are more delightful than the reflection in still water of overhanging rocks clothed with masses of blossom. A good example may be seen in Fig. 377.



FIG. 378.—STEPPING-STONES.

A little cascade, such as appears in Fig. 379, can sometimes be arranged. Where space permits, a path may be led down to the edge of a pool, and carried across by means of stepping-

stones, as in Fig. 378.

IN EQUAL PARTS

No rock garden is complete without a space of boggy ground, for many gems, such as primulas farinosa and rosea, are never completely happy under other conditions than those afforded by moist ground. The type of pond illustrated in Fig. 380 has been found admirably adapted to the needs of the small garden. Upon the margins contained within the actual

SECTIONAL VIEW boundaries of the pond Japanese



FIG. 379.—BOLD STRATIFIED ROCKWORK AND SMALL CASCADE.

WATER LEVEL

CONCRETE OF
CEMENT ONE PART
SAND AND LOAM

WATER LEVEL

CONCRETE OF
CEMENT ONE PART
SAND THREE
PARTS.

FIG. 380.—POND FOR SMALL GARDEN.

irises, primulas, dodecatheons and other moisture - loving plants will flourish. Primula rosea grown in this way is a prodigy of vigour and abundant bloom. A typical bog



FIG. 381.—A ROCKY PATH.

and water garden is seen in Fig. 376, but such a conception can only be carried out where there is a good stream. With a little forethought in planning and construction, however, a wonderful illusion of spaciousness may be produced in a small area.

As to paths in the rock garden, the best form is that seen in Fig. 381, but it is somewhat expensive to make. It is, however, one with the garden, and is beautiful in itself, not a hideous and anomalous intrusion, as is the common gravel path. A paved path, as in Fig. 382, is another good type. Fig. 369 shows what may be called "land stepping-stones." The slabs of stone which form the path, instead of being let in flush with the surface of the soil, are left projecting some eight



FIG. 382.—A ROUGH PAVED PATH.

or nine inches. The interspaces are filled with dwarf flowers, and thus one may walk over a veritable sea of blossom without so much as damaging a petal. Failing the rocky or stone path, the best kind is of grass. In many respects it is more natural than any other kind, and serves as a setting to the rocks and their vegetation. The amount of labour entailed is somewhat heavy, and care should be taken that no rock is placed within six inches of the verge of the grass, otherwise the edges will need to be trimmed by hand.

Where the garden lies on a slope it may be terraced, the terraces being supported by retaining walls of rock, preferably constructed of large unhewn blocks after the manner described in Chapter XII. The secret of success is to have a thick layer




FIG. 383.—CYPRIPEDIUMS THOROUGHLY AT HOME ON THE UPPER MARGIN OF A ROCK GARDEN.



FIG. 384.—ROCK STEPS LEADING FROM TERRACE THROUGH ROCK WALL TO ROCK GARDEN.

grown with herbage, though small fry, like Erinus alpinus, Ionopsidium acaule and Linaria alpina, may be suffered to grow in the interstices. In the small bog garden one must carefully avoid such vigorous growers as Gunnera, Rodgersia, Saxifraga peltata and all those plants which appear in catalogues under the heading "Bog and Waterside Plants." The bog should be devoted to Primulas rosea, cockburniana, farinosa, frondosa, japonica, pulverulenta, capitata, denticulata, Sieboldii; to shortias, terrestrial orchids, the choicer trolliuses. dodecatheons and mertensias.

of rich compost behind the rock face. Fig. 384 shows the charming effect of roughly - hewn rocky steps leading down through such a wall from the terrace to the rock garden. Such steps should not be allowed to become over-

The soil must be spongy and constantly moist, but at the same time well drained, for nothing worth growing will endure stagnant moisture. A few large, flat slabs of stone on the surface will be of great value in affording access to all parts of the

bog without injury to the plants. Fig. 383 shows cypripediums thoroughly at home upon the upper margin of a bog garden. A moraine garden is troublesome to construct, but repays the trouble. The essentials are very sharp drainage and abundance of moisture in dry weather. Unless the supply of water is very limited,




FIG. 385.—CONSTRUCTION OF SMALL MORAINE.

it is not necessary to have the concrete foundation shown in Fig. 385, although the latter is the best form for the small moraine, affording the most complete control over the water supply. In wet weather the inlet pipe is shut and the outlet opened; in dry weather the converse. Where a slope is available, Fig. 386 shows a simple but efficient type of moraine. A half-inch pipe perforated at every six inches is led along the top six inches below the surface. Flat rocks are useful, as in the bog garden, for access to the plants. Fig. 387 shows the construction of a moraine which has been found to work well in practice.




FIG. 386.—CONSTRUCTION OF MORAINE ON SLOPE




FIG. 387.—CONSTRUCTION OF MORAINE ON LEVEL GROUND.

In this moraine (Fig. 387) the following, among other Alpines, flourish and bear flowers in profusion: Androsace brigantiaca, carnea, lanuginosa, primuloides, villosa; Asperula suberosa; Antirrhinum asarinum; Arenaria purpurascens; Campanula collina, pulla, pulloides, Steveni nana, waldsteiniana; Cyananthus lobatus; Dianthus Freynii, microlepis, neglectus; Edraianthus Pumilio, pumiliorum;

Gentiana verna; Linaria alpina; Primula nivalis; Saxifrages apiculata, aretioides, Boryi, Boydi, Boydi alba, burseriana and its varieties crenata, major, minor, Gloria, etc., cochlearis, cochlearis minor, dalmatica, Faldonside, Ferdinandi-Coburgi, Frederici-Augusti, Grisebachi, media, porophylla, Petraschi, rocheliana.

In the present edition it has been considered advisable to suggest a certain number of plants and shrubs for the rock garden. The lists are not in any way exclusive, and the alternatives are very numerous. But every one of the plants

suggested will give satisfaction if treated with reasonable care.

For the rocky "corners" illustrated in Figs. 359, 360 and 363.

PLANTS (For shrubs see list below).

Achillea argentea.

Anemones blanda and apennina.

Arenaria montana.

Artemisia Baumgarteni. Aubrietia Dr. Mules.

Campanulas muralis and pusilla Miss Willmott.

Chionodoxa sardensis.

Dianthus cæsius and neglectus.

Edraianthus serpyllifolius.

Erica carnea.

Hyacinthus azureus.

Iberis sempervirens Little Gem.

Iris reticulata.

Lithospermum prostratum Heavenly Blue.

Muscari Heavenly Blue.

Saxifraga (silvery) longifolia.

lingulata.

Wallacei.

Sedum pulchellum.

spathulatum.

Viola gracilis

For the type of rockery illustrated in Fig. 361.

ON THE WALL.

Achillea umbellata.

Androsace lanuginosa.

sarmentosa.

Antirrhinum asarinum.

glutinosum.

Campanula garganica hirsuta. Cotoneaster adpressa.

horizontalis.

Cytisus decumbens.

Dianthus cæsius.

Euonymus radicans kewensis.

Gypsophila prostrata rosea.

Juniperus Sabina prostrata.

Lychnis Lagascæ. Phlox subulata G. F. Wilson.

Santolina incana.

Saponaria ocymoides.

Saxifraga nepalensis.

sarmentosa.

,, sarm Silene Schafta.

AT THE FOOT OF THE WALL.

Campanula persicifolia.

Cheiranthus Allioni.

Crocus biflorus.

(Kabschia) burseriana.

(mossy) bathoniensis.

Crocus speciosus.

Cyclamen Coum.

europæum. Dianthus deltoides roseus.

Epimedium colchicum.

Erodium macradenum.

Gentiana acaulis.

Geranium argenteum.

Geum montanum.

Helianthemum Mrs. Croft.

Hypericum reptans.

Iris pumila cærulea.

stylosa.

Lavender, dwarf Munstead.

Narcissus odorus rugulosus.

Nierembergia rivularis.

Omphalodes verna.

Onosma stellulatum.

Polygonum vaccinifolium.

Potentilla Miss Willmott.

Primrose, common yellow.

Saxifraga umbrosa.

Wallacei.

Tulipa kauffmanniana. Tunica Saxifraga flore pleno.

Veronica Hulkeana.

Plants suitable for a rough retaining wall in a sunny position, such as that illustrated in Fig. 366. A simple colour scheme in grey and pink.

Achillea umbellata.

Androsace sarmentosa.

Armeria maritima laucheana.

Artemisia Abrotanum.

Cerastium tomentosum.

Convolvulus althæoides. Dianthus deltoides.

Geranium einereum. Helianthemum Mrs. Croft. Saponaria ocymoides.

Saxifraga (silvery in variety).

Sempervivum arachnoideum.

Stachys lanata.

Tunica Saxifraga.

If the space is at all confined, omit the Cerastium, the Convolvulus and the Stachys.

A list of shrubs, in addition to those already mentioned, suitable for the rock garden in positions similar to those seen in Fig. 372.

Berberis Wilsoni.
Cistus corbariensis.
Dabœcia polifolia.
Daphne Cneorum.
Erica vagans.
Gaultheria procumbens.
Genista hispanica.
Helianthemums in variety.
Lavender, dwarf Munstead.
Ledum palustre (peat).
Nepeta Mussini.

Spiræa prunifolia flore pleno. Veronica cupressoides.

DWARF CONIFERS. A good selection is:

Cupressus nootkatensis var. nana compacta. Juniperus recurva squamata. Picea excelsa nana.

Picea excelsa nana.
Pinus Bandaisho.
Retinospora obtusa nana.
Thuja dolabrata nana.
,, Rheingold.

A simple scheme of planting for a bog and water garden such as is illustrated in Figs. 376 and 378.

Eomecon chionantha.
Inula glandulosa.
Iris Kæmpferi.
,, sibirica.
,, ,, Snow Queen.
Kniphofias in variety.
Menyanthes trifoliata.

Primula japonica.
,, rosea.
Rodgersia podophylla.
Saxifraga peltata.
Senecio Clivorum.
Spiræa palmata.
Trollius europæus Orange Globe.

For a shady rock garden such as that illustrated in Figs. 379 and 384.

Aquilegia cærulea.
,, glandulosa.
Cyclamen neapolitanum, etc.
Erythronium Dens-canis.
Haberlea rhodopensis.
Hepatica triloba in variety.
Hutchinsia alpina.
Linnæa borealis americana.
Mertensia virginica.
Myosotis alpestris rupicola.
Phlox subulata in variety.


Primula frondosa.
,, nivalis.
Ramondia pyrenaica.
Saxifrages bathoniensis.
,, Guildford Seedling.
,, Stormonth's Seedling.
,, Wallacei.
Tiarella cordifolia.
Trillium grandiflorum.
Uvularia grandiflora.

Minute prostrate plants suitable for carpeting as in Fig. 381.

Acæna Buchanani. Arenaria balearica. Dianthus deltoides. Helxine Solieroli. Hutchinsia alpina. Mentha Requieni. Muehlenbeckia complexa.
Saxifraga muscoides atropurpurea.
Thymus lanuginosus.
,, Serpyllum coccineus.
Veronica canescens.

AUTUMN AND WINTER EFFECT.

To avoid dulness in the rock garden in the autumn and winter months plant clumps of such autumn-flowering bulbs as the autumn crocuses, colchicums, Scilla autumnalis and Galanthus cilicicus. Late-sown nemesias will flower right up to the severe frosts, as will other dwarf annuals, such as leptosiphon and brachycome. Anemone japonica is indispensable. Japanese maples and azaleas in the background will give superbly rich colour effects in late autumn. A mass of the dwarf Thuja Rheingold will harmonise with the colour of the maples and azaleas and with the tints of deciduous trees at that season. Spiræa Thunbergi and Berberis Wilsoni should not be omitted. Jasminum nudiflorum and the witch hazels will link late autumn with the first arrivals of the New Year, namely, snowdrops, winter aconites and Crocuses Imperati, tomassinianus, etc. Ceratostigma plumbaginoides (syn. Plumbago Larpentæ) should be planted freely on rock walls, and Corydalis Wilsoni at their base. A liberal planting of dwarf conifers will afford a sight of beauty even in mid-winter.



INDEX.

Note.—The large numerals indicate illustrations of the subject indexed, and refer not to the Figure numbers, but to the pages on which illustrations will be found. The small numerals indicate references in the text.

Acid in soil, 11. Acremead, Kent, garden at, 188, 191. Alpines, 52, 68, 119, 244. Amalfi, pergola at, 179, 180. Amorini, Chapter XIX. passim. "Antiques," 219. Arches, iron, for pergolas, 188. 190; of treillage, xliv. Ardkinglas, garden stair at, 85, 85. Athelhampton, garden at, 145, 147, 105, 106, 208, 208. Autumn-blooming shrubs, 43, 44, 44. Balusters, 100-104. Balustrades, xxiii., xxiv., 155, Chapter X. Bankart, George P., designs by, 163, 164, 164, 226 226, 228, 232. Bargate stone, 3, 171, 171. Barrow-way at side of long garden, 9. Bases for sundials, 227. Basin, tile-built, 160, 161. Basin, tiled, 59, 60.
Bathing pool, 165, 166.
"Battering" of retaining walls, 122.
Berkshire, a garden in, Chapter III. Biddestone Manor, gate at, 195, 196. Bidlake, W. H., garden designed by, 10. Billerey, Fernand, design by, 214, 215. Bird-baths, 165, 165, 223.

Blackamoor in lead, 227, 230.

Blomfield, Reginald, A.R.A., designs by, 138, 140: quoted, 12. Blow, Detmar, designs by, 211, 211, 214, 215. Blythburgh, garden at, 143, 145. Bog garden, 249, 251, 254, 254. Bologna, Gian di, 223. Bolton, Arthur T., designs by, 78. Borders, backed by hedge, 131, 133; by well, xlii., xliii. Borders by serpentine walls, 108, 108. Borders, flower, xl., xlix, 3, 7, 8, 21, 25, 35, 39, 40, 42, 52, 121. Borwick, Leonard, his garden, xlvii., xlviii. Boundary walls of rock, 248, 249, 250. Bowling greens, 131, 131, 132. Box hedges, 36, 37, 42, 132. Boy and Dolphin, 220, 222, 223, 223. Boy statues, Chapter XIX. passim. Bracken, 11, 16. Bramley, Millmead, Chapter I. Brick dry walls, 120, 122, 123, 126. Brick fountain, 150, 151, 157; do. paths, 56, 58; do. paving, 176-8, 176-8; do. steps, 201, 206. Brickwork, open, 104.
Bridge End garden, Saffron Walden, xxxiii.—xxxvi., xxxix. Bridge over pool, 147, 151. Bridges over moats, 165, 166. Brierley, Walter, design by, 196, 196

Broadway, a garden at, 213, 214.

Bromsgrove Guild, ornaments by, 222,

Brockenhurst, hedges at, 132.

Bronze dials, 231, 233.

Building of retaining walls, 122, 126, 127. Bulwick, yews at, 132, 136. Buncker, a smith, 200. Calcareous soil, 53. Canal treatment, **56**, 58, **159**, 160. Carriage gates, 197, 197. Carriage ways, xlvii., xlix.
Carter, W. T. A. T., designs by, 209, 210. Cascades, 149, 251, 251. Cashmore, H. W., modelling by, 162, 162. Cave, Walter, designs by, 89, 89, 92, 93, 93, 185, 189, 209, 209. Cementing of walls, 105. Chains for pergolas, 188. Chance, Lady, garden sculpture by, 161, 161, 162. Chelwood Vetchery, garden at, 159, 160, 183, 187, 204, 204. Chesterton, Frank, design by, 82, 83. Cheyne Walk, 100, garden at, 60, 62, 64, 65. Children and gardens, 89. Circular garden, 29—32, **30—32.**Circular paving, **174**, 176; do. pool, **46**. Cisterns, lead, 164, 164, 165, 165. Cleeve Prior, gate at, 194, 195; do., yews at, 130, 131. Climbing plants, 37, Chapter XI. Clipped box, 36, 37, 42. Clipping of yew hedges, 132. "Clocks," game of, 231, 233. " Cob" walls, 212, 213. Cole, Leopold E., design by, xlvii. Colonnade of treillage, xlv. Colour schemes, 31, 40, 41, 42, 44, 54, 124, 125. Colour schemes in the flower garden, reference to, 42. Colours for garden furniture, 238. Combelands, Pulborough, garden at, 59, 61. Compartments, a garden in, 27. Concrete walls, 109, 109. Cordon fruit pergolas, 188, 190. Coronal garden, 105, 106. Cottages, motor approaches for, xlvii.—xlix. Courtyard gates, 196, 196. Cray, garden at, 59, 61. Creepers—see climbing plants. Cupid and Swan, 223, 223. Cupids, Chapter XIX. passim. Cypress hedges, 132. Danby Hall, Yorkshire, seat at, 234, 237. Dancing Boy fountain, 163, 163. Deas, F. W., design by, xxx., xxxv. Deep planting, 11. Dialling, 231. Dillistone, George, garden laid out by, xxv. Dipping-wells, 8, 9, 9, 56, 58. Ditton Place, sundial at, 227, 229. Dolphin, lead, 162, 162. Dorchester. a garden at, 72. Dormy House, Walton Heath, garden at, xxvii—xxx, xl., xl. Dovecotes, 58, 58.

Dry walling, 23; diagrams, 127. Dry wall planting, 49, 50, 51. Dry walls, see retaining walls, Chapter XII. East Coast, scheme for a garden on the, 64, 66-68. Eastwood Cottage, Walberswick, garden at, 69, 69, 70. Edzell Castle, walled garden at, xli. Emerson, quoted, 12. English Leadwork: Its Art and History, reference to, 228. Ewelme Down, garden at, 89, 89, 92, 93, 93, 185, 189. Excavation, cost of, 76. Fan gardens, 141, 141. Firebrick, burnt, for steps, 83. Flag paving, 175. Fleming, quoted, 202. Flower-boxes in walls, 105, 105. Flying Mercury, 223, 225 Forecourts, xlvii., xlvii.--xlix. Fountains, Chapter XIV., xvi., xxxiii., 59, 71, 135, 137, 158, 159, 160, 161-2, 163, 164. Four Oaks, Woodgate, Chapter II. Fraser, Gilbert, design by, 175. Fruit garden walls, 104. Fruit pergolas, 188, 190. Fruit room combined with pergola, 183, 187. Garden houses, 1, 6, 8, 9, 10, 10, 13, 35, 44, 45, 52, 53, 56, 58, 202 and Chapter XVIII.

Garden in West Surrey, a, Chapter V. Garden plans, see Plans, garden. Gardner, J. Starkie, quoted, 199. Gargoyle of lead, 76. Garland rose, 17, 22. Garston Park, pergola at, 185, 189. Gate-piers, statues on, 219, 220, 221. Gates and gateways, Chapter XVII., 57, 58, 71. Gateway, creeper-clad, 111, 112, 114. Gazebos, Chapter XVIII., 44, 45; also see Garden Gibson, Dan, the late, designs by, 95, 95. Gilbert, Alfred, fountain by, 162, 163. Gimson, Ernest, design by, 165, 166. Godalming, Westbrook, Chapter IV. Goodrich House, Hatfield, garden at, 70, 70, 71. Gourd pergola, 181, 183. Granite chips for Alpines, 244. Granite unsuitable for rock gardens, 240. Great Maytham, garden at, 203, 204, 204, 206, 206, 215, 215. Grove, The, Mill Hill, garden at, 211, 211. Guildford, garden at (Littleholme), 76, 78-80. Guildford, garden at (Highmount), Chapter VI. Guthrie, Rome, designs by, 159, 160, 183, 187, 204, 204. Hamp, Stanley, design by, 211, 211. Hampton Court, garden at, 162, 163, 225, 226; misuse of ampelopsis at, 116. Happisburgh, design for garden at, 64, 66—68. Happisburgh, garden at, 211, 211. Hare, C. G., restoration by, 199. Hatfield, a garden at, 70, 70, 71. Heath garden, 31. Hedges, Introduction passim, Chapter XIII. Heveningham Hall, wall at, 107, 108. High Coxlease, Lyndhurst, Chapter II. Highmount, Guildford, Chapter VI. Hillside gardens, xix.—xxx., Chapter VIII. and 119. Hippocampus of lead, 158, 161, 162.

Historical examples, value of, 55, 102. Home Place, Norfolk, garden at, 89, 90, 91, 183, 187. Horder, P. Morley, designs by, 72, 73, 73, 109, 109, 169, 170. Horman's Vulgaria, quoted, 73. Horsnell, Alick, design by, xlvii., xlix. Hurtwood Edge, garden at, 78, 81, 82. Hurtwood, garden at, 75, 76, 141, 141, 142, 143, 208. 208. Husson, Pierre, quoted, 141. Hutchinson, Horace, his garden, xxix., xxx., xxxiii. Ilex hedges, 132. Iron gates, Chapter XVII. Ironstone paving, 171, 171, 173. Island, Steep, garden at, 59, 60, 92, 93, 148, 151. Italian pergolas, 179, 179, 180. Italian well-heads, 166—168, 167, 169. Ivy, misuse of, 111, 113, 201, 206; well-used, 115. James, Alan, design by, 217, 218. Jet for pool, 149. Kelsale Manor, Saxmundham, garden at, 165, 166. Laburnum pergola, 191, 193. Lake District architecture, 95. Lambay, wall at, 109, 109. Lane, Sir Hugh, his garden, 60, 62, 64, 65. Larch pergolas, 181, 181, 182, 183. Laurel hedges, 135.
Lead gargoyle, 76; figures on stone seat, 239; fountain figure, xxxiii.; garden ornaments, 220; inlay, 228, 231; peacocks, xxv.; pump-heads, 168, 168; sundial, 232. Leslie, G. D., R.A., mask designed by, 36, 42. Lethaby, Professor, house designed by, 14, 15; quoted, 220, 225. Lilies, good soil for, II. Lily ponds, xvi., xxxiii., 12, 13, 46, 49, 145, 154, 208. Limes, pleached, 27, 35; pollarded, 138, 138. Limy soil, 11, 53, 63, 132, 244. Lion mask for fountain, 161, 161. Liphook, gardens at, 83, 84. Little Boarhunt, Liphook, garden at, 55, 56, 57, 213, 214. Littleholme, Guildford, garden at, 76, 78-80, 162, 162. Little Ridge, garden at, 214, 215. Loggias, 29, 35 Lorimer, Sir Robert, designs by, 85, 85. Lucas, Seymour, R.A., his garden, 145. Lutyens, E. L., designs by, 1, 2, 17, 62, 64, 65, 93, 93, 95, 95, 109, 109, 154, 155, 158, 160, 161, 182, 185, 186, 203, 204, 206, 206, 215, 215, 228, 231, 237. Lyndhurst, High Coxlease, Chapter II. MacLeod, W. M., his garden, xxv., xxv. Macquoid, Percy, pavilion in his garden, 216, 218.

Mallows, C. E., designs by, i., ii., ii., 64, 66—68, 76, 77, 96, 97, 131, 134, 144, 145. Markyate Cell, garden at, xx., xxiii.—xxviii. Marliac lilies, 15. Marrowells, garden at, 232, 233. Marsh Court, garden at, 154, 155, 158, 161, 177, 182, 185, 228, 231. Mathern, garden at, 94, 139, 140. Mawson, Thomas, designs by, 175, 223, 224. Melbourne, garden at, 222, 222. Methods of paving, Chapter XV. Millfield, Brentwood, pool at, 152, 158. Millmead, Bramley, Chapter I.

Millstones, 231, 232. Mitchell, Arnold, designs by, 209, 209, 233, 233. Moats, bridges over, 165, 166. Montagu, Lady Mary Wortley, quoted, 74. Moraine garden, 254-5, 254-5. Morton House, Hatfield, garden at, 144, 149. Mottoes on sundials, 228. Mounting block at Cleeve Prior, 194, 195. Muntzer, G., his garden, 76, 78—80. Murrel, The, Aberdour, garden at, xxx., xxxv. Narcissus statue, 220. Narrow gardens, designing of, 1-9, and Chapter VII. Nature imitated in rock gardens, 240. Negus, Raymond E., on rock gardens, Chapter XX. Newton Ferrers, balustrade at, 101, 103. Noah's Ark ornament on tub, 226. North aspect for flower border, 35 Norton Conyers, garden at, 200, 202, 202, 206. Oak for seats, 238; for pergolas, 181. Old iron gates, use of, 197. Old materials, use of, 214 Oliver, Basil, design by, 217, 218. Openwork walls, 104, 104. Ornaments, garden, xxvi., Chapter XIX.
"Overthrow" of gates, 197; of well-heads, 166, 167. Owlpen Manor, garden at, xix., xix.—xxii.; gate and steps at, 86. Packwood House, garden at, 200, 201, 206. Palissy, Bernard, quoted, 170. Pan, 223, 223. Papillon Hall, garden at, 156, 158, 220, 221. Paradisi in Sole, reference to, xli. Parker, W. J., designs by, 197, 197-198. Parterres, 56, 59, 60, 63, 132, 135, 157. Paths, xlvii., xlviii., 21, 70; behind flower-beds, 62, 64, 108, 108; of escape, 31; in rock gardens, 251, 252, 252; meeting under pergola, 183, 187. Paved court, 36, 37, 39, 41. Pavilions, Chapter XVIII. Paving, xl., xl., 3, 25, 48, 56, 58, 59, 60, 61, 68; broken by pools, 153; methods of, Chapter XV.; planting of, 175, 176. Paxton, Sir Joseph, 170. Peaty earth, 36. Pergola, the, Chapter XVI. Pergolas, xxiii., xxxix., 53, 53, 73, 173, 176, 177; good dimensions for, 185-186; stepped, 188, 191. Petersfield, garden at, 147, 151. Peto, H., design by, 234, 237. Pinkerton, Godfrey, designs by, 182, 183, 215, 217. Piping Boy statue, 221, 222. Pisé or "cob" walls, 212, 213. Pitsford, pump-house at, 169, 170. Plan of stepped pergola, 188, 191. Plans, garden, xvii., xx., xxvi., xxix., xxxi., xxxii., xxxv., xxxvii., xlvi., xlix., 5, 11, 18, 28, 38, 59, 62, 63, 64, 67, 69, 70, 72, 73, 76, 78, 83, 135, 157. Planting for pergolas, 188; of pavement joints, xl., 128; of retaining walls, Chapter XII.; scheme for seaside garden, 64. Planting plans, 2, 5, 6, 20, 25, 26, 30, 33, 41, 43, 49, 58, 136, 175. Plastered pergola posts, 179, 180. Platts, The, Petersfield, garden at, 59, 61. Pleached alleys, 27, 35, 191. Plewland, Haslemere, garden at, 59, 62, 231, 232.

Pollarded limes, 138, 138.

Pools, xxxiii., 12, 19, 29, 31, 32, 36, 42, 46, 49, 51, 56. 60, 61, 63, 65, 68, 71, 80, 89, 90, 97, 137. Pools generally, Chapter XIX. Pools, various shapes for, 148—151, 149—151. Porch, detached, 93, 93. Porter, Horatio, design by, 227, 229. Portland stone paving, 171, 173. Portugal laurel hedge, 137. Portuguese bricks, 104. Postern in wooden gate, 205, 206. Potters' Arts Guild, 223. Primulas in rock gardens, 243, 244, 247. Principles of garden design, 12 et passim. Prior, E. S., designs by, 59, 61, 89, 90, 91, 183, 187. Privet hedges, 132. Puech, a sculptor, 223, 224. Pump-casing, 168, 168; heads, 168, 168; house, 169, 170. "Random" paving, 171, 173; walling, 126. Ravensbury Manor, treillage at, xliii. Read and Macdonald, designs by, 59, 62. Reed-screens, to protect against wind, 67. Retaining walls, 21, 59, 61, 62, 244, 248, 249, 250. Retaining walls and their planting, 2, 3, 6, 23, 68, Chapter XII. Ribbon wall, **107**, 108. Rick-stones, use of, 210, 211, 231, 233. Rills, 56, 58, 159, 160. Roberts, the Brothers, smiths, 198. Robinson, Thomas, smith, 200. Robinson, W., his garden at Gravetye, 227, 227. Robinson Crusoe, quoted, 194. Rock gardens, xlv., xlvi., 15, 69, Chapter XXI. Rock pools, 250, 250. Roller as sundial base, 228, 232. Roofed seats, 29, 35, 35. Rose, A. Winter, designs by, 69, 69, 70, 70, 71, 144, 149, 152, 158, 165, 166, 218, 218, 219, 223, 232, 233. Rose gardens, xxvii., 47, 50, 51, 56, 58, 59, 60, 175, 232, 233. Rotherfield, garden at, 100, 102. Round, Douglas, designs by, 51. "Rustic" building, 213. Saffron Walden, topiary garden at, xxxiii.—xxxvi., xxxix. Saighton Grange, sundial at, 233. St. Clere, Kemsing, garden at, 182, 183, 211, 215 Samuel, Sir Stuart, Bart., M.P., his garden, 159, 187, 204, 204. Sandhouse, Witley, garden at, 185, 188, 223, 225. Sand paths, 31. Sandy soil, 11, 36. Sartorius, Major-General, his garden, 141-2-3, 143. Scott, Baillie, designs by, 59, 60. Scottish garden houses, typical, 217, 218. Screen, open, for garden, 65. Sculpture, garden, Chapter XIX. Seal Hollow, Sevenoaks, paved court at, 59, 60. Seaside gardens, 64, 66—68. Seats, Chapter XX., 13, 29, 35, 35, 70. Sedgwick Hall, Horsham, seat at, 234, 237. Serpentine walls, 107, 108, 110. Servants' garden, 73. Shady walls, planting of, 121. Sheltered garden, a, 64, 66—68. Shelters, garden, 217, 218.

Shepherd's Gate, garden at, xxix., xxx., xxxiii. Shrubs in rock garden, 247, 248; for walls, 118. Sitwell, Sir George, quoted, 222. Slate stones in retaining walls, 119. Sloping ground, treatment of, xix.—xxxv., 74. Small Country Houses of To-day, reference to, 109. Small sites, the treatment of, Chapter VII. Smith and Brewer, design by, 188, 191. Smith, F. E., his house at Charlton, thatched shelters at, 217, 218. Smith, Maberley, design by, 59, 61. South Kensington Museum, fountain at, 163. Stairways, xxiii.—xxviii., Chapter IX., 225, 225 and see Steps. Staplefield Grange, garden house at, 216, 218. Statues, 19, 26, 56, 58, 62, 63, 65, 232, 233, 234, 237, 237, 238, Chapter XIX. Statues in pools, xxxiii., 161. Stepped water gardens. 155, 156. Steps, xxiii.—xxvi., 6, 7, 8, 10, 10, 19, 21, 23, 37, 46, 48, 49, 50, 51, 52, 57, 75, 76, 77, 80, 127, 127, 128, 195, 206; in rock gardens, 254, 254; over pool, 147, 151. Stoneywell Cottage, pool at, 165, 166. Stratification in rock gardens, 240, 241. Suburban garden, plan for, 73, 73. Sullingstead, Hascombe, porch at, 93, 93. Summer houses, Chapter XVIII., and see garden Sundial, pools grouped round, 148 Sundials, 6, 8, 174, 176, Chapter XX. Sunk gardens, 29—32, 30—32, 56, 58, 61, 155, 156. Sun-trap walls, 108—110, 108—109. Sutton Courtenay, well-head at, 168, 169. Tables, garden, 237, 238, 238. Tank garden, 19, 20, 21. Teak for seats, 238. Temple Dinsley, garden at, 219, 221. Term figures, 223, 223. Terraces, xx.—xxviii., 74, 76, 79, 80, 93, 95; pavilions for, 218, 218; gates on, 204, 204; in rock garden, 254, 254; cost of, 48. Terra-cotta garden ornaments, 223. Thatched roof for garden houses, 9, 211, 211, 212, 217. The House and its Equipment, quoted, 199. Thomas, Inigo, designs by, 100, 102, 105, 106. "Thunder-House," 44, 45. Thursley, garden at, xxxi., xxxv. Tijou, Jean, smith, 199. Tile-built basin, 145; fountain, 160, 161; parapets, 103, 104, 104; pergolas, 182, 183, 185. Tile-paving, 177—178, 176—178. Tinned ornament on leadwork, 226, 226. Tipping, H. Avray, planting scheme by, 64. Toads of lead, 161. Tool-houses, 13, 218, 218. Topiary work, xix.—xxii., xxiv., xxvii., xxxiii.—xxxvi., 139, 140, 185, 189. Tortoise of lead, 161, 161 Town Gardens, 60, 62. Trees as rose supports, 20, 24. Treillage, xvi., xliii.—xlvi., xliii.—iv., 60, 63, 191, 192; perspective, 185, 189; shelter, 217, 218; door, 206, 206; roofing to pergola, 185, 188.

Troup, F. W., designs by, 109, 185, 188, 225, 225.

Triggs, H. Inigo, designs by, 55, 59, **63**, 97, **97**, 104—105, 104—105, 132, 135, 157, 157, 158, 159, 177, 178, 182, 184, 207, 207, 213. Tubs, placed by pool, 148. Turner, Thackeray, garden designed by, Chapter IV. Turnor, Christopher, ,, ,, 143, "The Twelve Apostles" yew hedge, 130, 131. Unsworth, W. F., designs by, 57, 214, 216. 143, 141-2-3. Unsworth and Triggs, designs by, 60, 61, 83, 84, 92, 93, 147, 148, 151, 214. Van Nost, Jan, 225, 226, 227, 230; figures modelled by, **221**, **222**, 222. Vases, **xxiii.**, Chapter XIX. Vernacular, building, 209 View, framing of, by garden features, xxxv., 54. Vineyards, Great Baddow, garden at, 143, 145, 209, 209, 233, 233. Vistas made by gates, 198, 203; treatment of, xxvi. Voysey, C. F. A., designs by, 76, 162, 162. Vulgaria, Horman's, quoted, 193. Walberswick, garden at, 69, 69, 70 Walks, see Wood-walks. Wallace, R. and Co., garden laid out by, xxv. Wall-fountains, 160, 161, 162, 163. Walled gardens, xxx., xli., 34, 198, 203, 203, 214, 215, 215. Walls, xl., xlii., Chapter X., 56, 57, 58; climbing plants for, 2; retaining, and their planting, Chapter XII. Warren, a smith, 200. Water gardens, 15, 16, 19, 20, 21. Water, in rock gardens, 249, 250, 250. Water in the formal garden, Chapter XIV. Water level in pools, 147. Watts, Mrs. G. F., 223. Well-heads, 166—168, 167, 169. Westbrook, Godalming, Chapter IV. West Dean, pergola at, 191, 193. White, E., design by, xxxi., xxxv. White, Gilbert, Natural History of Selborne, quoted, 58. White, J. P., designs by, 185, 189, 191, 192, 238. Wind, garden protected against, 64. Windows in garden houses, 216. Winter garden, 33, 34, 34. Wistaria, misplaced, 115, 116. Witley, Reading, garden at, 82, 83. Wittersham House, garden at, 203, 204, 215, 215, 237, 238. Wood-walks, 41, 42, 42, 43, 44. Wooden gates, 194, 196, 204, 205. Woodgate, Four Oaks, Chapter II. Woodland gardens, Chapter II. Woodland walk, steps for, 98, 99. Wootton Lodge, Staffs, pool at, 146, 149. Wotton House, gate at, 200, 200. Wroxall Abbey, wall at, 108, 110. Wren, Sir Christopher, 108. Wrought-iron gates, Chapter XVII. Wych Cross Place, garden at, 162, 163, 200, 202, 223, Yew and other hedges, xix.—xxii., xxiv., xxvii., xxxiii. xxxvi., xix., xxxiii., xxxix., Chapter XIII., 27, 73. Yews, Irish, 60, 63. York stone paving, 171. Young, Thomas, designs by, 76, 78-80. Youth and Maiden figures, 220, 221. Yuccas, 40, 42.

Note.—The large numerals indicate illustrations of the subject indexed, and refer not to the Figure numbers, but to the pages on which illustrations will be found. The small numerals indicate references in the text.

COUNTRY LIFE

THE Journal for all interested in Domestic Architecture and in Country Life & Pursuits

NTIL the advent of COUNTRY LIFE, the premier illustrated paper, few people had realised the treasures possessed by Great Britain in the way of country houses and gardens. In some cases even the very owners did not fully know the artistic, architectural and antiquarian value of their own possessions; and in spite of the exercise of the most fastidious and scrupulous care in selection, the number of old houses possessing instructive and interesting features seems unending. One of the aims of Country Life is to enlarge public taste, and the surest way of doing this is to illustrate the best examples of all styles of building and garden-making. The houses themselves are often equalled in interest by the wealth of furniture and pictures which they enshrine. The historic mansion is, however, for the few, while there is a great and increasing public which is deeply interested in the "Lesser Country Houses of To-day." Articles on these, and on small houses of yesterday which have been repaired and enlarged to make them suit modern needs, appear every week in Country Life. Under the heading of "In the Garden," the latest developments of planting and garden design are illustrated, with notes by acknowledged experts.

By this means the public at large becomes acquainted with the best work of the architects and garden designers of the day, who have revived and are carrying to their logical development those traditions, so diverse and full of vitality, which give to each county its distinctive buildings and gardens. A study of the articles in Country Life in the two series of "Country Homes and Gardens Old and New" and "Lesser Country Houses of To-day" will equip the reader with a knowledge of all that is best in historic and modern homes, great and small.

The above notes on Country Life, appearing as they do at the end of a book dealing with the surroundings of the house, naturally emphasize that side of its activities. It is hardly needful to remind readers that the paper, week by week, presents country life in all its aspects, and illustrates agriculture, sport, and natural history with a fulness attempted by no other journal.

Published Weekly—Price SIXPENCE.

Subscription Prices-Per annum, post free, and including Double Numbers

INLAND - 29s. 2d. CANADA - 35s. 10d. Other Colonies and Foreign Countries, 48s. 0d.

Everyone interested in gardens and gardening should subscribe to

THE GARDEN

The Best, and one of the oldest, of the Horticultural Journals

ONE PENNY WEEKLY

TS articles, by recognized authorities, are practical and exhaustive, and deal with every subject connected with horticulture. The illustrations include new and uncommon plants, photographs of various gardens in the making, the grouping of flowers, and sketches depicting actual work in the garden. A charming illustration in colour of some new garden subject is presented with each copy, on alternate weeks.



A TYPICAL PICTURE FROM "THE GARDEN," ILLUSTRATING AN ARTICLE ON ROCK GARDENS.

An important feature of THE GARDEN is, that subscribers can have the benefit of the advice of the Editor and his staff of experts on the naming, diseases, or cultivation of any plant.

THE GARDEN is published every Thursday—Price One Penny—and can be obtained of all newsagents, bookstalls, etc., or by subscription, direct from the office, 20, Tavistock Street, Covent Garden, London, W.C.

Annual Subscription, including postage, Inland, 6/6; Foreign, 8/8

The Publisher will be glad to send a specimen copy containing a coloured plate on receipt of post card giving name and address.

A CATALOGUE OF BOOKS

PUBLISHED AT
THE OFFICES OF

"COUNTRY LIFE," LTD.

20, TAVISTOCK STREET COVENT GARDEN LONDON, W.C.



SMALL COUNTRY HOUSES OF TO-DAY

Edited by LAWRENCE WEAVER.

Second Edition now ready. Large quarto, gilt.

Price 15/- net.

By post (inland) 15/6. (Foreign and Colonial) 16/6.
224 pages and 300 illustrations.

THIS volume fills a distinctive place, because not only is the picked work of more than forty of the best architects



A FINE BRICK HOUSE. (Reduced specimen illustration.)

of the day shown by plan and photograph, but it is discussed in detail, frankly yet sympathetically. As the houses illustrated, nearly fifty in all, vary from large cottages costing £600 to

dignified country homes costing £5,000, all sorts of internal arrangement and architectural and garden treatment are brought under review. To all of moderate means who contemplate building a country house, this book will be of the utmost value.

Small Country Houses: Their Repair and Enlargement

FORTY EXAMPLES CHOSEN FROM FIVE CENTURIES.

By LAWRENCE WEAVER.

Large quarto, gilt.

Price 15/- net.

By post (inland), 15/6. (Foreign and Colonial) 16/6.

Nearly 250 pages and 300 illustrations.

THE growing tendency to rescue old buildings from neglect and the important problems which are raised by such work prompted the issue of this book. Detailed descriptions re-



A Fit Subject for Repair.

veal how houses of bygone days have been reequipped as modern needs demand, without destroying the witness they bear to the old traditions of build-

ing. Incidentally, the author has shown in how many cases the records of modest little houses have been preserved, and how intimately their local history is woven into the larger fabric of national history. The book is an invaluable guide to all who are desirous of repairing an old house, and who wish to achieve it in the right spirit.

THE HOUSE AND ITS EQUIPMENT

Edited by LAWRENCE WEAVER

Large quarto, gilt.

PRICE 15/- NET.

By post (inland) 15/6. Foreign and Colonial post, 16/6.
212 pages and 240 illustrations.

T is impossible that any one writer can deal with the many problems that arise out of the artistic and practical equipment of a house, at least with equal knowledge and sympathy. The scheme of this volume, with its forty-three chapters contributed by twenty-three experts of acknowledged ability, ensures the throwing of fresh light on scores of questions that concern the comfort and pleasure of everyone. To all who own a home, and are not wholly satisfied with it, and to all who contemplate improving an existing house, or building anew, this volume will be of the utmost value.

THE "COUNTRY LIFE" BOOK OF COTTAGES

(Costing from £150 to £600)

By LAWRENCE WEAVER

Large octavo; Cloth, gilt.

PRICE 5/- NET.

By post (inland), 5/5. Foreign and Colonial Post, 6/-.
Nearly 250 pages and 300 Illustrations and Plans.

THE word "cottage" has been grossly misused, especially in the titles of books where it is often employed to describe country houses which cost thousands. Save for a few gate lodges the buildings illustrated in this volume are truly cottages and none of a greater cost than £600 is included. Full consideration has been given to cottages of all types—for the rural labourer, the estate servant, the smallholder, the clerk who lives outside the town, the "week-ender" and those of limited means who want a permanent home of refined character in the country at the smallest possible cost. This book is indispensable to all estate owners, to everyone who contemplates building a cottage of any sort, and to all who are interested in Housing questions.

The finest Architectural Monograph ever published in this country.

WINDSOR CASTLE

AN ARCHITECTURAL HISTORY

Collected and written by command of Their Majesties

QUEEN VICTORIA
KING EDWARD VII. and
KING GEORGE V.

By W. H. ST. JOHN HOPE, Litt.D., D.C.L.

Imperial Quarto, in two sumptuous Volumes, and a Portfolio.

Bound in Half Sheepskin - £6 6 0 net

, Whole Sheepskin - 8 8 0 ,

" Full Morocco - 10 10 0 "

INDSOR CASTLE stands alone among the buildings of Great Britain. It is the greatest among our early fortresses and the most splendid of Royal Palaces. It includes within its walls a rich example of the most typically English phase of Gothic Architecture—St. George's Chapel, the home of the Knights of the oldest existing order of Chivalry in Christendom, the most noble Order of the Garter. The story of English building during eight centuries is very fully written in the stones of Windsor, but not so that everyone may read. The slow accretions of centuries are not easy to disentangle, and it needed the skill and wide archæological experience of Mr. W. H. St. John Hope to set out in its true proportions the fascinating story of the growth of this great architectural organism.

The edition is strictly limited to 1,050 numbered copies, of which nearly 400 were subscribed before publication. In no circumstances will the book be reprinted. It is illustrated by exquisite reproductions in colour of drawings by Paul Sandby; by a large number of collotype plates reproducing a unique collection of original drawings, engravings and photographs which show the Castle at every stage of its development; as well as by beautiful woodcuts, prepared expressly by the great engraver Orlando Jewitt for this History, when it was first projected. The Portfolio contains a notable reproduction of Norden's View of Windsor and a complete series of plans, specially printed in fourteen colours, which show the dates of all the buildings in the Castle and their successive changes. Many of the illustrations are reproduced for the first time, by special permission of His Majesty the King, from originals in the Royal Library at Windsor.

The text is printed from new type on pure rag paper, specially made for this edition, and the volumes are produced in a way which does the fullest justice to a work of national importance.

A New Series of Architectural Books.

THE PROPRIETORS OF "COUNTRY LIFE" have pleasure in announcing a new and important series of Architectural Monographs under the general editorship of Lawrence Weaver, F.S.A., Hon. A.R.I.B.A., of which "Houses and Gardens by E. L. Lutyens" is the first volume.

The series will include books by authors of acknowledged authority on the work of great architects of the past, such as the Brothers Adam, and great craftsmen like Grinling Gibbons; on the architectural development of the minor arts of Plasterwork, Ironwork, and the like; and on individual features of buildings, such as Fireplaces and Chimneypieces, Staircases and Panelled Rooms. The volumes will be uniform in size, type and style of binding. Two are now in the press, and six more are in active preparation. The prices at which they are published will vary with the number of pages in each volume, but in all cases will be much lower than ever before attempted for books so fully and finely illustrated.

It is hoped that the following Monographs will be published in 1914-15. Fully illustrated Prospectuses will be forwarded, as issued, to anyone making application.

GRINLING GIBBONS AND THE WOODWORK OF HIS AGE [1648-1720), BY H. AVRAY TIPPING, M.A., F.S.A. [In the Press.

THE WORK OF THE BROTHERS ADAM, BY ARTHUR T. BOLTON, F.S.A., F.R.I.B.A. [In the Press.

DECORATIVE PLASTERWORK, BY LAURENCE TURNER.

[In the Press.

WROUGHT IRONWORK: GATES, RAILINGS AND SCREENS, BY MAXWELL AYRTON.

ENGLISH PANELLED ROOMS, BY W. H. WARD, M.A.Cantab., A.R.I.B.A.

ENGLISH FIREPLACES AND CHIMNEYPIECES, BY WALTER H. GODFREY.

STAIRCASES: THEIR DESIGN AND DECORATION.

HOUSES AND GARDENS BY E. L. LUTYENS

Described and criticised by LAWRENCE WEAVER

Large crown folio (16 by 11), bound in quarter buckram, gilt.

Nearly 400 pages and 600 superb illustrations.

PRICE 25/- NET.

Inland Postage 10d. extra, Foreign and Colonial Post 2/- extra.



HIS book is lavishly illustrated with photographs of about eighty of Mr. Lutyens' most typical houses and gardens, many of which have never previously been published. Interspersed in the text is a large number of plans, and there is an appendix of 22 pages giving a valuable series of scale drawings of typical buildings. The subjects are accompanied by descriptions and critical appreciations which incidentally throw considerable light on the general development of the domestic

building of to-day. In all respects the book is the most important and interesting monograph on the work of an architect yet published.

The Morning Post says: "The publication of Mr. Weaver's work on the buildings and career of Mr. Lutyens is . . . an event in the world of architecture."

The Manchester Guardian says: "It is only when we see a publication such as this that we realise what quality characterises some of the building of to-day. Abundantly and splendidly illustrated this book shows the work of a great master, whose influence is even greater than his most enthusiastic admirers can appreciate."

In English Homes

Illustrating the architectural character, decorations and furniture of some of the most notable Houses of England

Volumes I., II. and III.

AND THE RECENTLY PUBLISHED FOURTH VOLUME

ENGLISH HOMES of the EARLY RENAISSANCE

(ELIZABETHAN AND JACOBEAN HOUSES AND GARDENS)

Edited by H. AVRAY TIPPING, M.A., F.S.A.


Price £2 2s. net each.

By post £2 3s.

THESE four notable volumes form together an unequalled pictorial survey of the domestic architecture of England of every style and period. They are, moreover, a treasury, not only of the life stories of the notable men and women who have lived in our historic homes, but of those county and village traditions which throw so much light on the larger issues that have made the history of the nation.

[&]quot;A veritable revelation of the wealth of internal adornments, architectural and other, contained in the great country mansions of England. To turn over the pages is to obtain keen pleasure, as well as enlightenment, concerning a treasury of domestic art and archæology, which to a large extent is kept closed from the common eye."—Scotsman.

IN ENGLISH HOMES



A RECESS AT SPEKE HALL, LANCASHIRE.
(Reduced specimen illustration.)

"In English Homes comes as something of a revelation. One may have a general idea, or even some particular knowledge of the splendours of architecture, decoration, furniture, and works of art appertaining to our country mansions, and yet be astonished at all the taste and magnificence represented in the profusion of excellent photographs."—Morning Post.

GARDENS OLD AND NEW

(The Country House and its Garden Environment)

Edited by H. AVRAY TIPPING, M.A., F.S.A. Handsomely bound in cloth, gilt edges

Volumes 1., II., and III.

Price £2 2s. net each


By post £2 3s.

THESE three volumes illustrate the relationship between house and garden, and the beauties of every type of garden, both formal and natural, in a way never before attempted. They afford a complete survey of the whole history of garden design and garden architecture, considered from every point of view, historical, artistic and horticultural.

"The title given to this handsome book hardly does justice to the contents. The gardens that it so lavishly portrays, charming as they are, would be without life and meaning, except as settings to the priceless old English halls, manor-houses, and castles that are centred in each well-chosen view. There must be almost a thousand of these fascinating pictures in this one volume, and all, with one exception, have been chosen from sixty-four famous places, so that one does not merely have a passing glimpse of a multitude of widely-scattered scenes, but, on an average, fifteen careful outdoor studies of each beautiful house and its surroundings."

-Morning Post.

Gardens Old and New



REDUCED SPECIMEN ILLUSTRATION.

"To those who are unacquainted with the wealth of English gardens, these books will be in a way a revelation. Other countries may be justly proud of their gardens, but none can show such a variety or such wealth as England, and never before has this wealth been so liberally or so artistically displayed."—Scotsman.

Our Common Sea-Birds

CORMORANTS, TERNS, GULLS, SKUAS, PETRELS, AND AUKS.

By PERCY R. LOWE, B.A., M.B., B.C.

With Chapters by Bentley Beetham, Francis Heatherley, W. R. Ogilvie-Grant, Oliver G. Pike, W. R. Pycraft, A. J. Roberts, etc.

Large quarto, cloth, gilt, with over 300 pages and nearly 250 illustrations.

Price 15/- Net. Inland postage 7d. extra.



(Reduced specimen illustration.)

Unlike the majority of books dealing with birds, this volume is of interest to the general reader and to the student of ornithology alike. It is a book that enables the reader to identify our sea-birds by name, to understand their movements, their habits, their nests, and their eggs.

Dr. Lowe, during many yachting trips round the British Islands, in the Mediterranean, and across the Atlantic, has had exceptional opportunities of studying the habits and lifehistories of our sea-birds, and this book, in addition to embodying much

valuable information from the latest records, contains a large number of new facts and original theories of intense interest to all. The Introductory pages and the chapters on the Flight of Birds deserve the closest attention.

The Illustrations are of extraordinary merit and beauty. They exhibit in a marked degree the result not only of the skill, knowledge, and ingenuity of the photographers, but of their high enthusiasm and unwearying patience.

PASTIME WITH GOOD COMPANY

Pictured by G. D. ARMOUR. With an Introduction by Horace G. HUTCHINSON.

Royal quarto, tastefully bound, containing over fifty choice plates.

PRICE 15/- NET.

Inland Postage 6d. extra.

THIS volume is sure of a warm welcome from every Sportsman and Sportswoman of to-day. In the beautiful picture gallery disclosed through its pages, Mr. Armour presents a wonderfully representative collection of his art. Whether it is the field in "full cry," the grouse coming over the heather, the polo player dashing towards the goal, or the otto hound surging through the rapids; all are portrayed with individuality and fidelity, by means which have the appealing merit of simplicity and directness. The plates are perfect specimens of pictorial art. Each one deserves, and, indeed, demands a frame.

A Book that should appeal to all Nature Lovers

THE PEREGRINE FALCON AT THE EYRIE

By FRANCIS HEATHERLEY, F.R.C.S.

Illustrated throughout with photographs by the Author and C. J. KING. Quarto, cloth, gilt.

PRICE 5/- NET. By Inland Post 5/6

THIS fascinating book on the Peregrine Falcon—the grandest bird of prey left in England—combines the salient facts of almost innumerable field notes, written at the eyrie itself. It is a book that should appeal with irresistible force to all true nature lovers. Many striking and unexpected facts were revealed to the author as a result of unwearying patience in a diminutive hut slung from the precipice of a lonely islet. These records are here set forth in a wonderful narrative which discloses the life history of the Peregrine Falcon from the moment of its hatching to the day it finally leaves the eyrie.

THE

"Country Life" Library of Sport

Edited by HORACE G. HUTCHINSON.

Price 12/6 net each volume. By post 6d. extra.

A Series devoted to Sport and Pastime; each branch being dealt with by the most qualified experts on the subjects which they have made peculiarly their own

CRICKET With over 80 Illustrations taken from the most interesting of the old cricketing prints. One Volume.

FISHING With Coloured Plates of Salmon and Trout Flies. Over 250 full-page Illustrations and numerous diagrams. In Two Volumes.

SHOOTING The breeding, rearing and shooting of pheasants, partridges, and wild duck. In Two Volumes.

BIG GAME SHOOTING With over 200 Illustrations from photographs, showing animals in their actual habitat and natural environment. In Two Volumes.

POLO, PAST AND PRESENT The game is traced from its cradle in Persia, many centuries back, up to the present time. Profusely Illustrated. In One Volume.

"Mr. Hutchinson and his colleagues have done their work thoroughly."-The Globe.



GOLF GREENS AND GREEN KEEPING

By HORACE G. HUTCHINSON.

Cheap Edition 5s. net. By post 5s. 4d.

"The practical worth of the volume is nearly equal to the combined worth of all the books that have been written on the theory and practice of golf."—Yorkshire Post.

THE CENTURY BOOK OF GARDENING.

Edited by E. T. Cook. A comprehensive work for every lover of the garden. 624 pages, with about 600 Illustrations, many of them full-page 4to (12 in. by $8\frac{1}{2}$ in:). 21s. Net, by post 21s. 10d.

GARDENING FOR BEGINNERS.

(A Handbook to the Garden). By E. T. Cook. With Coloured Plates, and over 200 Illustrations, plans, and diagrams from photographs of selected specimens of Plants, Flowers, Trees, Shrubs, Fruits, etc. Sixth Edition. 12s. 6d. Net, by post 12s. 11d.

WALL AND WATER GARDENS.

By Gertrude Jekyll. Containing instructions and hints on the cultivation of suitable plants on dry walls, rock walls, in streams, marsh pools, lakes, ponds, tanks, and water margins. With nearly 200 Illustrations, Plans, Diagrams, etc. Fifth Edition. Large 8vo. over 200 pages. 12s. 6d. Net, by post 12s. 11d.

COLOUR SCHEMES FOR THE FLOWER GARDEN. By GERTRUDE JEKYLL. With over 100 Illustrations and Planting Plans. Third Edition. 12s. 6d. Net, by post 12s. 10d.

TREES & SHRUBS FOR ENGLISH GARDENS.

By E. T. COOK. 12s. 6d. Net, by post 12s. 11d.

MY GARDEN.

By Eden Phillpotts.

60 full-page Illustrations. Cheap Edition, 6s. Net, by post 6s. 4d.

THE FRUIT GARDEN.

By George Bunyard and Owen Thomas. 507 pages. Size, $10\frac{1}{2}$ in. by $7\frac{1}{2}$ in. 12s. 6d. Net, by post 12s. 11d.

A GARDEN IN VENICE.

By F. Eden. An account of the author's beautiful garden on the Island of the Guidecca at Venice. With 21 Collotype and 50 other Illustrations. Parchment, limp.' 10s. 6d. Net, by post 10s. 10d.

THE DISEASES OF TREES.

By Professor R. Hartig. Royal 8vo. 10s. 6d. Net, by post 10s. 11d.

THE UNHEATED GREENHOUSE.

By Mrs. K. L. Davidson. Cheap Edition, 5s. Net, by post 5s. 4d.

LILIES FOR ENGLISH GARDENS. [8s. 10d. Written and compiled by GERTRUDE JEKYLL. 8s. 6d. Net, by post.

CHILDREN AND GARDENS

By Gertrude Jekyll. A garden book for children. Thoroughly practical and full of pictures.
6s. Net, by post 6s. 5d.

ROCK AND WATER GARDENS

THEIR MAKING AND PLANTING.

With Chapters on Wall and Heath Gardens. By F. H. MEYER.

Edited by E. T. Cook.

6s. Net, by post 6s. 4d.

SEASIDE PLANTING OF TREES & SHRUBS. By Alfred Gaut, F.R.H.S. An interesting and instructive book

dealing with a phase of arboriculture hitherto not touched upon. It is profusely illustrated, and diagrams are given explaining certain details.

5s. Net, by post 5s. 6d.

THE BOOK OF BRITISH FERNS.

By Chas. T. Druery, F.L.S., V.M.H., President of the British Pteridological Society.

3s. 6d. Net, by post 3s. 9d.

THE HARDY FLOWER BOOK.

By E. H. JENKINS. 50 Illustrations and coloured frontispiece.

2s. 6d. Net, by post 2s. 10d.

THE SMALL ROCK GARDEN.

By E. H. JENKINS. Over 50 Illustrations and coloured frontispiece. 2s. 6d. Net, by post 2s. 10d.

GARDENING MADE EASY.

By E. T. Cook. 200 pages and 23 Illustrations. The A.B.C. of gardening. 1s. Net. Cloth, 1s. 6d. Net, by post 3d. extra.

ROSE GROWING MADE EASY.

By E. T. Cook. A simple Rose Guide for amateurs, freely illustrated with diagrams showing ways of increasing, pruning and protecting roses.

1s. Net. Cloth, 1s. 6d. Net, by post 3d. extra.

VEGETABLE GROWING MADE EASY.

A simple and concise handbook on the cultivation of Vegetables. By OWEN THOMAS, F.R.H.S., V.M.H., and GEORGE WYTHES, F.R.H.S., V.M.H., and THE COOKING OF VEGETABLES by Mrs. Frances Keyzer. 1s. Net. Cloth, 1s. 6d. Net. Postage 3d. extra.

THE ENGLISH VEGETABLE GARDEN.

By various Experts. Cheap Edition, 5s. Net, by post 5s. 6d.

FRUIT-GROWING FOR BEGINNERS.

A simple and concise handbook on the cultivation of Fruit. By F. W. Harvey. 1s. Net. Cloth, 1s. 6d. Net. Postage 3d. extra.

POEMS. By Dorothy Frances Gurney. 5s. Net, by post 5s. 4d.

ENGLISH LEADWORK; ITS ART & HISTORY.

By LAWRENCE WEAVER. 25s. Net, by post 25s. 7d.

THE FIRST AND CHIEF GROUNDES OF ARCHITECTURE.

By John Shute, 1563, a fac-simile edition of the first book on Architecture published in England, with a historical and critical introducduction by Lawrence Weaver. 15s. Net, by post 15s. 6d.

CAUSERIES ON ENGLISH PEWTER.

By Antonio de Navarro A book for all lovers of the Pewterer's Art.

10s. 6d. Net, by post 11s.

ANIMAL LIFE BY THE SEA-SHORE.

By G. A. BOULENGER, LL.D., D.Sc., Ph.D., F.R.S., F.Z.S., and C. L. BOULENGER, M.A., D.Sc., F.Z.S. Nearly 100 Illustrations.

5s. Net, by post 5s. 4d.

TOYS OF OTHER DAYS.

By Mrs. Nevill Jackson. Cheap Edition, 5s. Net. Edition de Luxe, 21s. Net, by post 6d. extra.

ECONOMIES IN DAIRY FARMING.

An important Work on Dairying by Ernest Mathews (the well-known Judge and Expert) 7s. 6d. Net, by post 7s. 10d.

PHOTOGRAPHY FOR BEGINNERS.

This is an instructive and practical book, worded clearly but non-scientifically, for the tyro camera user.

1s. Net. Cloth, 1s. 6d. Net, by post 3d. extra.

FRENCH HOUSEHOLD COOKING.

By Mrs. Frances Keyzer. Shows how simple and inexpensive is the art of cooking as the French understand it.

1s. Net. Cloth, 1s. 6d. Net, by post 3d. extra.









