





Digitized by the Internet Archive
in 2013

Parish Churches.

LONDON :
STEVENS AND CO., PRINTERS, BELL YARD,
TEMPLE BAR.

Parish Churches;

BEING

PERSPECTIVE VIEWS

OF

ENGLISH ECCLESIASTICAL STRUCTURES:

ACCOMPANIED BY

PLANS DRAWN TO A UNIFORM SCALE,

AND

LETTER-PRESS DESCRIPTIONS.



BY

RAPHAEL AND J. ARTHUR BRANDON,

Architects,

AUTHORS OF "AN ANALYSIS OF GOTHICK ARCHITECTURE,"

"OPEN TIMBER ROOFS OF THE MIDDLE AGES,"

ETC.


VOLUME I.

LONDON:

DAVID BOGUE, 86, FLEET STREET;

SOLD ALSO BY GEORGE BELL, 186, FLEET STREET.

MDCCCLI.





THIS VOLUME,

PROJECTED, COMMENCED, AND ALMOST COMPLETED

BY

TWO BROTHERS,

Is Dedicated

TO

THE BELOVED MEMORY OF

ONE BROTHER,

BY

THE SURVIVOR.



THIS Work, by Raphael Brandon, and
J. Arthur Brandon, Architects, was origin-
ally published in Twelve Parts: of these,
Part I. appeared March, 1846, and Part XI.
November 1st, 1847. J. Arthur Brandon,
after a few days' illness, departed this life,
December 11th, 1847, in the 26th year of
his age.

C O N T E N T S.

	PAGE
LITTLE CASTERTON CHURCH, RUTLANDSHIRE	9
AYSTON CHURCH, RUTLANDSHIRE	11
DUDDINGTON CHURCH, NORTHAMPTONSHIRE	13
HERNE CHURCH, KENT	15
HOWELL CHURCH, LINCOLNSHIRE	17
BRAMPTON CHURCH, NORTHAMPTONSHIRE	19
ETON CHURCH, NORTHAMPTONSHIRE	21
TEMPLE BALSAL CHURCH, WARWICKSHIRE	23
WARMINGTON CHURCH, NORTHAMPTONSHIRE	25
SOUTHFLEET CHURCH, KENT	27
FLOORE CHURCH, NORTHAMPTONSHIRE	29
NORTH MIMS CHURCH, HERTFORDSHIRE	31
MANTON CHURCH, RUTLANDSHIRE	33
WESTWICK CHURCH, NORFOLK	35
TRUNCH CHURCH, NORFOLK	37
BAENWELL CHURCH, NORTHAMPTONSHIRE	39
LONG STANTON CHURCH, CAMBRIDGESHIRE	41
WORSTEAD CHURCH, NORFOLK	43
FILBY CHURCH, NORFOLK	45
MARTHAM CHURCH, NORFOLK	47
HINGHAM CHURCH, NORFOLK	49
DEOPHAM CHURCH, NORFOLK	51


	PAGE
RICKENHALL CHURCH, SUFFOLK	53
MORLEY ST. BOTOLPH CHURCH, NORFOLK	55
WOOLPIT CHURCH, SUFFOLK	57
FLEET CHURCH, LINCOLNSHIRE	59
DONINGTON CHURCH, LINCOLNSHIRE	61
ACHURCH CHURCH, NORTHAMPTONSHIRE	63
STANWICK CHURCH, NORTHAMPTONSHIRE	65
ALDWINKLE CHURCH, NORTHAMPTONSHIRE	67
BISHOP'S LYDEARD CHURCH, SOMERSETSHIRE	69
LECKHAMPTON CHURCH, GLOUCESTERSHIRE	71
ISLIP CHURCH, NORTHAMPTONSHIRE	73








LITTLE CASTERTON CHURCH, RUTLANDSHIRE.



LITTLE CASTERTON CHURCH, RUTLANDSHIRE.

PELUSH, CHURCH.





Little Casterton Church, Rutlandshire.



THIS Church appears to have been rebuilt in the Early English style: that one existed here previously is unquestionable, as the nave-piers and arches are of Norman character.

With the exception of the clear-story, which is Perpendicular, this Structure is a simple yet admirable model for a small Parish Church.

The effect of the west end with its belfry is much injured by the addition of the clear-story, but, as originally designed, it must have formed a very beautiful specimen of the most appropriate arrangement for so small a Church.*

In the south wall of the Chancel is a very good piscina of Decorated character; and immediately beneath it, on the floor, is another formed by a large four-leaved flower with holes in the centre for the drain.

A piscina in this position is very unusual, and in the present instance it probably dates back to the beginning of the thirteenth century, if it be not contemporary with the nave-piers and arches.

* The crosses which terminate the gables are all similar, and will be found illustrated in "Brandon's Analysis of Gothick Architecture," (Section I. Early English, Plate XVI.)

On the Chancel floor is a very excellent (though unfortunately rather mutilated) brass of a Knight and his Lady; the Knight bearing the collar of S.S.

The lower part of the rood-screen still remains, and exhibits some very good carving.


In the south wall of the south aisle is an interesting sepulchral recess containing a cross on a coped stone of Early English character; there is also a piscina in this wall.

This Church will afford accommodation for about 160 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	32	0
Width of Chancel	14	8
Length of Nave	31	6
Width of Nave	15	4
Length of North Aisle	32	0
Width of North Aisle	7	7
Length of South Aisle	32	0
Width of South Aisle	7	9





PLAN OF LITTLE CASTERTON CHURCH,
RUTLANDSHIRE

SCALE OF 0 10 20 40 60 FEET



AYSTON CHURCH, RUTLANDSHIRE.

Ayston Church, Rutlandshire.



WITH the exception of parts of the tower, and two windows, which are Decorated, this Church is of the Perpendicular style externally, though in the interior there are evidences of a much earlier origin, which exhibit themselves in the Semi-Norman piers and arches of the nave; the arches on the north side are circular, and those on the south segmental pointed.

The Church is built entirely of dressed stone, and is beautifully situated amidst magnificent trees.

The Chancel, which is very regular in its composition, is rather more ornamented than the rest of the Edifice, having an enriched string-course running all round it under the parapet, and two crocketed pinnacles at the north-east and south-east angles. It is lighted by a five-light window at the east end, and by a three-light and a two-light window on the north and south sides; the sills of the westernmost windows, north and south, being lower than the others.

The Chancel arch is supported on corbels, the upper parts of which alone remain. The ascent to the rood-loft, now destroyed, was on the north.

There are remains of excellent stained glass in some of the windows.

The tower contains three bells; the staircase to the belfry is at the south-west angle.


In the Church-yard, near the south aisle, is a monumental slab, on which are carved the effigies of a Knight with his shield and sword lying over him, and his lady by his side; they are now very much defaced, and it does not appear to be known whom they represent; the absurd tradition in the village is, that two twin brothers were born united together, and lived in these parts, and that after their decease, these, their effigies, were placed over their grave.

The Church will accommodate about 200 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	27	0
Width of Chancel	15	6
Length of Nave	38	10
Width of Nave	15	9
Width of North Aisle	5	8
Width of South Aisle	8	6





PLAN OF AYSTON CHURCH,
RUTLANDSHIRE.

SCALE OF 10 20 30 40 50 60 FEET.



BUDDINGTON CHURCH, NORTHAMPTONSHIRE

PARISH CHURCHES

Duddington Church,
Northamptonshire.



THIS Church appears to have been rebuilt very shortly after its first erection, for while the north aisle is of Norman workmanship, all the rest of the Church was constructed during the period of transition from Norman to Early English. The plan is valuable, as it probably remains exactly as it was first designed, without any subsequent alteration or addition. The tower, situated at the east end of the south aisle, is of the same date as the main body of the Church. It has no staircase turret; the ascent to the upper stages being by means of a wide ladder; this fact, were other features wanting, would help to indicate its early origin.

The addition of a Perpendicular clear-story, and the lowering of the nave roof, have done much to destroy the original character of the Building.

The door in the south porch has some curious but very rude iron work covering the whole of its surface.

The Church contains accommodation for about 270 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	38	0
Width of Chancel	15	4
Length of Nave	40	6
Width of Nave	15	4
Width of North Aisle	7	0
Width of South Aisle	9	2






PLAN OF DUDDINGTON CHURCH,
NORTHAMPTONSHIRE.

SCALE OF
10 20 30 40 50 FEET



INTERIOR OF TOWER, HERNE CHURCH, KENT





PARISH CHURCHES

HERNE CHURCH, KENT.

DRAWN AND ENGRAVED BY F. J. A. BRADSHAW

Herne Church,

Kent.



THE principal feature of interest in this Church is its noble tower and elegant staircase turret, situated very happily at the west end of the north aisle. The time of its erection is the early part of the Decorated period; the lower stage, which is open to the Church, is groined over, and answers the purpose of a baptistery, and contains a very fine font of Perpendicular character. The corbels supporting the ribs of the groin are extremely beautiful, and present valuable examples of the head dresses of the period. The construction of the tower is remarkable and well worthy of notice, having been built entirely separate from the main body of the Church, with its buttresses coming down boldly into the interior: the clear-story, instead of being a continuation of the wall of the tower, is in this instance carried on an arch, as shown in the interior view.*

The body of the Church partakes of the same character as the tower, but the Chancel, as well as the two large Chapels, appear to have been restored at a subsequent period. The curious projection of the north wall of the Chancel is to make room for a tomb

* One of the beautiful windows of the Tower is illustrated in "Brandon's Analysis of Gothick Architecture," (Section I. Decorated, Plate XX.)

which is placed under the window, and is probably that of the founder, or at any rate a great benefactor to the Church.

The sedilia of three seats and a piscina remain in the south wall.

The screen dividing the north Chapel from the aisle is a mixture of Perpendicular and Elizabethan, and does not possess much interest.

The Church contains some fine and curious brasses, both ecclesiastical and civil, and also many of its old encaustic tiles. A hagioscope, as shown on the plan, exists in the north Chapel.


The Church, independent of the Chapels and tower, offers accommodation for about 820 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	41	0
Width of Chancel	20	6
Length of Nave	71	0
Width of Nave	15	9
Width of North Aisle	22	6
Width of South Aisle	15	8



PLAN OF HERNE CHURCH.
KENT.



SCALE OF $\frac{1}{2}$ FEET



HOWELL CHURCH, LINCOLNSHIRE

PARISH CHURCHES

J. K. Colling lith.

Howell Church, Lincolnshire.



THE earliest parts of this structure are the piers and arches of the nave, which are of late Norman character, and very plain.

The Chancel is lighted by a small two-light Decorated window at the east, and by two similar windows at the south; the sill of the easternmost window on the south side is lowered to form the sedilia. The Chancel arch, if it ever existed, has been cut away. There is a good specimen of an incised slab on the floor.

The north Chapel must have been added during the Decorated period, when most of the windows appear to have been inserted. In the north wall of this Chapel, between the two windows, is a very interesting sepulchral recess. The font is plain and of Decorated character. The porch is also Decorated. Some of the old seats still exist in the Church, though much mutilated.*

Externally, though plain, this Church is a valuable specimen, especially for its bell gable, and for the general arrangement of the west end.

The Church will accommodate about 130 worshippers.


* A finial from one of these seats will be found illustrated in "Brandon's Analysis of Gothic Architecture," Section II., Woodwork, Plate 16.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	24	0
Width of Chancel	15	0
Length of Nave	34	0
Width of Nave	13	9
Width of North Aisle	6	0
Length of North Chapel	21	9
Width of North Chapel	10	4




PLAN OF HOWELL CHURCH
LINCOLNSHIRE



SCALE OF 10 20 30 40 FEET



BRAMPTON CHURCH, NORTHAMPTONSHIRE.



Brampton Church,
Northamptonshire.



WITH the exception of the Chancel, the whole of this beautiful Church is Perpendicular: remarkable for its regularity, it presents a striking instance of how much may be effected with but little ornament, if judiciously arranged. The Building consists of a Chancel, nave, and aisles, north and south porch, and a noble west steeple, the simplicity and severity of which are only to be exceeded by its beauty and magnificent appearance. There is no western entrance. Some of the old seats may still be seen in the nave, but they are quite plain, and devoid of architectural interest.


The Chancel is of late Early English character, which was probably the style of the original Building. The windows are interesting, and possess good mouldings; especially the east window which is of four lights, and of rather peculiar design. There is a north Priest's door.

The Church offers accommodation for about 418 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	31	10
Width of Chancel	18	3
Length of Nave	46	6
Width of Nave	19	0
Width of North Aisle	8	3
Width of South Aisle	8	8





PLAN OF BRAMPTON CHURCH,
NORTHAMPTONSHIRE.

SCALE OF 60 FEET





ETTON CHURCH, NORTHAMPTONSHIRE.

Etton Church,
Northamptonshire.



A SIMPLE and pure specimen of an Early English Church, the whole being of one date, with the exception perhaps of the clear-story, which was probably added towards the close of the style.

The tower is surmounted by a plain stone broach spire with two rows of lights alternated. The arrangement of the broach is rather peculiar.

The windows in the aisles are all similar, and consist of two lancets with a circle above, the whole being under one dripstone. The east end of the north aisle appears to have opened formerly into a chapel, which communicated also by an arch with the Chancel: the chapel however is now destroyed and the arches are blocked up, though still visible. An altar formerly stood at the end of the south aisle, and here some highly interesting and beautiful distemper painting, in a tolerable state of preservation, has been lately discovered; it extends over the entire surface of the wall, with the exception of the place occupied by the altar. The piscina in the south aisle occupies its usual position, and there is also a double piscina in the Chancel, and adjoining this last are sedilia of three seats of simple yet excellent design. In the same wall of the Chancel occurs the Priest's door and

a lychroscope. In the north wall there remains the door which opened into a vestry, now destroyed, also a very small aumbrie.

The east window consists of five lancets under one arch; the arrangement is peculiar and effective; the other windows in the Chancel are partly filled with the incipient and characteristic tracery of the Early English period.


On the east jamb of the south doorway occurs the rather unusual feature of a dedication cross. It consists in this instance of a small diamond-shaped piece of purbeck of about the usual size of a window quarrel, on which has been sunk a cross fleury; the whole being let into the jamb of the door.

This Church affords accommodation for about 245 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	35	9
Width of Chancel	14	0
Length of Nave	37	6
Width of Nave	14	6
Width of North Aisle	11	9
Width of South Aisle	11	6





PLAN OF ETTON CHURCH.
NORTHAMPTONSHIRE.


SCALE OF
50 FEET



S.W. VIEW OF TEMPLE BALSAL CHURCH

PARISH CHURCHES

DRAWN & MEASURED BY R. & J. A. BRANDON



J.K. Gally lith.

TEMPLE BALSAL CHURCH, WARWICKSHIRE.

PATISH CHURCHES

DRAWN & MEASURED BY R. & J. A. BRANTON

Temple Balsal Church,
Warwickshire.



THIS truly elegant specimen of the early Decorated style of architecture was formerly the Church belonging to the preceptory of the Knight Templars at their manor of Balsal. After the suppression of the Order, (Edw. II. 1312,) the Church was suffered to fall into a state of dilapidation, and it so remained until the year 1677, when it was restored in accordance with the will of Lady Catherine Leveson, to whom the manor had descended: she having devised the whole of this property in trust for the building and endowment of an almshouse for the perpetual sustenance of aged and infirm females, by the same instrument directed that the Church should be put into a complete state of repair.

The roof, gable-terminations, and the upper part of the tower were probably rebuilt at this period; the rather unusual arrangement of the latter constitutes one of the most interesting features in the Building.

The south doorway is now blocked up; it was originally covered by a stone porch, of which the springers for the groined roof still remain.

The windows generally throughout the Church are of extraordinary


beauty, and only two are similar in design. The east window is a magnificent opening of five lights, and offers some little peculiarity in the construction of the tracery. At the west end there are two windows, the lower one of five lights, but considerably smaller than that in the Chancel, and above in the gable is an elegant wheel or circular window. The two most easterly windows on the north side are higher than the others, and therefore probably a difference in level helped to indicate the distinction between the Chancel and the nave. On the south side the most westerly window in the Chancel is slychnoscopic, the other is rather stilted to make room for the piscina and sedilia: the latter of three seats is richly wrought with mouldings, and of most exquisite design.

The Church will afford accommodation for about 220 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length	93	0
Width	30	1





PLAN OF TEMPLE BALSAL CHURCH
WARWICKSHIRE

SCALE OF 10 20 30 40 50 FEET



WARMINGTON CHURCH, NORTHAMPTONSHIRE

PARISH CHURCHES.

J.K. Colling del.

Warmington Church, Northamptonshire.



THIS is a very interesting Church, of pure Early English character, with a clear-story also of the same date. The tower at the west end of the nave is a noble structure and deserving of especial attention. The west doorway is of unusual magnificence, with four rows of shafts, and richly ornamented with dog-tooth and circular flowers.* The belfry windows partake of the same degree of richness, and the beautiful broach spire with its three rows of non-alternated spire-lights is equally deserving of commendation; these latter are surmounted by crosses of elegant design. The large circular openings which occur on three sides of the tower form a feature peculiar to this neighbourhood; they are found in several of the surrounding Churches.

The south aisle is lighted at the west end by a perpendicular window of three lights, and at the east by a window of five lights, apparently original, and consisting simply of four mullions running quite up to the soffit of the arch. A series of beautiful triplets of good proportions light the south side, the two most easterly being

* This Doorway is illustrated in "Brandon's Analysis of Gothick Architecture" (Section I. Early English, Plate 21).

enriched with dog-tooth. Over the porch there is a small quatrefoil opening. The windows on the north are principally couplets of lancets with a circle above, the whole under one dripstone; one of these windows is placed over the north doorway, eurtailed of its proper proportion to make room for the porch roof.

The nave is groined in wood, the ribs starting from stone springers; it is probable that the vaulting was not continued in stone from an apprehended weakness in the walls; the ribs spring from small shafts terminating in capitals of the most exquisite foliage, which are supported on corbels chiefly representing heads of Bishops and Priests. Similar shafts with equally beautiful foliage supported the second order of mouldings of the Chancel arch, of which the capitals alone remain.


The extreme flatness of the roofs as well of the Chancel as the nave, aisles and porches is deserving of notice, there being every reason to believe that they are of the original pitch. An old oak chest clamped with iron, may still be seen in the Chancel.

The Church will accommodate about 550 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	42	3
Width of Chancel	19	6
Length of Nave	74	6
Width of Nave	17	0
Width of North Aisle	13	6
Width of South Aisle	13	6

PLAN OF WARMINGTON CHURCH.
NORTHAMPTONSHIRE



SCALE OF 10 20 30 40 FEET

PARTS CHURCHES



SOUTHFLEET CHURCH . KENT

PERISH - CHURCHES

J. E. Colver del.

Southfleet Church,

Kent.



THE whole of this spacious and very interesting Building is of pure Decorated character.

The west tower and staircase turret at the north-east angle is of the kind so frequently met with in this part of Kent; remarkable for extreme plainness, and entirely devoid of buttresses, it still produces an excellent effect, in consequence of its boldness of outline and solidity of construction; in this instance the appearance of the tower is the more effective, because the aisles do not extend so far westward as the nave, and it is thereby detached, as it were, from the body of the Church.

The windows generally in this Church are excellent in design and well moulded; the east window of the Chancel is of five lights, and several square-headed windows occur in various parts of the Church.

The plan of the Church is peculiar, owing to the shortness of the aisles already alluded to; this however does not mar the general good effect of the interior; the vestry with its door into the Chancel is original, and of the same date as the rest of the Church, though it has undergone some restorations during the Perpendicular period. It is worthy of notice that it contains in the south wall a water drain,

yet it is hardly possible that it could ever have been used as a chapel.* The piscina and sedilia of three seats still remain in the south wall of the Chancel; the sedilia are enriched with purbeck shafts and crocketed canopies; they are both of Decorated character. A few of the old misericords are left, but are not remarkable for their carving. The Chancel still contains a fine collection of beautiful encaustic tiles.

The Church is rich in monuments and sepulchral brasses; five of the latter are in tolerable preservation, and the stone matrices of many others are scattered about the pavement. In the south aisle are the remains of a very early Decorated wooden screen, the mouldings of which are nearly similar to the beautiful one still existing in Northfleet Church.

The font is octagonal, of early Perpendicular character; it is well sculptured and forms a very good specimen.


A sill mould runs uninterruptedly inside the Church, under the windows and over the doorways, and adds very much to the general good effect. Relics of the stained glass that once filled the windows attest the pristine magnificence of the Building.

The Church will accommodate about 500 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	43	0
Width of Chancel	20	6
Length of Nave	60	0
Width of Nave	21	6
Width of North Aisle	18	6
Width of South Aisle	17	6

* A similar drain occupies the same position in the beautiful vestry of Willingham Church, Cambridgeshire.




PLAN OF SOUTHFLEET CHURCH,
KENT.

SCALE
10 20 30 40 FEET

PARISH CHURCHES

DRAWN & MEASURED BY R. E. J. BRANDON



FLOORE CHURCH, NORTHAMPTONSHIRE

PARISH CHURCHES.

DRAWN & MEASURED BY R. & J.A. BRANSON

Floore Church,
Northamptonshire.



SEVERAL parts of this Church, and especially the Chancel, indicate its Early English origin, though considerable additions have been made to it during the Decorated period. The tower situate at the west end of the nave is partly engaged, and of unusually massive construction, with walls six feet thick. It is of three stages and embattled above. The west door is deeply recessed with very bold mouldings and above it is a lancet. The piers in the nave have a very good effect, though their foliated caps are somewhat rudely carved; their plan is peculiar, and consists of a central pillar, on the cardinal points of which are clusters of three small shafts. There are no responds in the east wall of the nave, and the arches are carried on foliated corbels of the same style as the caps of the piers. The clear-story is of very late insertion, with square-headed windows entirely devoid of tracery or mullions; the old pitch of the roof is still visible on the wall of the tower. The windows in the aisles are decorated, of two and three lights and filled mostly with net tracery. The Chancel is separated from the nave by the rood screen, the lower part of which with its folding doors, opening inward, still remains. The ascent is on the north side, the staircase being partly corbelled


out into the Chancel. The east window is a Perpendicular insertion of four lights, and immediately below it externally occurs the small buttress, so highly characteristic of the Semi-Norman and Early English periods. The west window on the south side is of three lights and transomed; the lower part, consisting of three short lights, forms a lychnoscope. The Priest's door is a beautiful and well-known example. A very complete aumbrie, with its original doors, ornamented hinges and closing ring, remains in the north wall.

The Church is rich in interesting brasses; one especially of unusual design represents a cross in perspective with a nail lying at the foot: the arms of the cross are lost, or probably the two other nails would be found represented one on each. The date of this brass is 1537. The piscina is double, and consists of two trefoiled arches under one hood-mould, with a disengaged shaft between them and a quatrefoil above. Adjoining is a plain pointed sedile.

The Church affords accommodation for about 435 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	33	6
Width of Chancel	20	6
Length of Nave	46	0
Width of Nave	20	9
Length of North Aisle	62	3
Width of North Aisle	11	6
Length of South Aisle	62	3
Width of South Aisle	12	0



NORTH MIMS CHURCH, HERTFORDSHIRE.

PARISH CHURCHES.

DRAWN & MEASURED BY R. J. A. BRANDON

North Mims Church,
Hertfordshire.



A BEAUTIFUL and interesting structure of pure Decorated character : apparently it was originally intended to be a cross Church with an intersection tower, but for some reason this plan was abandoned, and the tower placed west of the nave. Remains of the piers that were prepared to carry the tower may be traced on either side of the Chancel arch, and at the east end of the north aisle, the arch that in the original design would have opened into the north transept now communicates with a chapel,* and a similar arch remains in the south aisle, and may be traced on the exterior.

A small vestry is partitioned off from the chapel, with a door opening into the Chancel ; and this appears to have formed part of the original construction.

The beautiful west doorway in the tower, with its foliated caps and mouldings richly studded with flowers, is figured in "Brandon's Analysis of Gothick Architecture," Section I. Decorated, Plate XXV.

* This chantry, mentioned as St. Catherine's Chapel, was founded by Simon Swanlond, 1328, anno 3 Ed. III., for the daily celebration of mass during his life and that of his wife, and after their death for their souls and those of their ancestors.—*Clutterbuck's History of Hertfordshire.*

Some excellent corbels remain in the nave, illustrating in some instances the head-dresses of the period, and at other times consisting of beautiful knots of foliage.

The Church is rich in sepulchral brasses ; one of a Priest especially is of extraordinary beauty, and closely resembles in its design and execution the noble brass of Abbot Dclamere in St. Alban's Abbey Church.

Against one of the seats in the nave is the poor's box of the date of 1637, with the inscription "Remember the poor."


The greater number of the windows are filled with net tracery.

This Church affords accommodation for about 305 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	32	3
Width of Chancel	18	6
Length of Nave	43	0
Width of Nave	17	0
Width of North Aisle	12	3
Width of South Aisle	11	0
Length of North Chapel	23	3
Width of North Chapel	14	0





PLAN OF NORTH MIMS CHURCH,
HERTFORDSHIRE.





MANTON CHURCH, RUTLANDSHIRE.

PARISH CHURCHES


Manton Church,
Rutlandshire.



THE west front of this Church affords such a valuable and perfect specimen of a Semi-Norman bell turret, that it has been considered worthy of being published, although the remainder of the Church does not present the same amount of interest.

In this instance, as in many others, the addition of the clear-story has done much to destroy the original beauty of the design.






PLAN OF WEST END OF MANTON CHURCH,
RUTLANDSHIRE.



SCALE OF
10 20 30 40 50
FEET



WESTWICK CHURCH NORFOLK

PARISH CHURCHES

J.K. Collins del.

DRAWN & MEASURED BY R. E. J. BRANDON

Westwick Church, Norfolk.



THE whole of this little Church belongs to the Decorated period with the exception of some windows and the western tower;* the latter is an elegant and well-proportioned structure, and the distant effect of its gray battlements appearing above the thick foliage which surrounds the Church is truly beautiful. Its base mouldings are particularly good, and represent in quatrefoils some of the emblems of the Crucifixion. In the third stage occur the square windows so common in the towers of this part of Norfolk; in this instance they are all precisely similar to those occupying the same position in St. George's Church, Norwich.† A well-managed turret staircase runs up in the N. E. angle of the tower, and is lighted by small openings of rather peculiar character.‡

* The following passage occurs in Blomefield's History of Norfolk. "John Grundesburgh, senior, of Westwick, was buried in 1473 in this Church, and leaves to the building of the tower £9; and John Batayle, buried in the Churchyard, 1460, was a benefactor to its building."

† See "Brandon's Analysis of Gothick Architecture," Plate XXII. Perpendicular, Section I.

‡ See also "Brandon's Analysis of Gothick Architecture," Plate XXII. Perpendicular, Section I.

If there were any windows on the north side of the Chancel they have been blocked up. The situation of the rood turret may still be traced. A piscina remains in the south wall of the south aisle with a beautiful basin formed by a quatrefoil, the cusps terminating in roses and a well-carved flower in the centre, with holes under its leaves for the escape of the water. A piscina of plainer design occupies a similar position in the north aisle. A benatura occurs inside to the east of the south door, and a recess near the north door may possibly have served for the same purpose.


There is a very beautiful octagonal font, and three wooden screens of Perpendicular design, and probably of about the same date as the tower.

The Church will afford accommodation for about 254 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	31	10
Width of Chancel	16	6
Length of Nave	48	0
Width of Nave	16	10
Width of North Aisle	8	9
Width of South Aisle	9	0





PLAN OF WESTWICK CHURCH,
NORFOLK.

SCALE OF 10 20 30 40 50 FEET



INTERIOR OF TRUNCH CHURCH NORFOLK

Trunch Church, Norfolk.



A FINE and interesting Decorated Building, with however considerable alterations and additions of Perpendicular date. The Priest's entrance has a curious Perpendicular porch covered with lead and supporting a boldly projecting buttress.* This arrangement was probably had recourse to after the construction of the Priest's doorway, which is Decorated, to resist an apprehended spreading of the wall in that spot, and is a remarkable instance of the simple yet elegant manner in which the ancient architects surmounted any difficulty of the kind.

The remains of the vestry, with a piscina in the south wall, may be traced on the north side of the Chancel. Some of the copings of the roof are terminated with very good gablets, and a magnificent cross,† in a very good condition, still crowns the Chancel. The remains of another may also be seen over the nave. Traces of a benatura exist in the porch.

The interior effect however of the Church is far finer than the exterior. The nave, lighted by a fine Perpendicular clear-story and still retaining its old open seats, is spanned by a noble hammer-beam roof with spandrels, filled with the most beautiful and intricate tracery. Deeply is it to be regretted that such a splendid work, in common

* A somewhat similar arrangement occurs in Grundisburgh Church, Suffolk.

† See "Brandon's Analysis of Gothick Architecture," Plate XXI. Perpendicular, Section I.

with many others equally good that abound in the county, should be fast hurrying to decay, from sheer neglect. The wall plates literally crumble to dust on being touched.

The arrangement of the font is very unusual; it is surrounded by screenwork of late Perpendicular character sufficiently spacious to accommodate several persons and supporting a crocketed canopy: a similar plan occurs in Lutton Church, Bedfordshire.


The rood screen, though but the wreck of a once glorious composition, still glows with its ancient colouring; its lower panels are filled with paintings of Saints and Martyrs, on beautifully diapered grounds. The carvings are of exquisite design and masterly execution. Some of the stalls in the Chancel remain in their original position, and in a tolerable state of preservation. The Priest's door is particularly well managed internally with very good mouldings; opposite it is the entrance to the vestry, now blocked up. The easternmost window is lowered to form the sedilia.

A brass occurs in the nave, which originally consisted of a heart with three legends issuing from it: it is in a mutilated condition and one of the legends is missing. The matrix of a chalice may be seen in the south aisle.

This Church will accommodate about 310 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	34	6
Width of Chancel	18	3
Length of Nave	55	8
Width of Nave	19	3
Width of North Aisle	9	5
Width of South Aisle	9	10



PLAN OF TRUNCH CHURCH
NORFOLK.





BARNWELL CHURCH NORTHAMPTONSHIRE.

Barnwell Church,
Northamptonshire.



THIS beautiful structure exhibits the features peculiar to the Churches of this county, and is principally of Early English work, although some portion of it must be assigned to the Decorated period. The examination however of the Church in its present state requires a critical and practised eye, for on the demolition of a neighbouring Church of about the same date, which took place some years back, many of its beautiful fragments were brought for preservation to Barnwell, and have been applied with more good feeling than taste to divers parts of the Building: thus the heads of the spire lights now figure internally as canopies to the Priest's and vestry doorways; the caps of Early English shafts have been used as bases, &c. &c., and from the circumstance of the style being similar, much perplexity has been caused to many worthy Ecclesiologists.

The tower is devoid of buttresses, and has a considerable set-off level with the belfry floor; it is surmounted by an elegant broach spire with three rows of spire lights non-alternated; the belfry windows are particularly rich and beautiful, and are ornamented with rows of dog-tooth and circular flowers. The west doorway has

some good mouldings, but it is now almost hid by the ivy that grows thickly around it.

The windows in the north aisle are decorated of two lights and very good. The south doorway is an excellent Early English example with banded shafts and dog-tooth in the hollows; the mouldings are of precisely the same character as those of the west doorway of Warmington Church, and probably of the same date.

The Chancel arch is carried on beautiful corbels, consisting of three small detached shafts with caps and bases supported by notch-heads; this arrangement is particularly good and well worthy of imitation.

The Vestry is modern, built out of the fragments of the Church already mentioned: the opening into it from the Chancel is however original, and proves the existence of a former vestry.


On the south side of the Churchyard lies a stone slab with an Early English cross cut upon it of extraordinary beauty and, perhaps, unrivalled elegance of design: it had been stolen, and used as a stepping-stone in a neighbouring brook, but was reclaimed by the present Rector, and placed in the position it now occupies. A small brass of the date of 1610 is nailed up against one of the walls.

The Church will accommodate about 290 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	29	4
Width of Chancel	16	3
Length of Nave	48	6
Width of Nave	18	4
Width of North Aisle	10	6
Width of South Aisle	9	10


PLAN OF BARNWELL CHURCH,
NORTHAMPTONSHIRE



SCALE OF
0 10 20 30 40 FEET



INTERIOR OF LONG STANTON CHURCH CAMBRIDGEHIRE ✓



LONG STANTON CHURCH, CAMBRIDGESHIRE

J.K. Colling del.

PARTS OF CHURCHES

Long Stanton Church, Cambridgeshire.



THIS is a very beautiful yet simple specimen of a small Early English Church. It consists of Chancel, with a nave and aisles under the same roof, a south porch, north doorway and western bell gable, and presents a remarkable similarity in its plan and general design to the well-known and exquisite little Chapel at Skelton ;* in the latter however the bell gable is between the Chancel and nave.

The Chancel, with the exception of a huge modern fire place (which greatly disfigures it both within and without), remains very nearly in its original condition : a beautiful triplet adorns the east end, and to the present day coloured rays of light find their way through the ancient glass that remains in some of the narrow side lancets. There is a large and interesting double piscina with intersecting arches in its usual position, and an aumbrie on the north side. Three stone brackets remain over the Altar, the central one being the largest. A plain string runs round the Chancel internally, under the windows and over the Priest's door. The old roof of trussed rafters has been

* See Ewan Christian's excellent work on Skelton Church, Yorkshire.—G. Bell, Fleet Street.

underdrawn and lime whited. A wooden sill is all that remains of the rood screen.

The aisles retain but one of the original lancets, the other windows are mostly Decorated: the two easternmost are of three lights, and apparently have contained good tracery; the upper parts however have been cut off, and are now level with the eaves of the roof; it is not improbable that formerly the roof over these windows was gabled transept-wise, and thus allowed room for the heads of the windows; it would be difficult otherwise to account for their present mutilated condition. There are no responds against the eastern wall of the nave and the arches are carried on well-designed brackets. Both the north and south doorways are good plain Early English, with jamb shafts. The original roof* covering both nave and aisles still remains, though treated in a similar manner to that of the Chancel.


The present seats in the Church are mere deal boxes, which completely hide the proportions of the piers.

This Church affords accommodation for about 200 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	29	3
Width of Chancel	14	9
Length of Nave	49	2
Width of Nave	14	0
Width of North Aisle	5	9
Width of South Aisle	5	9

* Delineated in the "Open Timber Roofs of the Middle Ages."—G. Bell, Fleet Street.




PLAN OF LONG STANTON CHURCH
CAMBRIDGESHIRE.



INTERIOR OF WORSTEAD CHURCH, NORFOLK.





WORSTEAD CHURCH, NORFOLK.
PARISH CHURCHES.

A. K. Collyer del.



J.K. Colling lith.

WORSTEAD CHURCH, NORFOLK.

Worstead Church, Norfolk.



A SPACIOUS and magnificent Church of rather late Decorated. It is impossible to comprise within the limits of such a brief account a description of the many and varied beauties of this Edifice.*

The tower forms a conspicuous object from all points, and although partaking of the usual characteristics of the towers in these parts, is of superior beauty in its proportions and ornamental accessories. The base mouldings are unusually fine, and are worked in stone and flint. The arrangement of the western doorway, surmounted by a four-light window of very good tracery, is somewhat Perpendicular. The ball flower occurs in the easement of the belfry windows; the pinnacles are modern.

Similar mouldings to those in the tower, enriched with quatrefoils, run all round the Church. The south porch is groined, with a parvise above, and forms an important feature in the south elevation. The vestry occupies the same position with regard to the north Chapel, as in North Mims Church, Hertfordshire: it has a room over it lighted by windows of two lights; the vestry, probably for security, is lighted by narrow lancets.

The interior of this noble structure is most complete, and fully realizes the highly favourable impression which the contemplation of

* For various parts of this Church see "Brandon's Analysis of Gothic Architecture."

the exterior cannot fail to produce. The beautiful roof and clear-story to the nave were added during the Perpendicular period, when it was found necessary to strengthen the piers, which had been thrust out a little, by the addition on either side of two strong flying buttresses.* The roof is of the ordinary hammer-beam kind, with however considerable elegance of outline and very rich tracery in the spandrels. There is a good Perpendicular font and cover.

The Chancel screen is not unlike the screen in Trunch Church, and retains much of its original colouring. At the foot of it is a small brass, bearing the name of John Alblastyr, who is said to have been the donor of this screen: he deceased in 1520, leaving to his wife the finishing of the work, an inscription to whose memory, of the date of 1524, is placed by the side of his. This Church was formerly very rich in brasses, but owing to gross carelessness and ignorance on the one part, and sacrilegious cupidity on the other, almost the whole have been stolen at different times.

The south-east window of the Chancel is lowered to form the sedilia.


This Church will afford accommodation for about 700 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	39	0
Width of Chancel	29	3
Length of Nave	89	0
Width of Nave	29	0
Width of North Aisle	11	11
Width of South Aisle	11	8

* Blomefield, in his History of Norfolk, mentions that "John de Kynneburle, being vicar in the 2nd year of Richard II., the chancel of this Church was new built; the prior of the convent of Norwich granted fifteen oaks out of Plumstead Wood, and timber also out of St. Leonard's Wood, and the expenses in money were £24 4s. 4d."

It is very probable that the nave roof and clear-story, together with some windows of Perpendicular tracery, were added at the same time.



PLAN OF WORSTED CHURCH.
NORFOLK.



J.K. Colling lith.

INTERIOR OF FILBY CHURCH, NORFOLK.

Filby Church,

Norfolk.



THIS little Church is beautifully situated in a magnificent grove of trees, and its elegant Perpendicular tower rises nobly from the thick foliage which surrounds it. On a near inspection of the Building we find that here, as in so many other places, time and neglect have done their work; the Chancel roof is lowered, the south porch suffered to fall into ruins, the upper part of the finely painted rood-screen demolished, and the well carved and solid seats of former days concealed by high deal pews.

Still the interior has not suffered nearly so much as the exterior; its proportions are excellent, and the clear-story of small quatrefoils* contributes considerably to the general good effect. The removal of the lath and plaster with which the roof is underdrawn, would be an immense gain to the beauty of the interior. The roof is composed of trussed rafters: this construction was deservedly very general during the Early English and Decorated periods, combining a simple appearance with great security, durability, and economy of material. The belfry arch is Perpendicular as well as the rest

* The diameter of the window externally, from outside to outside, is 1 ft. 5 in.

of the tower; the latter is a fine structure with angle buttresses terminating in small octagonal turrets, each supporting a figure; the parapet is enriched with flint panels and stepped after a fashion very prevalent in this county.


The west door has been richly carved, and the remains of a good closing ring may be seen on the north door. The door to the turret staircase is crossed and re-crossed with bands of iron closely set together, and is fastened by seven locks curiously wrought. This excess of precaution seems to have been taken with a view of converting, on an emergency, the tower into a stronghold: the turret door of Hingham Church is similarly protected.

This Church affords accommodation for about 380 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	34	0
Length of Nave	56	0
Width of Chancel	17	9
Width of Nave	19	5
Width of North Aisle	10	8
Width of South Aisle	10	8






PLAN OFFILBY CHURCH,
NORFOLK

SCALE OF FEET

REMAINS
OF
SOUTH PORCH.

MARTHAM CHURCH, NORFOLK



PARISH CHURCHES

DRAWN & MEASURED BY R. A. J. BRADTON
J. K. COOPER, LITH.

Martham Church,

Norfolk.



THIS fine Church is a pure Perpendieular Structure, of great magnificence, but now much neglected. The tower is of noble proportions, with a rich embattled parapet and excellent base mouldings worked in flint and stone which continue round the body of the Church, the Chancel being left singularly plain. The absence of parapets is a peculiar feature in the Norfolk Churches and stamps them, as in this case, with a remarkable character, the thin line of overlapping lead sharply defining the junction of the roof with the walls. The south door has been a beautiful piece of wood-work exquisitely carved, with a very good closing ring and key plate; it is now sadly mutilated; most of the old benches remain, without backs and with very well executed finials. The ascent to the rood loft is on the north side, and a post-Reformation roodscreen with doors, locks, &c., complete, separates the Chancel from the nave. Considerable portions of the old stained glass are scattered throughout the different windows of the Church.

There is a fine hammer-beam roof over the nave, of the same date as the rest of the Church; it is in a very dangerous state,

and unless immediately attended to must shortly fall. It is lamentable to think how many of these noble roofs, which with common attention would yet last many centuries, are being lost by the neglect of those whose duty it is to repair and hand down to posterity the Churches which their more pious ancestors so liberally bequeathed to them.

There is one brass in the Church, a heart with three legends issuing from it.


The Font is octagonal, Perpendicular, and carved on its different faces.

The Church affords accommodation for about 470 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	34	0
Width of Nave	71	3
Width of Chancel	20	6
Length of Nave	19	3
Width of North Aisle	10	9
Width of South Aisle	10	9





PLAN OF MARTHAM CHURCH,
NORFOLK


SCALE OF 0 10 20 30 40 50 60 FEET

PARTIAL CHURCH.

DRAWN AND ENGRAVED BY F. L. BRINDON



INTERIOR OF HINGHAM CHURCH, NORFOLK.



HINGHAM CHURCH, NORFOLK

PARISH CHURCHES

DRAWN & ENGRAVED BY G. J. BRANSON

J. K. COLEMAN 1876

Hingham Church, Norfolk.



THIS Church was entirely rebuilt by Remegius de Hethersete, Rector, with the assistance of John le Marshall, his patron, who contributed largely to the perfection of the work. Remegius became Rector in 1319, and was succeeded in 1359 by John de Ulford. The Building therefore was probably begun in the early part of the reign of Edward III. and completed towards the middle of it. It is a perfect and beautiful specimen of a Church of this period, and a comparison of it, both in plan and elevation, with St. Mary's at Martham, a valuable example of a fine Perpendicular structure, will be of infinite use in enabling us to detect the peculiarities of each style. Both are magnificent Buildings, yet the grand appearance of Hingham must be attributed to the massiveness of its different parts, and the steepness of its roofs, rather than to its ornamental accessories; and of Martham, on the contrary, to its great height combined with considerable lightness, and richness in details and tracery. The difference in the two embattled parapets is worthy of remark, also the relative proportions of the Chancel and nave in each Church.

There is great irregularity in the arrangement of the plan, the windows on either side being made to correspond even to the numbers of their lights. It is also to be noticed that all the buttresses, with the exception of those of the porch, are placed at right angles to the walls; this is a feature more universal in Decorated work than is generally admitted. Blomfield mentions that "there were several Chapels of which the most remarkable

were at the end of each aisle, that on the north being dedicated to the Holy Trinity, that on the south to the Holy Virgin," this explains a peculiarity, otherwise not accounted for, in the arrangement of the easternmost windows of the aisles, which are of three lights, all the others in the body of the Church being only of two. That at the east of the south aisle is of great beauty and presents a curious mixture of geometrical and flowing tracery: the other three-light windows were probably similar, but have all been replaced by Perpendicular insertions; in one case on the north side the Decorated mullions remain with Perpendicular tracery. The string-course under the windows is effectively managed and is continued all round the Church.

The west doorway, with three rows of shafts, well-sunk mouldings and crocketed dripstone, and the beautiful base mouldings of the tower, are especially deserving of attention.

In the Chancel is a stately monument to the memory of Thomas, Lord Morley, who died about 1435.

The vestry, now partly in ruins, is a Perpendicular addition, and blocks up one of the fine Decorated windows. It had formerly a room over it.

The masonry of the Church is of rough flints with stone dressings.

The roofs over the nave and Chancel have been considerably lowered; they are restored in the exterior sketch by following the weather moulds which still remain against the tower and east wall of the nave, in order to obtain the full effect of the Building in its perfect state. The aisle roofs retain the original pitch. The probable age of the present roof over the nave is indicated by one of the shields under the hammer-beams: it bears the date of 1664, and on the corresponding shield are the initials C. W. R. D. A. R.

The Church affords accommodation for about 830 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	60	0
Length of Nave	97	6
Width of Chancel	27	6
Width of Nave	27	6
Width of North Aisle	14	1
Width of South Aisle	14	1



PLAN OF MINCHAM CHURCH,
NORFOLK

SCALE OF FEET 0 10 20 30 40 50





DEOPHAM CHURCH, NORFOLK.

Deopham Church, Norfolk.



THE noble tower of this Church is perhaps not excelled by any in Norfolk. It is of pure Perpendicular, with good base mouldings,* well graduated buttresses, and excellent window tracery. The turrets which terminate the buttresses are hexagonal, and with the crocketed gables surmounted by crosses that rise out of the parapet, form a rather unusual and very beautiful arrangement.

The west and south doorways are richly carved; the latter has an embattled label over the doorway, with spandrels filled with tracery.

Both within and without, this Church is in a sad state of decay: most of the windows of the tower are blocked up, also those in the porch, and the east window of the Chancel, a fine piece of Perpendicular tracery.

There were formerly Chapels at the east end of the aisles; parts of the screens remain, retaining some of their ancient colouring. The Chapel in the south aisle was that of the

* Published in the "Analysis of Gothick Architecture," Section I., Perpendicular, Plate XXV.

Assumption, and in the north that of St. John the Baptist. There is a piscina in each.


There is a good plain roof over the nave, and many of the old benches (for they have no backs) still remain. A very remarkable monument occurs in the north aisle; the foot of it is partly buried in the east wall. It is of Purbeck marble, and the upper part, instead of being coped, is raised in gradations, probably with a view to gain more room for an inscription which covers the whole surface.

The Church affords accommodation for about 430 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	32	4
Length of Nave	72	1
Width of Chancel	18	0
Width of Nave	17	5
Width of South Aisle	11	0
Width of North Aisle	11	0






PLAN OF DEOPHAM CHURCH,
NORFOLK.



PARISH CHURCHES

DRAWN & ENGRAVED BY E. & J. BRANDON



J.K. Collyer, lith.

RICKENHALL CHURCH, SUFFOLK.

Rickenhall Church, Suffolk.



A VERY early Decorated Building, highly interesting, with a south aisle of great magnificence. The tower, which is Norman, is the only part that has been preserved of the old Church; it is circular on plan, with the upper stage Perpendicular and octagonal, and terminating in a richly embattled parapet with pinnacles at the angles. A great proportion of the round towers both in this county and in Norfolk have been similarly treated.

The parvise over the porch, the Priests' doorway, and three windows on the north side of rather poor tracery, seem to have been added at the same time as the upper stage of the tower. All the rest of the Church is of one date and very beautiful; considerable care has been bestowed on the south aisle, the windows in which are beautifully moulded with excellent tracery. The most interesting feature, however, is the east window of the south aisle. It possesses every characteristic of a late Perpendicular design, and a casual observer would most probably assign it to that period; it is only by attentive examination and comparison of it with the other windows that convincing proofs are afforded

that they are identical in date and workmanship.* The mouldings are precisely similar in all of them.

The roof is of trussed rafters of seven cants; it is unfortunately underdrawn; that over the Chancel, which appears to have rafters with circular ribs, is in the same condition. The nave roof is of very poor construction and late.

The piers are simply but effectively moulded, and are of pleasing proportions.

The Font is Early Decorated with characteristick panels.

The tower communicates with the nave through a low Norman archway.


The Church affords accommodation for about 190 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	17	2
Width of Nave	18	6
Width of Chancel	24	5
Length of Nave	38	8
Width of South Aisle	17	0
Length of South Aisle	39	6

* A window of the Early Decorated period occurs in Evington Church, Leicestershire, with most of the peculiarities of Perpendicular tracery, such as trausoms, super-mullions, &c.






PLAN OF RICKENHALL CHURCH,
SUFFOLK.

SCALE OF FEET

PARISH CHURCHES

DRAWN & MEASURED BY F. L. A. BRANSON



J. G. Collyer del.

MORLEY ST BOTOLPH CHURCH, NORFOLK.

Morley St. Botolph Church,
Norfolk.



THIS Church illustrates a class of plans of peculiar proportion and well worthy of notice. Where they occur the Churches are generally of early date, in most cases Norman, as at Kisly Church, Suffolk, which has a round tower at the west. The earliest parts of Morley Church may be assigned to the end of the thirteenth century. St. James's, Cowley, Oxford, is of this period, and with a similar plan; Flempton Church, Suffolk, is another example; its Chancel was rebuilt about the middle of the fourteenth century. In all these instances the proportions are precisely similar, the Chancel and nave forming four squares.

Sir Thomas Warde, who was instituted Rector of St. Botolph's Morley in 1480, fitted up and adorned the Chancel; the two square-headed windows on the south side, of very questionable elegance, are probably part of his work. The tower and other portions of the Church are also Perpendicular, but appear to be very much anterior to 1480.

Two flat coffin-shaped stones, probably those of the founders, form the sill to the south doorway.*

The crosses over the gables are modern.


The Church affords accommodation for about 140 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	34	6
Width of Chancel	18	0
Length of Nave	53	0
Width of Nave	18	3

* It was a usual practice in the early days of Church Architecture for the founders or benefactors to be buried at the sill of the doorways, as at Deopham Church, Norfolk; or under the walls of the Church, as at Bottisham, Cambridgeshire, where the whole of the south aisle is arcaded both within and without, with low arches, under each of which rests a stone coffin. Afterwards the founder's tomb was frequently placed on the north side of the Chancel, as at Herne Church, Kent.






PLAN OF MORLEY ST BOTOLPH CHURCH,
NORFOLK.

SCALE OF 10 20 30 40 50 60 FEET

INTERIOR OF WOOLPIT CHURCH, SUFFOLK



J.K. Colling lith.

Woolpit Church, Suffolk.



THIS Church is a Decorated structure with numerous Perpendicular additions; of these the south porch is the most important; it is a beautiful and elaborate design, richly groined, with a parvise over it and fine open parapet.

The angle buttresses to the Chancel are Decorated, worked in two stages with niches, cinquefoiled and ogeed. The vestry is modern, but built on the old site; the door into it from the Chancel is original.

The interior however is deserving of the most attention; a lofty clear-story added during the Perpendicular period is spanned by a splendid double hammer-beam roof of the most costly description. The wall pieces are wrought into niches filled with figures of Saints supported by Angels with expanded wings. A similar roof with the timbers finely moulded and coloured remains over the nave of Knapton Church, Norfolk.*

The aisle roofs are of the same date as those over the nave, and equally rich in detail. Happily in this instance they have all been well restored, and appear now in good preservation.

* See the "Open Timber Roofs of the Middle Ages."—G. Bell, Fleet Street.

The seats are very perfect and beautiful, the roodscreen also is a fine specimen of the carver's art, though much mutilated.

The easternmost window in the south aisle is lowered to form the sedilia, and an elegant piscina is cut out of the angles of the jamb, which is supported by a small shaft.

In the Chancel is a double piscina with trefoiled heads, a stone shelf and quatrefoil orifices.


The masonry of the Church is composed of stone dressings with flints laid in random courses.

The Church affords accommodation for 360 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Width of Chancel	18	5
Width of Nave	18	5
Length of Chancel	32	8
Length of Nave	68	0
Width of South Aisle	8	5
Width of North Aisle	8	8
Length of Aisle	65	7





PLAN OF WOOLPIT CHURCH,
SUFFOLK.



W. & A. BRADSHAW

BRADSHAW & BRADSHAW, ARCHT. & BLDG. SVCS.



J.R. Colvill del.

FLEET CHURCH, LINCOLNSHIRE.

DRAWN & MEASURED BY R & J A BRANDON

PARISH CHURCHES

**Fleet Church,
Lincolnshire.**



IN the midst of a district famed for the magnificence of its ecclesiastical structures, Fleet Church might formerly have vied with any in beauty and richness; its present neglected condition offers a miserable contrast to its former splendour. Most of the windows have lost their tracery, and although the old arches remain, circular-headed openings have been built up within them and filled with common square glazing; the pitch of the roof has been lowered, (it is restored in the accompanying view,) and the Chancel aisles suffered to fall into ruins. It is only by examining closely the walls of the Chancel, in which the piers and arches yet remain, that their former existence can be ascertained, and their position determined. The south Priest's doorway seems at present singularly placed in the east buttress of the south aisle; this, however, was continued on and formed the south wall of the Chapel.

The buttresses on the north side are of great beauty, and are gabled; especially those to the Chancel, which clearly belonged formerly to the north Chapel, and on its destruction were built up in their present position. The east window is blocked up.

There are very good Decorated sedilia of three seats with crocketed canopies, and a piscina similarly enriched.

The nave piers are circular, they are of unusual height, and particularly elegant proportions. The font is octagonal, Perpendicular, with rather plain panelling.


The detached position of the tower, a very unusual arrangement, makes it a commanding feature in the design, and imparts considerable originality to the exterior of the Church, though inside, the absence of the belfry arch is much felt. It is of the same date as the Church (Early Decorated), and in every respect worthy of it.

Outside, by the north doorway, is a slab with a beautifully incised cross fleurie; only part of the inscription remains:—
 PASEY : PUR : LES ALMES RICHARD : ATTEGREME :
 AGNEYS : SA : FEMME : PRIEZ : QUATRE : VINGS :
 IOUR : DE : PA On either side of the Chancel are two coffin stones, with very good raised crosses; they were formerly no doubt inclosed within the Chapels that have been destroyed.

The Church affords accommodation for about 450 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	42	0
Width of Chancel	17	5
Length of Nave	61	0
Width of Nave	20	0
Width of North Aisle	14	4
Width of South Aisle	15	4



CHANCEL AISLE

CHANCEL AISLE

FLEET CHURCH,
LINCOLNSHIRE.

SCALE OF
0 10 20 30 40 50 60
FEET

PARISH CHURCHES.

DRAWN & MEASURED BY R. A. J. BRADON.



J.K. Colling lith.

DONINGTON CHURCH, LINCOLNSHIRE.

Donington Church, Lincolnshire.



THE Priest's doorway, and the steep pitch of a former roof still visible, indicate the prior existence of an Early English Church, which was probably almost entirely pulled down to make room for the present beautiful structure.*

From the general style of the work, it would appear extremely probable that this Church was rebuilt at the same time, perhaps even by the same hands that erected the glorious Churches of Heckington and Ewerby.

The tower and spire are particularly good, and built of excellent masonry; the lower portion of the tower forms the porch, and is very richly groined: the entrance into the Church is through a beautifully moulded doorway having jamb shafts with good caps and bases.

The nave piers are lofty and well proportioned, with crenellated caps of rather unusual character.

* It is interesting to notice how very reluctant our forefathers were to destroy all traces of their predecessors' pious munificence, though anxious themselves to rebuild the Church with additional splendour and with the increased skill they had at their command. How very frequently a Norman doorway or font, carefully preserved, alone remains to attest the piety of a past generation.

The windows in the south aisle are segmental-pointed, with good tracery, jamb shafts, and excellent mouldings, of pure Decorated outline. The north windows, on the contrary, are quite different; they are acutely pointed, and their jambs consist of a plain broad chamfer, not unfrequently met with in these parts, the effect of which however is extremely poor.

The buttresses to the Church are very good; most of them are gabled, and in every instance are placed at right angles with the wall.*

The Chancel is mostly Perpendicular, with a very fine east window of five lights; that at the west does not appear to be quite so late.

The Font is octagonal, Decorated, with canopied panels.


A gallery is built across the Chancel arch; and, as likely soon to be among the things that have been, the pews are worth mentioning from their gigantic size; they are upwards of six feet in height.

This Church affords accommodation for about 610 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	42	0
Width of Chancel	19	3
Length of Nave	81	0
Width of Nave	21	9
Width of South Aisle	16	0
Width of North Aisle	14	0

* See remark on angle buttresses at page 49.




DONINGTON CHURCH
LINCOLNSHIRE

SCALE OF 0 10 20 30 40 50 60 FEET

DRAWN & MEASURED BY R & J.A. BRANDON.

PARISH CHURCHES.

J.R. JOBBINS, LITH.



ACHURCH CHURCH, NORTHAMPTONSHIRE.

Achurch Church, Northamptonshire.



AN Early English Church, cruciform on plan, with a west tower surmounted by a beautifully proportioned spire. The staircase turret at the north-west angle is singularly well managed, and is lighted by small trefoiled lancets with projecting canopies instead of dripstones. The buttresses round the Church are all very excellent Early English specimens; those to the Chancel are gabled, with the heads filled with very early tracery.* The windows also are valuable as showing the gradual development of tracery which began to manifest itself towards the close of the Early English period of mediæval Architecture. The body of the Church has lost much of its original character, the roofs are lowered and the windows and doorways in a great measure blocked up. The Chancel and transept arches are carried on corbels well moulded and carved with good Early English foliage. The space occupied by the intersection of the cross is in this instance given to the nave, the roof of which is continued eastward to the Chancel

* Illustrated in "Brandon's Analysis of Gothick Architecture," (Section I. Early English, Plate XXII.)

wall. The roofs to the transepts are quite distinct from, and abut against, the north and south walls of the nave. That over the Chancel is coved; they are unfortunately all underdrawn, but probably consist of trussed rafters.


The Font is octagonal, quite plain, and of the same age as the Church.

The Church affords accommodation for about 210 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	32	0
Width of Chancel	16	9
Width of Cross Transepts	46	8
Length of Nave	59	0
Width of Nave	20	0





PLAN OF ACHURCH CHURCH,
NORTHAMPTONSHIRE.

SCALE OF 10 20 30 40 50 60 FEET



STANWICK CHURCH, NORTHAMPTONSHIRE.

Stanwick Church, Northamptonshire.



A SMALL Early English Church deserving of notice from its peculiarly beautiful and perhaps unique tower and spire. Although all the rest of the Building is more or less mutilated and disfigured, the steeple luckily remains in its original condition.

When such perfect examples as the present are met with, an exact record of their date is most desirable, but in this case we have unfortunately nothing to guide us but the peculiarities of style, which would induce us to assign its erection to the early part of the reign of Henry III. An elegant little doorway that opens from the turret staircase into the belfry, and the simple and rather early arrangement of the windows, show that up to this point the works were carried on without interruption or transition of style; the spire, however, is certainly of later date, and although a very similar one was undoubtedly intended, yet we must presume that a suspension of the works (after bringing the tower up to the underside of the corbel table) caused its details to be somewhat influenced by the gradual change which at the time was taking place.

The lancet in the west front of the tower is enriched internally

by two rows of jamb shafts, the caps on the north side only being foliated. The tower was formerly groined.

The turret staircase on the south does not go higher than the roof over the south aisle to which it gives access: from this level a passage through the thickness of the wall leads to another staircase which continues up to the belfry floor.

So little of the body of the Church remains in its original condition that but a very brief notice of it is needed. The Chancel has been rebuilt and curtailed of its proper proportions, and is now two or three feet narrower than was at first intended, as will be seen on referring to the plan.


From the remains of a dripstone in the west wall of the aisle, we may infer that the roof at one time was gabled and has since been converted into a "lean-to."

The little that remains of the Font (part of the bowl and the foot) shows it to have been a beautiful Decorated design; it is octagonal, with crocketed canopies and pinnales, with double cusped tracery.

The Church contains accommodation for about 310 worshippers.


PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	32	0
Width of Chancel	17	4
Length of Nave	62	0
Width of Nave	18	8
Width of Aisle	15	4



PLAN OF STANWICK CHURCH
NORTHAMPTONSHIRE.

SCALE OF 10 20 30 40 50 60 FEET



J.K. Colting lith.

ALDWINKLE CHURCH, NORTHAMPTONSHIRE.

Aldwinkle Church, Northamptonshire.



A SMALL Early English Church of considerable interest and beauty. The elegant spire forms in this instance, as in almost all the Churches of Northamptonshire, the distinguishing feature. It is of later date than the body of the Church, and was probably added with the porch when the Chancel and vestry were rebuilt.*

The Priest's doorway is a little westward of the vestry and is illustrative of the constant practice of the period to avoid external doorways in the sacristies. There is a stone seat on either side of the Chancel in lieu of stalls. The Chancel arch is carried on corbels; the easternmost arches of the nave are similarly managed.

* In Bridge's History of Northamptonshire it is mentioned that, "in the east window of the Chancel are the portraits of a king crowned and of a person praying; and round him, within a label in Saxon characters, 'Orate pro anima Wil. . . . wyk Rectoris istius Ecclesie.' In the southern panel of the same window is a like portrait, and in a label this inscription: 'Orate pro aia Rogeri Travers condam Rectoris istius Ecclesie:'" a considerable portion of this glass yet remains. Referring to the list of Rectors, we find that in 1308 Roger Travers was rector, and was succeeded in 1335 by William de Luswick, the party who appears to be commemorated in the stained glass. We may therefore fairly presume that these were the parties who rebuilt the Chancel and added the steeple and south porch.

There have been Chapels at the east end of both aisles; the piscina and step round the Altar remain in both cases.


The west window in the south aisle is very remarkable, from the circumstance of being transomed, and presenting every indication that the lower part below the transom, though now glazed, was formerly secured by a wooden shutter. The hooks for the hinges and the bolt holes give sufficient evidence of the fact. Had this window occurred on either side of the Chancel, we should have considered it as an ordinary instance of a lychnoscope; does it not therefore materially support the opinion of those who consider that these singular openings were for the purpose either of distributing alms, or for receiving tithes, &c., the more especially as in this instance the Chancel is without a lychnoscope? A window of this date with a transom, and the lower part secured by a wooden shutter, remains quite perfect in the south side of the Chancel of Hartley Church, Kent.

The font is Early English, octagonal, and though plain is of good character.

This Church affords accommodation for about 200 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	32	0
Width of Chancel	17	6
Length of Nave	37	3
Width of Nave	14	6
Width of North Aisle	9	1
Width of South Aisle	10	9



PLAN OF ALDWINKLE CHURCH,
NORTHAMPTONSHIRE.

SCALE OF 60 FEET



BISHOPS LYDEARD CHURCH, SOMERSETSHIRE.

Bishop's Lydeard Church,
Somersetshire.



THE noble tower of this Church is an excellent specimen of a style peculiar to this county: erected towards the close of the Perpendicular era, and with many symptoms of a declining art, in all of them we find nevertheless such admirable and dignified proportions as almost to compensate for the loss of that purity of detail so conspicuous in the works of the previous century.

In the example before us, the tower is of four stages and diminishes gradually as it rises, and such is the consummate skill displayed in the arrangement of the buttresses that the eye is completely satisfied, no awkward break occurring to disturb the beautiful tapering outline. The upper windows of the tower are filled with pierced stone panels, an excellent substitute for louvre boards, and contributing considerably to the richness of the structure.

The body of the Church appears in every respect cotemporary with the tower. On referring to the plan, we shall perceive that the south aisle is considerably wider than that on the north side, its arches are loftier, and it is roofed with a distinct gable, while the north aisle is under a lean-to continuing from the nave-roof.

In numerous instances we may remark the superior importance given to the south aisle, more especially in its having a gabled roof.

The Chantry Chapel appears an after addition, as in constructing it the east wall has been splayed, to allow access to the lychnoscope in the south wall of the Chancel, which would probably have been brought a little more eastward had the Chapel formed part of the original design.

The Church retains all its old seats and a beautiful and richly carved screen extending across the Chancel and Chapel. It partakes of the usual elaborate character of the screens of this county, and has the whole of the Creed in raised letters in a casement at the top.

In a Church of this date the absence of a clear-story is very remarkable.

An elaborate Ionic Altar-piece in stucco blocks up the east window. The Priest's door is on the north side.


The font is octagonal, poorly panelled, and of the same date as the Church.

The Church affords accommodation (exclusive of the Chapel) for about 280 worshippers.

PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	26	5
Width of Chancel	16	0
Length of Nave	48	0
Width of Nave	20	5
Width of South Aisle	12	3
Width of North Aisle	7	1

PLAN OF BISHOP LYDEARD CHURCH,
SOMERSETSHIRE.



SCALE OF 10 20 30 40 50 60 FEET

J. R. JOBBINS, Z.N.C.O.

PARISH CHURCHES.

DRAWN & MEASURED BY R & J. A. BRANDON.



LECKHAMPTON CHURCH, GLOUCESTERSHIRE.

Leckhampton Church,
Gloucestershire.



THE peculiarity of this Church consists in its decidedly Norman arrangement of plan, whilst in all other respects it is a Decorated Building. This we perceive more especially in the situation of the tower over the western extremity of the Chancel, which at once suggests the idea of a Norman Church, an idea still further strengthened on entering the Church, by the appearance of the old Font, a circular bowl, in good preservation, with the cable ornament twisted round it. A respond against the east wall of the nave separating it from the north aisle, confirms the belief that an earlier Building existed, and at the same time shows that the present aisle as well as the rest of the Church, was rebuilt on the site of its predecessor.

The body of the Church, internally, is quite devoid of interest; the nave piers and arches were swept away about ten years back for the greater convenience of the occupiers of the gallery, which extends the length of the south aisle. Under what would be the easternmost arch of the nave, is a panelled Altar-tomb with the effigies of a knight and his lady: the figure of the knight is cross-legged, and is supposed to represent Sir John Giffard, who died in

the third of Edward III. There is little doubt that through his pious munificence the present Church was built. The tomb of this once honoured benefactor is now sadly disfigured and mutilated.

The Chancel, the most perfect and interesting part of the Church, is divided into two distinct parts (another characteristic feature in Norman Churches), and is groined with two bays of simple quadripartite groining, with well carved heads and bosses; in the first compartment a space is left for lowering the bells. The tower is remarkably small, and to save room inside, the north and south walls are very much reduced in thickness below, and carried above on corbelled arches. The old roof of trussed rafters with an occasional tie-beam remains over the Chancel.

The unusual lowness of the buttresses all round the Church is deserving of notice; possibly the builders were influenced by the unimportance of the buttresses in the former structure.

In the Church-yard are several effigies, probably removed from the Church, and also many coped coffin stones.

The Church affords accommodation for about 220 worshippers.


PRINCIPAL DIMENSIONS.

	Ft.	In.
Length of Chancel	27	0
Width of Chancel	11	11
Length of Nave	48	5
Width of Nave	18	10
Width of North Aisle	12	3



PLAN OF LECKHAMPTON CHURCH,
GLOUCESTERSHIRE

SCALE OF 0 10 20 30 40 50 60 FEET



INTERIOR OF ISLIP CHURCH NORTHAMPTONSHIRE.



ISLIP CHURCH, NORTHAMPTONSHIRE.



ISLIP CHURCH, NORTHAMPTONSHIRE.

PARISH CHURCHES

DRAWING MEASURED BY R. J. A. BRANCO

Islip Church, Northamptonshire.



A CHURCH of a pure Perpendicular style, apparently rebuilt on the site of an Early English structure. As in Donington Church, some slight portions of the old work have purposely been left as evidences of the fact. They consist in this instance of the weather mould against the east gable of the nave, the piscina in the Chancel, and perhaps the font; the latter is quite plain, octagonal, the bowl being carried on eight small shafts not detached, but clustered round a central stem.

The present Church is a valuable example of a Building of this period, as it appears to be quite as at first designed, without having suffered, as in many cases, either by the subtraction of any of its original parts, or by injudicious additions. The proportions and grouping are pleasing and well managed, and the details, although not partaking of that profuseness of decoration which prevailed at this period, are nevertheless correct and well executed. The west doorway and window in the tower are very good; the former is ogeed with a square-headed dripstone, and has quatrefoiled circles in the spandrels. The roof over the Chancel is of a heavy and inelegant construction, although richly carved.

There are a few specimens of excellent quarries in the windows, and some small remains of stained glass.

The Church affords accommodation for about 210 worshippers.

PRINCIPAL DIMENSIONS.


	Ft.	In.
Length of Chancel	30	6
Width of Chancel	15	8
Length of Nave	41	0
Width of Nave	15	10
Width of South Aisle	9	0
Width of North Aisle	9	0

END OF VOL. I.









PLAN OF ISLIP CHURCH,
NORTHAMPTONSHIRE

SCALE OF 60 FEET





GETTY CENTER LIBRARY



3 3125 00074 7549

