DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

GHQ/SCAP Records (RG 331, National Archives and Records Service)

Description of contents

(1) Box no. 2820

(2) Folder title/number: (23) (end)
Saitama General

(3) Date: ? - Nov. 1949

(4) Subject:

Classification	Type of record
9750	z

(5) Item description and comment:

Saitama

(6) Reproduction: (Yes) No

(7) Film no. Sheet no.

(Compiled by *National Diet Library*)

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Saitama General

No.	Date.	Subject.
		Prefectural Public Health Department Organization Plan

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

川越市附近圖

縮尺一万五千分之一



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

地圖

SAIT

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣管內地圖

SAITAMA PREFECTURE

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

熊谷市附近圖

縮尺一万五千分之一

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

浦和市附近圖

縮尺壹万五千分之壹

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013



東京都中央区丸ノ内二丁目
関東兵事部公衆衛生課
獸医務係御中

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

昭和二十五年十一月二十八日

関東民事部長　殿

神奈川県

牛の流行性感冒予防のための牛の移動禁止解除について

本県においては十月二十日牛の流行性感冒が終熄したので牛の流行性感冒予防のための牛移動並びに牛の集合施設禁止を解除し旦つ本県への牛の移入の制限を一部緩和したことについて別紙寫のとおり告示によつたから報告（通報）する。

尚改正後の告示文は別紙参考文のようになつたから御参照願いたい。

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

神奈川県告示第五百八十六号

牛の移動禁止の告示（昭和三十五年九月神奈川県告示第四百七十五号）の一部を次のように改正し、昭和三十五年十一月二十二日から適用する。

昭和三十五年十一月二十八日

神奈川県知事　内山岩太郎

「及び第十八條」を削り、同県下における牛の移動及び牛の集合施設を禁止し北海道、青森県、宮城県、秋田県、山形県、及び岩手県の都府県からの」を「次の地域以外の地域からの」に改め、但書中「又は定時的に往来する牛」を削り、別記として次のものを加える

北海道、青森県、宮城県、秋田県、山形県、岩手県、東京都、岡山県、島根県、広島県、鳥取県、埼玉県（川口市、大宮市、浦和市、行田市、川越市、熊谷市、所沢市）静岡県、兵庫県（美方郡、宍粟郡、加古川市、加古郡、姫路市、飾磨郡、美嚢郡、神戸市、豊岡市、有馬郡、多可郡、加西郡、州本市、津名郡、神崎郡、赤穂郡、佐用郡、城崎郡、朝来郡、氷上郡、武庫郡、西宮市、尼ヶ崎市、伊丹市）、徳島県（鳴門市、板野郡、阿波郡、麻植郡、美馬郡、三好郡）、茨城県、三重県、京都府

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

（参考）

告示改正後の告示文

家畜伝染病予防法第十六条の規定に基き昭和二十五年九月三日から当分の間次の地域以外の地域からの牛の本県への移入を禁止する。

但し知事が特に認めたもの及び屠場に直行するものはこの限りでない。

昭和二十五年九月二十六日

神奈川県知事内山岩太郎

（次の地域）

省略（告示文写参照）

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Saitama-1

15 Nov. 1949

Subject : Health Section Report.
To : Education Section, S.C.A.T.

Oct. 31 -- Nov. 3

The second parasite examination was held at the Naguri E.S., Iruma Gun for 600 E.S. & L.S.S. pupils.

Nov. 1,

Circuit dental prevention treatment was operated at the Fukaya E.S. for 300 pupils.

Nov. 4

The same was operated at the Kuna E.S., Chichibu Gun for 500 pupils.

Nov. 4 -- 7

The Parasite Examination was held at the Irumagawa L.S.S. Iruma Gun for 400 L.S.S. pupils.

Nov. 7.

The formal official commendation of physical-perfect pupils was held at the auditorium of the Urawa C's 1st U.S.S.. 100 in-prefectural E.S. pupils were commended officially.

Nov. 8

Circuit dental prevention treatment was operated at the Kawagoe 1st E.S. for 350 pupils.

Nov. 14

Health Education Study Meeting was held at the Shitami L.S.S., Kita-Saitama Gun and was attended by 200 E. & L.S.S. teachers.

K. Kawauchi
Head of Health Section

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

This newspaper is reportedly "gangster" pubs. "Gangsters" use various means to extort money. If your work should call for you to check into the report stated below, CI would be glad to get your version of the facts of the case. WHG

PH

Sitana -

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

FH

The Saitama Nippo
Nov. 27, 1949

100,000 Omiya citizens being defeated
by one obstinate person

Why the Hasumi Hospital standing in the
way of the city planning ?

The removal of the Hasumi Hospital was taken up first in June 1945 so as to carry on the city planning but no step has yet been taken up to this day. The city planning cannot be carried out chiefly due to the person standing in the way. During the war time when the air-raids were being repeated from time to time, 229 houses in front of the Station were forced to move out. They moved out somehow but the Hasumi Hospital did not do so. The year before last, there was taken up the city planning by which the area in front of the station would be enlarged with the State subsidy and the prefectural subsidy granted and here again the Hasumi Hospital came up to the fore. This hospital is one of the 229 houses for forced removal and naturally it should move out. 35 of the 36 city Assembly members (Dr. Hasumi objected) supported the removal of the hospital. There is said to exist some persons pulling the wire from behind but anyway 35 members were defeated by one objector.
Dr. Hasumi says there is no trouble in connection with his hospital at present. Whereas the city authorities as well as citizens are desirous of the removal effected at an earliest date. The city planning program was to have been carried out in 1947 and 1948 with ¥ 1,500,000 subsidized by the State for removal of the hospital with another 1,500,000 raised by the city. The State subsidy was however cancelled and the attempt failed. Why it was cancelled we do not know and the matter is left as it is.

A good site has been found at the Omiya High school, where the hospital may be moved out and as Dr. Hasumi agreed to it, the removal might

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

be effected, were it not for the removal expenses involved.

The expenses needed would amount to ¥ 3,000,000 - 5,000,000 but the city coffer would not permit the outlay of so much money at this time. The city authorities say that they will have the removal effected by all means although the expenses involved would be larger - about ¥ 5,000,000 from the previous ¥ 3,000,000. The city would have to raise the money by some means - floating loans or holding a bicycle race event to realize some funds. Anyway, Dr. Hasumi has been persisting these 5 years and now it would be time for him to give in for the sake of the city itself.

Health insurance program at a cross road at Konosu

Same as elsewhere, the national health insurance program at Konosu-machi is now standing on the cross road. The program was initiated in March this year and too many patients are depending on the program and with the enforcement of the social insurance program, under which the prefecture and the town will have to share the expenses, people seem to misuse the system. To alleviate the situation, it was ruled that half of the doctors' fees were to be paid at their counters and yet there is said to have been accumulated as much as ¥ 800,000 still unsettled with the doctors. 6 workers are engaged in the business day and night and yet they are kept busy all the time. The cause is said to be due to some of the larger contractors who do not recognize the importance of the program.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Nursing Aff.
Mrs. Mukaes

- General Affairs
- PHN Education
- PHN Supervision
- CN Education
- CN Supervision
- Midwives Edu.
- Midwives Supervision

千浦和 3808, administration
3904 Public Health
3806 Sanitation

Sanitation

Pharmaceutical Sec.

- General Affairs
- Medical Supply
- Drug Production
- Norcotic control

Public H. Section Dr. Dai

- General Affairs
- Health Center
- Maternal & child Health
- Dental Health
- Medical Social work
- Nutrition

Public Health Dep't
Dr. Yanai

Preventive Medicine Sec. Dr. Oka

- General affairs
- Communicable Disease
- T.B.
- V.D.
- Chronic Diseases

Sanitation section Nakamura H. Y.

- General Affairs
- Environmental Sanitation ---------- Water Works
  ---------- Rodent & Insect Control
- Veterinary affairs -- Animal disease
  Meat & milk
  Slaughter houses
- Food Sanitation

Administration Section Mr. Hoshino

- General Affairs
- Personnel and Badget
- Licensing
- Medical Affairs

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Lie 9 Haiti Center

埼玉縣

醫院名	所在地	所在地	建物所有	建物所有	建物所有
浦和保健所	浦和市岸町五丁目一二四番地	浦和市岸町五丁目一二四番地	滯荷	二一、二五〇〇	二四、六八八
川越保健所	川越市大字町一五〇五、二	川越市大字町一五〇五、二	〃	六七、四五〇	一八、五八九
松山保健所	高橋輝良	比企郡松山町松山四三六五	〃	二四五、〇〇〇	一三四、四四一
行田保健所	相馬徳郎	北埼玉郡行田町長野三七〇四	〃	一四五、〇〇〇	一一三、三〇〇
所澤保健所	山下	入間郡所澤町大字一二九五	〃	一七六、三〇五	一八一、四五九
草平保健所	倉持覺吉	北葛郡草平町一二九五	〃	二六、〇〇〇	九一、七一七
春日部保健所	工藤正章	南埼玉郡春日部町粕壁一二三	〃	二四五、〇〇〇	一三九、一二九
粧文保健所	有子章	粧文郡粧文町大字一二八九	倍額	七五、八五	一三〇、四六五
川口保健所	田中玄英	川口市上青木町一二五九七	水有	一六四、〇〇〇	一六〇、五六四
非江保健所	柚浦徳三	安江郡非江町四二四番地	水有	二五五、〇〇〇	一〇八、九五二
鹽谷保健所	鹽谷郡長	鹽谷市鹽谷一一五、一	〃	六六五〇〇	三四七、五七一

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

PREFECTURAL PUBLIC HEALTH DEPARTMENT ORGANIZATION PLAN

- **Administration Division**
  - General Affairs Section
    - General Affairs
    - Finance
    - Personnel
  - Medical Affairs Section
    - Doctors Affairs
    - Dental Affairs
    - Massage, Acupuncture, Moxaxeutery, Judo bone setting
    - Medical Institutions
    - *Physical Exam. of Allied Forces employees
  - Statistics Section
    - Vital Statistics
    - Medical Statistics
- **Pharmaceutical Division**
  - Pharmaceutical Section
    - Control of poison drugs
  - Drug Production Section
  - Supply-Distribution Section
    - Construction
  - Narcotic Section
- **Health Promotion Div.**
  - Health Promotion Section
  - Maternal-Child Care Section
    - Prenatal
    - Pediatric
    - Eugenic
  - Nutrition Section
  - Dental Section
  - Medical Social Section
  - Health Education Section
  - Mental Hygiene Section
- **Disease Prevention Div.**
  - Dis. Prevention Section
  - Chronic Disease Prevention Section
    - Parastitical
    - Cancer
    - Leprosy
    - Trachoma
    - Heart
  - TB Prevention Section
  - VD Prevention Section
  - Communicable Disease Prevention Sec.
- **Sanitation Div.**
  - Sanitation Section
    - Park & Playground
    - Insect & Rodent Control
    - Sewage & Garbage Disposal
    - Water Supply
    - Graveyard Burial
    - Barbers
    - Public Bldg. Sanitation
    - Bath Houses
  - Environmental Sanitation Section
  - Veterinary Section
    - Milk & Milk Production
    - Butchering & Slaughter House
    - Animal Disease
    - Fish & Shell
  - Food Sanitation Sec.
    - Restaurant & Food Handlers
    - Markets
    - Production
- **Nursing Affairs Div.**
  - Public Health Nursing Sec.
  - Midwifery Education Sec.
  - Midwifery Sec.
  - Clinical Nurse Education Sec.
  - Clinical Nursing Sec.
  - P.H. Education Sec.

Dr.'s Assoc.
Dentists' Assoc.
Nurses' Assoc.

Chief P.H.D.

Adm. Ass't

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

THE GOVERNMENT OF SAITAMA PREFECTURE
URAWA CITY, SAITAMA PREFECTURE

LO - 1238 29 November, 1949.

SUBJECT: REPORT CONCERNING THE MATTERS DECIDED AT THE REGULAR SESSION OF PREF. ASSEMBLY FOR OCTOBER, 1949.

TO : DR. ANNA R. MANITOFF, CHIEF OF PUBLIC HEALTH SECTION, KANTO CIVIL AFFAIRS REGION

The regular session of Saitama Pref. Assembly for October was held for fourteen days from 28 Oct. to 10 November to discuss the bills presented to the Assembly. The matters decided relating to Health and Sanitation Expenses are submitted to you for your reference as per inclosure.

Dr. S. Kanai.
Chief of Public Health Dept.
Saitama Pref.

2 Incls.

1. Health and Sanitation Expenses.
2. By-law concerning prevention of rabies.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Incl: 1.

Total amount of supplementary budget of annual expenditure for Health and Sanitation : ¥31,868,260

Details:

1.	Construction expense of hygienic Laboratory :	¥16,387,000
2.	Construction expense of Omiya Health Center :	¥ 6,600,000
3.	Expenses for prevention of rabies:	¥ 2,804,770
4.	Expenses for tuberculosis medical treatment facilities :	¥ 2,150,000
5.	Expenses for simultaneous examination of sucklings :	¥ 748,060
6.	Expenses for Rodent and Insect Control :	¥ 2,393,940
	(Purchase expenses of motor-car for disease prevention use)	
7.	Others :	¥ 784,490

Total amount of Health and Sanitation annual expenses defrayed so far : ¥136,083,300

Total amount of supplementary budget of annual income for Health and Sanitation : ¥ 19,798,510

Details:

1.	Expenses defrayed by State :	¥ 7,178,500
	Subsidy for arrangement of Omiya Health Center :	¥ 1,000,000
	Expenses for construction of Hygienic Laboratory :	¥ 6,000,000
	Subsidy for others :	¥ 178,500
2.	Donation :	¥ 8,994,010
	Donation for the construction of Omiya Health Center :	¥ 2,800,000
	Donation for the construction of Hygienic Laboratory :	¥ 5,000,000
	Donation for the purchase of motor-car for disease prevention use :	¥ 1,093,010
	Donation for others :	¥ 101,000

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

3.	Miscellaneous incomes :	
	Fee of preventive injection against rabies :	¥ 3,500,000
4.	Others :	¥ 126,000

Total amount of annual income for Health and Sanitation expenses : ¥96,886,430

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

KCAR

From: G Liaison Officer 16 Sept 1949

3. The Prefectural Government of Saitama

(1) Establishment

On 1 July 1948, Nursing Section was established in Sanitary Bureau.

(2) Organization and staff

a.	Nursing Section:	1
b.	General Affairs Sub-Section:	5
c.	Public Health Nurse Sub-Section:	2
d.	Midwife Sub-Section:	2
e.	Nurse Sub-Section:	2
	Total	12

(3) Budget

Total of Baget from April, 1949 to March 1950 ¥ 1,440,000

a.	working expenses for Nurses	¥ 347,960
b.	expenses for training school of Public Health Nurses	¥ 446,350
c.	expenses of "B" class Nurse schools	¥ 700,000
d.	expenses for Medical Affairs	¥ 49,800
e.	expenses of the guidance for public health	¥ 97,180

Saitama Pref.

1949 Budget

縣の豫算と衛生部豫算との比較　24.10 縣会現計

衛生部總務課

区分	豫算額	縣予算に対する衛生部予算の率
縣の豫算	43億43.294.860円	
衛生部の豫算	1億36.083.300円	3.1%強

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

公衆衛生院衛生技術者再教育講習終了者調

学科名	講習者氏名
医学科	田島三吉 (22.12)、倉持亀吉 (23.3)、豊住政治郎 (23.7)、仁羅山秘 (23.12)、岡崎正太郎 (24.3)、金子章 (24.6)、
	者木敏生 (24.9)
衛生薬学科	加藤徳成 (23.3)、大河原新 (23.7)、川島浩 (23.9)、弓削清一郎 (23.12)、田部井康次 (24.3)
栄養学科	野尻清 (23.7)、金原壮 (23.10)、者兼俊子 (24.1)
衛生獣医学科	石川清敏 (23.3)、八谷順次郎 (23.6)、小原行夫 (23.8)、伊兼貞三 (23.12)、卜部保夫 (24.3)、吉田茂行 (24.6)
	野口繁 (24.8)、田中覚 (24.10)、富山政文 (24.11より)
衛生監視学科	草野稔 (23.3)、持木清 (23.7)、桑江昇 (23.10)、新衛者治 (24.3)
衛生工学科	西原重義 (23.8)、市川昇 (23.11)
衛生看護学科	牛込すえ (22.7)、今井好 (23.3)、長谷川種子 (23.3)、橋本秀子 (23.7)、吉川ちよ (23.7)、飯島彦重 (23.11)
	平アキ (24.3)、市原ふを (24.7)、平ゆき (24.11)、持田兆子 (24.11)、神谷智恵子 (24.12より)

備考 ( ) は講習終了年月なり

Live & Hospitals

加須保健所

所在地	名稱	病床数	所在地	名稱	病床数	所在地	名稱	病床数
久喜町	上宮本医院	3	加須町	南根医院	3	栢間村	大野医院	4
菖蒲町	島田医院	9	〃	梅沢 〃	9	久喜町	粕川 〃	3
三箇村	川石 〃	8	〃	島田 〃	3	加須町	柿沼 〃	4
加須町	宮本 〃	1	〃	加味 〃	3	〃	内田 〃	1
〃	中井 〃	(休止中) 2	〃	板村 〃	5			
〃	福島 〃	9	〃	坪井 〃	2	合計	16	76

春日部保健所

武里村	石川医院	6	和土村	岡田医院	6	松伏町村	宮里医院	6
蓮田町	金山 〃	5	越谷町	横田 〃	伝染4			
春日部町	粕壁 〃	5	八條村	岡田 〃	4			
岩槻町	虎加 〃	2	越谷	石川 〃	3			
〃	大橋 〃	5	岩槻	長井 〃	2	合計	11	総42 伝染4

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

縣下医療施設調

埼玉縣衛生部

昭和24年12月1日現在

(1) 病院

病類別＼病床別	病院数	病床別				官公立	国民保険 健康保険	農協立	日赤	其の他の法人	私立
		結核	精神	伝染	其の他						
結核	5	854		15	35	2			1	1	1
精神	4		400	7	28						4
其の他	102	388		301	2554	4	3	3	1	7	88
計	111	1252	400	323	2617	6	3	3	2	8	93

(2) 病室を有する診療所

保健所名	数	病床数	保健所名	数	病床数	保健所名	数	病床数	保健所名	数	病床数
浦和	27	137	熊谷	29	普 125 結 12	総文	5	25	春日部	11	普 42 伝 8
川口	17	80	鄕国	16	58	本庄	12	56			普通 1022
大宮	19	109	所沢	15	68	加須	16	76			伝染 10
川越	21	123	松山	17	96	幸手	7	普 27 伝 2	計	212	結核 12

(3)、病室を有しない診療所及歯科診療所

診療所				歯科診療所			
保健所名	施設数	保健所名	施設数	保健所名	施設数	保健所名	施設数
浦和保健所	108	本庄保健所	36	浦和保健所	85	本庄保健所	21
川口 〃	42	熊谷 〃	94	川口	50	熊谷 〃	64
川越 〃	64	行田 〃	44	川越	46	行田 〃	27
大宮 〃	71	加須 〃	51	大宮	53	加須 〃	30
所沢 〃	59	秩父 〃	47	所沢	46	秩父 〃	33
秩父 〃	46	春日部 〃	28	秩父	27	春日部 〃	21
松山 〃	39	計	729	松山	24	計	527

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

医療関係者数

保健所名	医師	歯科医師	あん摩師	はり師	きゅう師	医業類似行為	柔道整復師
浦和保健所	243	134	84	74	66	69	18
川口 〃	114	54	98	66	62	29	8
川越 〃	139	56	83	69	72	56	26
大宮 〃	156	105	187	105	102	9	41
所沢 〃	121	57	28	84	50	16	20
秩父 〃	73	37	45	21	22	10	13
松山 〃	79	34	83	48	32	12	8
本庄 〃	67	28	37	28	16	8	8
熊谷 〃	178	77	178	118	89	27	20
行田 〃	83	32	180	67	61	15	6
加須 〃	92	34	104	4	13	10	5
春日部 〃	111	51	44	3	6	14	9
幸手 〃	56	30	65	24	31	10	5
合計	1,512	729	1196	659	150	317	155

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

縣下病院一覧表

埼玉縣衛生部

現在(昭和24年12月1日)

(1) 結核病院

経営別	所在地	名稱	病床別 結核	精神病	伝染病	その他	備考
國立	南埼玉郡里浜村	國立埼玉療養所	525				
〃	入間郡豊岡町	國立療養所豊岡病院	150				
日赤赤十字社	比企郡小川町	小川赤十字病院	119		15	35	
医師会	秩父郡荒川村	秩父郡医師会病院	50				
私立	浦和市高砂町	仲田病院	20				
(5)	合計		864		15	35	

(2) 精神病院

経営別	所在地	名稱	病床別 結核	精神病	伝染病	その他	備考
私立	入間郡毛呂山町	毛呂病院		149	3	28	代用病院
私立	川越市	川越同仁病院		60			
私立	熊谷市	熊谷脳病院		120			

(1)

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

経営別	所在地	名称	病床別 結核	精神	伝染病	その他	備考
私立	浦和市別所	浦和脳病院		71	4		
	合計	4		400	7	28	

(3) 一般病院

経営別	所在地	名称	病床別 結核	精神病	伝染病	その他	備考
日本赤十字社	北足立郡吉野町	大宮赤十字病院	30		11	64	
社会保険厚生会	浦和市常盤町	社会保険第一病院				27	
〃	浦和市大谷口	財団法人埼玉厚生会尚和園病院				20	養老院
国立	北足立郡大和町	国立埼玉病院	116		20	64	
国立	入間郡所沢町	国立所沢病院	24			76	
済生会	川口市仁志町	川口済生会病院	20			65	
町立	入間郡所沢町	町立所沢病院			30	10	
町立	入間郡深谷町	町立深谷病院	10		10	10	
国民健康保険組合	川口市本町	川口市民病院				80	
〃	入間郡東吾野村	東吾野病院	10			10	未開設

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

経営別	所在地	名称	病床別 結核	精神	伝染	その他	備考
健保	大宮市高鼻町	健康保険大宮病院				20	
農業協同組合	熊谷市大字熊谷	熊谷協同組合病院				53	
全	北埼玉郡幸手町	幸手協同組合病院	20		11	62	
全	南埼玉郡春日部町	春日部協同組合病院			23	18	
戦災団体	南埼玉郡南桜井村	子供の町財団病院				20	休止状態
会社立	川口市芝	日本車輌工場東京支店病院	4			20	
〃	北足立郡大和町新倉	中央工業株式会社中央新生病院				20	
〃	北足立郡上尾町	東洋時計上尾工場附属病院				25	
〃	秩父郡影森村	昭和電工株式会社秩父工場附属病院				21	
私立	浦和市常盤町	高田病院				21	
〃	浦和市仲町	浦和病院			33	8	
〃	浦和市原山新田	関根病院			42		
〃	浦和市高砂町	名古屋病院				20	
〃	浦和市高砂町	川久保病院				21	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 773 013

経営別	所在地	名称	病床別				備考
			結核	精神	伝染	その他	
私立	北足立郡戸田町	荘病院				20	
〃	北足立郡内間木村	村山病院				20	
〃	川口市青木町	小島病院				20	
〃	川口市元郷町	宮岡病院				24	
〃	川口市本町	柳田病院				21	
〃	川口市青木町	佐藤病院				20	
〃	川口市福久	渡辺病院				20	
〃	川口市本町	北條外科病院				21	
〃	川口市本町	仁天堂 高橋病院				22	
〃	北足立郡草加町	天真堂 三宅病院				20	
〃	北足立郡草加町	花上病院				22	
〃	北足立郡草加町	丸山病院				20	
〃	大宮市土手町	荻原同仁病院				30	
〃	大宮市大宮	蓮見病院				25	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

経営別	所在地	名称	病床別				備考
			結核	精神	伝染	その他	
私立	大宮市大字大宮	須田病院				26	
〃	〃	三有堂 栄田病院				21	
〃	〃 大字高鼻	宇治病院	9			20	
〃	〃 大字大宮	至誠堂病院				20	
〃	〃 大字大成	大成病院				38	
〃	北足立郡浦和町	河野病院	30		12	15	
〃	〃	中村病院				41	
〃	北足立郡岩槻町大字村	みだ眼科 周行病院				25	
〃	川越市大字小仙波	私立埼玉病院			12	30	
〃	川越市大字川越	橋村病院			35	12	
〃	〃	川越病院			18	13	
〃	〃	須永病院			20	18	
〃	〃	吉川病院				20	
〃	〃	岸産婦人科病院				20	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

経営別	所在地	名称	病床別				備考
			結核	精中	伝染	其ノ他	
私立	川越市大字川越	佐藤病院				20	
〃	〃 大字野田	赤心堂病院				22	
〃	入間郡坂戸町	公立産婦人科病院				21	
〃	〃	吉川病院				24	
〃	入間郡勝呂村	勝呂病院			8	12	
〃	入間郡越生町	長生部病院				22	
〃	大里郡熊谷村	紫仏堂 高橋病院				21	
〃	熊谷市大字御正	藤岡病院				20	肝炎中
〃	〃	熊谷外科病院				25(26)	
〃	大里郡深谷町	下部病院	5			24	
〃	熊谷市大字熊谷	大関病院				20	肝炎中
〃	行田市大字佐間	田代病院				20	
〃	北埼玉郡太田村	蓮江病院				33	
〃	北埼玉郡川俣村	平野病院				20	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

経営別	所在地	名称	病床別				備考
			結核	精神	伝染	その他	
私立	入間郡飯能町	蓮江病院				20	
〃	〃	君塚病院				22	
〃	〃	小室病院				20	
〃	〃	石井病院				28	
〃	〃	山口病院				28	
〃	〃	飯能病院				22	
〃	入間郡入間川町	村上病院				20	
〃	〃	田中病院			10	12	
〃	入間郡所沢町	斉藤病院				25	
〃	〃	高井病院				23	
〃	比企郡松山町	須田病院				20	
〃	比企郡小川町	宮崎産婦人科病院				21	
〃	比企郡大河村	野崎病院				22	
〃	秩父郡秩父町	佐藤産婦人科病院				22	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

経営別	所在地	名称	病床別				備考
			結核	精神	伝染	その他	
私立	秩父郡秩父町	秩父病院				25	
〃	〃	松本病院				20	
〃	〃	内田病院				20	
〃	〃	岩田病院				21	
〃	〃	三上病院				20	
〃	〃	荒木眼科病院				20	
〃	〃	健生堂病院				25	
〃	秩父郡野上町	葵合眼科病院				80	
〃	〃 吉田町	新井病院				20	
〃	〃 皆野町	清水病院				22	
〃	児玉郡本庄町	本庄外科病院				21	
〃	〃	高橋外科病院				24	
〃	〃	青木外科病院				20	
〃	〃	福島小児科病院				20	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 773 013

経営別	所在地	名称	病床別				備考
			結核	精神	伝染	その他	
私立	児玉郡東児玉村	春山眼科病院				21	
〃	南埼玉郡久喜町	中宮本病院				20	
〃	〃	新井病院				20	
〃	〃	建江病院				20	
〃	南埼玉郡岩槻町	丸山病院				20	
〃	南埼玉郡越ヶ谷町	小口病院				20	
〃	北足立郡蕨町	浴水堂 斉藤病院			6	17	
〃	熊谷市大字鎌ヶ	河野内科病院				20	
	合計	102	388		301	2554	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 773 013

病室を有する診療所

埼玉縣衛生部

昭和24年12月1日現在

浦和保健所

所在地	名称	病床数	所在地	名称	病床数	所在地	名称	病床数
浦和	石塚眼科医院	4	浦和	渡辺医院	5	戸田町	中島医院	2
〃	大久保医院	2	〃	調 〃	2	朝霞町	朝霞医院	4
〃	石川医院	6	〃	伊藤 〃	9	浦和市	岩崎 〃	4
〃	藤生 〃	3	〃	山田 〃	4	蕨町	飯島 〃	5
〃	小峰 〃	2	〃	若山 〃	8	志木	細田 〃	6
〃	小野 〃	7	〃	青木 〃	6		計27	137
〃	三田 〃	9	與野町	島田 〃	4			
〃	滝本 〃	3	〃	坂 〃	5			
〃	宮崎 〃	3	〃	深美 〃	4			
〃	大畑 〃	4	〃	小川 〃	4			
〃	吉野 〃	5	〃	田中計器診療所	9			

川口保健所

所在地	名称	病床数	所在地	名称	病床数	所在地	名称	病床数
川口市	塚田医院	4	川口市	田沼医院	3	草加町	恵風堂医院	5
〃	樋口 〃	3	〃	石森 〃	7	川口市	桜井眼科医院	8
〃	船津 〃	3	〃	佐野 〃	3	〃	民生産業 川口工場診療所	9
〃	民生産業 神根診療所	9	〃	清水 〃	3	〃	高木医院	2
〃	荻島医院	3	〃	北見 〃	8	〃	森 〃	2
〃	永井 〃	2	草加町	小川 〃	6	計	永井 〃	40

所澤保健所

所在地	名称	病床数	所在地	名称	病床数	所在地	名称	病床数
飯能町	胖見製糸工場養生院	4	所沢町	桐原医院	1	飯能町	小川医院	5
所沢町	所澤眼科医院	3	豊岡町	小室 〃	6	〃	八木橋皮科	8
〃	秋山医院	6	〃	阿部 〃	4	〃	永井 〃	5
〃	斉藤 〃	3	入間町	安育 〃	6	〃	久保 〃	6
〃	道又 〃	2	〃	島崎 〃	6	〃	比留間 〃	3
							計 15	64

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

川越保健所

所在地	名稱	病床数	所在地	名稱	病床数	所在地	名稱	病床数
川越市	川越市国保診療所	15	川越市	宮崎産婦人科医院	7	南古谷村	清水医院	3
〃	日清紡績川越工場診療所	9	〃	加島眼科院	3	入西村	村田 〃	4
〃	忽滑谷医院	9	〃	浅田医院	2	毛呂山町	堀江 〃	2
〃	半沢 〃	8	〃	時田 〃	2	越生町	平沼 〃	6
〃	佐々木 〃	4	〃	岡田 〃	5	川越市	小杉眼科 〃	6
〃	武藏野 〃	7	〃	大河内 〃	9	〃	森山 〃	4
〃	管原 〃	6	坂戸町	御厨 〃	9	〃	高山 〃	3
						合計	21	123

幸手保健所

所在地	名稱	病床数	所在地	名稱	病床数	所在地	名稱	病床数
栗橋町	浅川医院	2	幸松村	梅原医院	4	八代村	岡安医院	1
杉所	山本 〃	4	上高野村	丸山医院	普 6 伝 2			
〃	今井 〃	4	栗橋町	渡辺 〃	6	計	7	普 27 伝 2

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

(2)

行田保健所

所在地	名稱	病床数	処在地	名稱	病床数	処在地	名稱	病床数
行田市	栗原医院	6	行田市	吉川医院 (休業中)	2	行田市	柳田医院	2
〃	川島 〃	8	〃	野口 〃	4	〃	小池 〃	4
共和村	本郷 〃	6	須加村	川島 〃	5	〃	村上 〃	2
行田	小堀 〃	2	行田市	村越 〃	4	〃	山下 〃	6
〃	中野 〃	4	〃	高野 〃	2	須影	今成 〃	1
						合計	16	58

大宮保健所

所在地	名稱	病床数	所在地	名稱	病床数	所在地	名稱	病床数
大宮市	片倉製糸診療所	8	鴻巣町	若山医院	3	大宮市	大野医院	3
平方町	平方国保診療所	15	〃	熊井 〃	5	〃	清水 〃	3
大石村	鯵坂医院	3	〃	山崎 〃	9	〃	林 〃	2
上尾町	岸出 〃	13	〃	葛海 〃	2	〃	塚田 〃	3
大宮市	佐味 〃	2	桶川町	田中 〃	2	〃	みた診療所	9
鴻巣町	鴻巣医院	9	大宮市	市川 〃	3	吹上町	昭和医院	10
吹上町	横田医院	5				合計	19	109

能去保健所

所在地	名称	病床数	所在地	名称	病床数	所在地	名称	病床数
能出市	県立診療所	9	能出市	志村医院	2	深出町	新医院	3
〃	大屋医院	2	〃	中川〃	6	〃	桔梗医院	4
〃	大関〃	4	〃	吹田〃	7	〃	田部井〃	4
〃	高野〃	2	〃	仁丸〃	1	〃	萩野〃	7
〃	飯田〃	6	〃	梅沢〃	8	〃	風間〃	3
〃	肥留川〃	3	〃	小林〃	2	〃	国松〃	2
〃	大沢〃	9	壷沼	鈴木〃	9	能北村	清水〃	1
〃	萩野〃	4	〃	坂田〃	6	用土村	清水〃	5
等岳町	野原〃	8	等岳町	松本医院	4	能北市	西田〃	総数 12
〃	山田〃	3	〃	内田〃	1	合計	29	普 125 特 12

秩父保健所

秩父町	柏崎医院	6	秩父町	奥野医院	6	上朝村	塚越医院	1
〃	近栄〃	6	大滝村	鉄文鉱山診療所	6	合計	5	25

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

本庄保健所

所在地	名称	病床数	所在地	名称	病床数	所在地	名称	病床数
本庄町	塚越医院	3	本庄町	立野医院	7	本庄町	牛山産院	4
〃	飯塚〃	4	〃	塩宮〃	5	〃	今野医院	2 48時間適用
〃	蓮尼〃	9	〃	飯塚産婦人科〃	5	児玉町	鈴木〃	5
〃	山内〃	5	藤田村	松本〃	4	本庄町	富士紡績工場診療所	3
						合計	12	56

松山保健所

松山町	柳医院	8	神川町	木下医院	7	三保谷村	小久保医院	2
〃	松本〃	9	〃	関根〃	9	福川村	福川村国保診療所	15
〃	内山〃	9	宮前村	上野〃	5	松山町	河野外科医院	2 48時間適用
〃	峯〃	4	管谷村	水野〃	3			
〃	高山〃	4	神川町	原〃	1			
〃	鈴木〃	4	〃	瀬川〃	6			
野本村	関部〃	4	〃	中村〃	4	合計	17	96

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

加須保健所

所在地	名称	病床数	所在地	名称	病床数	所在地	名称	病床数
久喜町	上宮本医院	3	加須町	南根医院	3	栢間村	大野医院	4
菖蒲町	島田医院	9	〃	桜沢 〃	9	久喜町	粉川 〃	3
三箇村	川石 〃	8	〃	島田 〃	3	加須町	柿沼 〃	4
加須町	宮本 〃	1	〃	加味 〃	3	〃	内田 〃	1
〃	中井 〃	2 (休止中)	〃	松村 〃	5			
〃	福島 〃	9	〃	坪井 〃	2	合計	16	76

春日部保健所

武里村	石川医院	6	和土村	岡田医院	6	松伏領村	宮里医院	6
蓮田町	金山 〃	5	春日部町	横田 〃	休業中			
春日部町	粕壁 〃	5	八條村	岡田 〃	4			
岩槻	春松 〃	2	越谷	石川 〃	3			
〃	大橋 〃	5	岩槻	長井 〃	2	合計	11	休42 伝4

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 73 013

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

1949年埼玉県月別年令別死亡者数

年令別＼月別	1月	2月	3月	4月	5月	6月	計
0	148	138	146	113	124	91	760
1	102	81	88	76	78	74	499
2	32	40	30	34	46	21	203
3	14	11	16	16	23	27	107
4	9	8	9	13	13	24	76
5～9	22	26	34	27	29	47	205
10～14	21	14	24	26	26	27	139
15～19	42	34	37	43	48	68	283
20～24	88	64	84	94	91	101	523
25～29	62	64	90	88	~~71~~ 91	84	481
30～34	73	60	64	79	~~66~~ 76	63	384
35～39	58	67	66	50	~~79~~ 66	64	361
40～44	64	64	60	76	~~64~~ 79	64	408
45～49	67	54	84	74	~~94~~ 64	59	399
50～54	91	80	92	86	~~47~~ 91	87	527
55～59	124	114	144	106	117	110	616
60～64	893	849	934	828	825	698	5028
年令不詳	6	3		3	1	4	17
合計	2336	2096	2344	2130	2015	1998	12919

埼玉縣

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

1949年埼玉県主要死因別死亡者統計

主要死因別	性別	1月	2月	3月	4月	5月	6月
腸チフス		2	4				
早産		29	27	40	27	29	26
下痢及び腸炎腸潰瘍		141	133	152	129	135	180
全心臓の疾患		138	132	150	146	137	123
流行性脳脊髄膜炎		2	1	1	1	1	1
百日咳		29	16	13	25	14	25
ジフテリヤ		4	2	1	2	1	
破傷風		6	2	2	2	9	4
癩		1	1				1
赤痢			4	2	2	11	35
梅毒		11	13	11	10	9	9
流行性感冒			1		1		
全結核		220	179	225	237	283	268
麻疹		2	4	10	24	69	66
日本脳炎							1
狂犬病			1	1	2	1	1
発疹チフス及同様疾患				1			
癌及び其の他悪性腫瘍		134	100	122	136	153	139
糖尿病		3	8	1	2	5	4
脚気		10	10	13	10	10	3

埼玉縣

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

	不慮の傷害	55	28	40	49	49	54
	単純性髄膜炎	22	13	22	26	7	18
	頭蓋内血管の損傷	309	269	307	259	250	240
	気管支炎	64	109	122	84	69	66
	肺炎	197	233	181	163	105	95
	胸膜炎(結核性を除く)	10	17	14	19	13	12
	猩紅熱				2		1
	急性灰白脊髄炎					1	2
	マラリヤ						1
	胃又は十二指腸の潰瘍	58	35	52	36	47	32
	虫垂炎	4	4	5	3	8	7
	賢炎	93	55	90	59	79	62
	妊娠分娩及び産褥疾患	12	11	11	14	11	8
	先天性奇形(兎唇を除く)	14	18	17	13	22	15
埼	先天性弱質	147	103	130	83	68	83
	分娩に依る産児の傷害	2		3	3		1
	老衰	185	164	134	143	118	102
玉	自殺	23	24	17	33	32	38
	他殺	4	1	1	4	7	1
縣	不詳の横死	44	40	72	44	30	44
	その他全死因	334	307	320	306	244	267
	合計	2336	2096	2328	2125 2088	2015	1995

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣

1948年埼玉縣月別人口動態統計

月別	出生数	死亡数	乳児死亡数	死産数	婚姻	離婚		出産数	死亡数
1	7.160	2.496	550	319	1.710	65		7.479	3.046
2	7.240	2.397	539	354	2.760	107		7.594	2.936
3	7.402	2.711	571	342	2.896	130		7.744	3.282
4	5.674	2.036	325	360	2.616	135		6.034	2.361
5	5.225	1.943	296	319	2.648	158		5.544	2.239
6	4.550	1.769	274	283	1.555	95		4.833	2.043
7	5.287	2.181	308	302	1.478	108		5.589	2.489
8	5.644	2.137	244	314	1.319	131		5.958	2.381
9	5.597	1.889	250	302	1.380	137		5.899	2.139
10	5.566	1.699	239	305	1.419	114		5.871	1.938
11	5.855	1.858	334	351	1.460	146		6.206	2.192
12	5.663	1.045	419	329	1.937	158		5.992	1.464
	70.863	24.161	4.349	3.880	23.178	1.484		74.743	28.510

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 773013

秘 密 扱

1949年 埼玉縣月別人口動態統計

月別	出生数 総数	男	女	満一才未満(死亡) 総数	男	女	その他(死亡) 総数	男	女	死産胎数 総数	男	女	不詳	結婚	離婚
1	7,771	4,011	3,760	465	201	264	1,811	986	825	426	226	200	12	2,093	113
2	6,314	3,314	3,000	316	271	245	1,607	832	775	361	187	163	11	2,330	133
3	6,889	3,421	3,468	411	270	239	1,876	990	886	382	216	160	6	2,223	136
4	7,886	3,850	3,836	381	214	167	1,765	936	829	390	229	150	11	2,327	140
5	7,229	3,763	3,463	316	177	139	1,685	862	823	411	219	176	16	2,274	133
6	7,413	3,805	3,608	368	199	169	1,705	874	831	368	199	169	16	1,372	108
7	7,213	3,741	3,472	366	183	183	1,666	866	800	345	181	164	11	1,213	111
8	7,076	3,689	3,387	366	179	187	1,666	866	800	345	181	164	11	1,213	111
9	7,076	3,689	3,387	366	179	187	1,666	866	800	345	181	164	11	1,213	111
10	7,076	3,689	3,387	366	179	187	1,666	866	800	345	181	164	11	1,213	111
11	7,076	3,689	3,387	366	179	187	1,666	866	800	345	181	164	11	1,213	111
12	7,076	3,689	3,387	366	179	187	1,666	866	800	345	181	164	11	1,213	111

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣

1949年埼玉縣出產數及死亡數

月別 \ 種別	出產數				死亡數		
	總數	男	女	不詳	總數	男	女
1	8,207	4,235	3960	12	2,376	1285	1091
2	6,675	3501	3163	11	2,121	1103	1018
3	7,271	3,637	3628	6	2,385	1216	1123
4	6,255	3259	1980	11	2140	1150	996
5	5,703	2948	~~2566~~ 2739	16	2001	1039	962
6	5,320	2738	2566	16	2010	1028	982
7	5,730	3,035	2684	11	2318	1178	1140
8	6482	3367	~~[illegible]~~ 3105	10	2266	1120	1146
9	6,301	3371	2917	13	1,969	994	975
10	6,265	3316	2,937	12	1,878	951	927

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣

1949年埼玉縣月別伝染病統計 (NO1)

病類別 / 月別	赤痢 患	赤痢 死	疫痢 患	疫痢 死	腸チフス 患	腸チフス 死	パラチフス 患	パラチフス 死	痘瘡 患	痘瘡 死	發疹チフス 患	發疹チフス 死	腸紀熱 患	腸紀熱 死	ヴィブリア 患	ヴィブリア 死	流腸 患	流腸 死	日本腸炎 患	日本腸炎 死
1	1		2		15	2	4						9		33	4	1			
2	3		1	2	8	2							7		27	3	5	2		
3	3	1	3	5	14	1	1						13		39	1	2	1		
4	2		4	1	7	3	4						29	2	27	3	7	2		
5	10	2	14	8	13	3	4						27		31	2	1	1		
6	47	4	70	35	72	12	20						106	3	177	13	18	7		
7	239	9	291	122	24	3	5						31	1	28	2	2	1		
8	256	14	338	148	33	3	12						12		13	1	3	1		
9	158	15	210	83	25	1	12						7		24		4	1	9	
10	39	4	63	27	14	1							17		26		2	1	5	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣

1949年埼玉縣月別伝染病統計 (No2)

	初マラリヤ	再マラリア	麻疹	百日咳	流胃腸	急性灰白	破傷風	肺	癸	臺橋熱	呼吸器結核	其の他結核	癩	紅犬病	トラコーマ	伝染性下痢
1			26	214 ~~219~~ 3	1	2	6 3	401	47	5	477	118 36 13			112	
2		1	62	219 4		5		519	81	2	440	71 64 14	1 1		102	
3		2	163	200 3	12		1 1	481	97	1	681	148 115 28	1	1 2	182	
4		1	362 8	227 7	32 1	1 1	2	369	117	2	774	139 87 22		1 1	168	
5		4	818 18	400 15	11 5	6 1	10 2	488	144	5	881	289 113 55		1 2	1069	
6		3	918 31	394 16		2	6 3	368	90	1	716	186 115 30	2	1 2	1442	
7	2	1	611 43	798 42		8	6 5	356	118	6	840	182 133 51	1		594	
8	1	4	370 25	1054 36		15	5 5	246	94	5	846	206 171 55		3 1	438	
9	2	5	91 4	519 21		10	9 1	212	57	3	878	138 143 43		2	317	
10		3	130 6	311 30		7	15 6	312	87	11	860	257 105 50	7	1 1	572	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

1949年埼玉縣月別傳染病統計 (No3)

病別 男女別 / 月別	梅毒 男	梅毒 女	淋病 男	淋病 女	軟性下疳 男	軟性下疳 女	鼠蹊淋巴肉芽腫症 男	鼠蹊淋巴肉芽腫症 女
1	105	62	86	28	10	1		
2	127	92	86	46	18	4		1
3	100	99	70	41	6	3	1	1
4	111	91	100	34	6	4		
5	141	175	102	75	14	5		
6	118	133	96	60	9	3		
7	137	132	113	69	6	3		
8	80	84	118	56	5	3		
9	122	95	106	52	11	6		
10	138	88	104	72	9	1		

埼玉縣

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

全国 昭和10～23年人口自然増加率（人口1,000対）

22.23年の対照のため沖縄を除いて改算した率



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣年令別結核死亡者

（昭和23.1～12月）



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣市郡別男女別結核死亡者数(昭和23.1～12月)



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

埼玉縣十大乳児主要死因(満才未満)死亡者数(昭和23.1～12月)



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

24832

埼玉縣十大主要死因別死亡者数（昭和23.1～12月）



DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Summary 1948

B. Disease Prevention Section, Venereal Disease Division

Venereal disease treatment rates have increased because of improved case follow-up methods. A total of 42,710 treatments were known to have been given during the year resulting in 2,107 cures. A total of 8,943 are now under treatment. The difference in this number and the 4,284 new cases reported this year results from a carry over of 8,433 untreated patients from previous years. Case finding techniques have shown some improvement. Blood tests were done on 25,258 persons in venereal disease clinics, 90,000 were done on pre-natal patients and an unknown number during the routine physical examination. Unfortunately the nurata method of testing was used in many of these cases. Actually the work of this Division may be summarized by saying that a firm foundation has been laid for a more effective program next year.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Summary 1948

i, Health Promotion Section, Dental Division

Particular emphasis has been placed on dental care for prenatal patients and for school children. A worthwhile educational program has also been launched.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

~~ratings are gradually improving~~.

3. Dental Affairs.

a. Dental clinic facilities are available in only the Model Health Center at the present time. An effort is being made to establish dental clinics in the other health centers. In the meantime, pre-natal patients and school children who need dental care are being referred to private dentists. Welfare assistance is being requested for those patients who are eligible but there is still a considerable group of persons from the low-average income group who are unable to receive adequate dental care until health center facilites are estabLished.

b. Mass dental examinations were given at three schools in the Model Health Center District.

c. A total of 427 patients were examined and 334 patients treated in the Model Health Center dental clinic last month.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

P. Disease Prevention Section, Communicable Disease Division

Summary 1948

Although two epidemics occurred during the year, the common communicable disease rates dropped significantly.

In May an epidemic of diarrhea peculiar to adults in Kodama gun occurred. A total of 650 cases was reported. Despite numerous tests and examinations, no causative organism was isolated.

In August, a Japanese B Encephalitis epidemic occurred with a total of 307 cases and 77 deaths.

The number of diphtheria cases dropped from 629 in 1947 to 374 in 1948.

Dysentery rates during the month of July dropped to 19% of the rates during the same period in 1947. Saitama showed the third greatest reduction in Japan that month. The years total dropped from 724 in 1947 to 410 in 1948.

Typhoid immunization and improved sanitation cut the number of typhoid cases from 488 in 1947 to 244 in 1948.

There were no smallpox cases in Saitama this year.

A murine typhus epidemic was averted by prompt action of this Division when 20 cases were reported in Ogawa. Approximately 80,000 inoculations were given, an excellent insect and rodent control went into effect and a house to house teaching campaign and survey for more cases was made.

The long hours spent in enthusiastic work by the members of the disease Prevention Section and the results obtained during the year deserve commendation.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Summary 1948

M. Disease Prevention Section, Tuberculosis Division

A total of 6,554 cases of TB were reported this year. This shows a great increase over last year because of the case finding work done by this Division. For example, during the last four months, 80,190 school children, 4677 factory employees and 27850 ordinary citizens had tuberculin tests; 5175 school children, 631 factory workers and 9384 ordinary citizens had BCG; 2078 school children, 2612 factory workers, and 3803 ordinary citizens had flouroscopes; and 35 school children, 54 factory workers and 140 citizens had X-ray. Wide spread educational programs have made the citizens conscious of the danger of tuberculosis and more and more people come voluntarily to the health centers for examination. An excellent system of follow-up work by the Public Health Nurses has also been established.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Insect and rodent control in Saitama is a village progect which is carried out under the supervision of the health center inspectors. Each village in the prefecture has insect and rodent control personnel.
Please see report of village inspections.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Health Education

This is a most outstanding Division. Mr Moriya the Chief is doing a wonderful piece of work. He distributes thousands of informational pamphlets, posters and leaflets a month. He does not depend entirely on national posters but prints many very fine ones within the prefecture.

Through the efforts of Mr. Moriya both through publications and through speechs and movies at Women's Association meetings Mr. Moriya has the whole prefecture talking health.

This was evidenced recently when a major change was about to be made in the prefectural department and thousands of letters poured in supporting the work of the department.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

b. Maternal and Child Care

(1) During the last six months the death rates of still births and miscarriage has dropped from 4.6% to 3.8%. If this reduced rate can be maintained, it will represent a saving of 1295 lives in one year.

(2) A total of 886 prenatal patients received complete physical examinations in the health centers last month. This represents 100% of the known pregnancies in many areas.

(3) A total of 387 infants and 181 pre-school age children attended health center well-child clinics.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Maternal and Ch d Care

This is an outstanding Division. It has really taken prenatal care out to the rice paddies. Please note on the village inspection reports that each village health department reports a very high percentage of its p enatal patients having had physical examinations.

The midwives do monthly physical exami ations also and turn all patients with untoward symptoms over to the doctor immediately.

The program was furthered by an arrangement with the food distribution office to allow supplementary rations for pregnant women as soon as their first ph sical examiniation by a physcican has been done. This allows rations for those who report under the fifth month of pregnancy. These rations are of course not staple foods but consist of tofu,cheese and other rations which the board may legally release.

Eugenics Committee Chief
Dr. Nakada - Pres. Dr's Assoc.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Summary 1948. j. Health Promotion Section, Medical Social Division

The number of patients referred to welfare agencies from health centers has incresed to about 50 per month. Although this is the heart of the Medical Social program it has been slow in getting under way while a great deal of emphasis has been placed on medical care in welfare institutions and a survey of handicapped children. All inmates of welfare institutions have received physical examinations including phychiatric evaluation. A number of congenital lues cases have been discovered in childrens homes. Three institutions showed extremely high intestinal parasite rates. A district by district survey of handicapped children has been made and the results will be used as a basis for corrective action on the part of both welfare and education authorities. The physical examinations of the handicapped children also included psyciatric examinations.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

6. Health Promotion.

a. Maternal and Child Care.

(1) During an analysis of still birth data, it was discovered that a large number of induced abortions are included in still birth rates. Reports of induced abortions are believed to be inaccurate but the number of cases reported is increasing every month. The number of reported induced abortions from February to July is 899 during the third month of pregnancy and 198 during the fourth month. Prefectural public health department physicians feel that the new eugenics law amendment places too much responsibility for the determining of whether or not an abortion should be done in the hands of lay people such as minseiiin. The prefectural Maternal and Child Section Chief feels that financial insecurity is not adequate justification for an abortion. He feels that birth control should be taught to financially dependent people but that abortions should not be performed. His main reason for believing that enforcement of the eugenics law should be left in the hands of physicians is that he feels the teaching of birth control methods should be an important part of the followi up program and that only the physician has the facilities and knowledge required to do this effectively.

Aug '49

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Medical Social

Miss Inowe, Chief of the Medical Social Division is doing a fine job. She recently completed the co rse for Medical Social workers at the Japan School of Social Work,

A complete survey of handicapped children in the prefecture has been done.

All children in prefectural and national children's homes have been examined.

Although these activities are still around the heart of a medical social program and not the heart of it, it is felt that real medical social programs are beginning to function. New workers are being trained for the health centers. A great deal of emphasis is also being placed on medical social services in the large hospitals.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Drug Production

There are only two important drug producers in Saitama. One is the Nihon Seibutsu Kagaku Kenkyosho (Japan Institute for Biological Research), a penicillin plant in Omiya which has received reparations equipment. The other is the Japan Medical Supply Co. in Honjo which produces everything from false teeth and vitamin C to hexylresorcinol and birth control medicine.

This section in the PH Department largely concerns itself with matters pertaining to retail and wholesale drug dealers.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Supply Di[illegible]ion

The most critical problem in supply concerns the formation of new Anti tuberculosis Associations and Disease Prevention Association whose main purpose is the distribution of serum. This has been reported to higher headquarters. I believe that these Associations violate the directive concerning the dissolution of sanitary associations. This directive specifically states that voluntary associations for the purpose of distributing medical supplies will not be formed.

The PHD officials are awaiting a ruling on these associations from higher headquarters.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Medical Affairs
Hospital Inspections - monthly reports.

Considering the fact that laymen are doing the hospital inspections, an excellent job is being done. These lay inspectors are trained to inspect only administrative functions and are warned that situations in any way concerned with medical practise are beyond their authority. They inspect for narcotic security, sanitation, safety hazards, and general administration. Their inspection includes questioning the patients to see that they are satisfied with the hospital service. They also check to see that sound rehabilitation policies are in operation in the hospital. For example, they check the number of referrals to welfare agencies and encourage the formation of occupational therapy units in those hospitals which have a large number of chronically ill patients who have been in the hospital for a long period of time.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Food Sanitation

Food shop grades are being posted in the windows of all food shops by the food inspectors. Copies of the stickers used are attached.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Food Sanita

Food s windowe of all
food shops f the stickers
used are a

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Food Sa

Food
food shop
used are

s windows of all
f the stickers

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

CORRECTION

THIS DOCUMENT

HAS BEEN REPHOTOGRAPHED

TO ASSURE LEGIBILITY

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Food Sanitation

Food shop grades are being posted in the windows of all food shops by the food inspectors. Copies of the stickers used are attached.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Food Sa[illegible]ta

Food s[illegible] windows of all
food shops [illegible] the stickers
used are at[illegible]

あなたの店の
衛生・施設
は

FAIR

可

50-74

埼玉縣
Saitama Pref.
保健所
Health Center

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Food Sa

Foo
food sho
used are

windows of all
the stickers

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

Food Sa

Foo
food sho
used are

windows of all
the stickers

あなたの店の
衛生・施設は

優良

埼玉縣　保健所
Saitama Pref. Health Center

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775 013

The present Organization Plan has worked very effectively during the last two years. This is evidenced by the fact that on only 1.9% of the budget the department accomplished a great decrease in disease rates and have been able to inspire the confidence of the citizens of the prefecture.

Please note that the Health Center Organizations are exactly the same as the prefectural one. The only difference is that there are fewer people to handle one program in the Health Centers. The goal toward which all are striving is to have one person per section in each Health Center responsible to the corresponding section Chief at the prefectural level. In this way a program may be developed at the prefectural level and passed to the district people for execution. In effect, the prefectural person would have 13 assistants in the field who were interested in and trained in his particular field. The plan is not working at its best because of insufficient personnel. Each Health Center person still has to be responsible to more than one prefectural official at the present time. However, the plan is there and progress is being made toward its attainment.

Saitama Public Health Department has always included the village public health departments in its planning. Each village in Saitama has a public health department and each is making fine progress. In another folder are the most recent inspection reports of the 372 local health departments. Each village has sanitation personnel. Each village keeps the immunization and prenatal examination records. Many of the villages show ~~over~~ 100% of their prenatal patients having had complete physicians examination.s