DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG No.

GHQ/SCAP Records (RG 331, National Archives and Records Service)

Description of contents

(1) Box no. 3106

(2) Folder title/number: (15)
Oita-ken

(3) Date: ?

(4) Subject:

Classification	Type of record
9750	1

(5) Item description and comment:

Oita

(6) Reproduction: (Yes) No

(7) Film no. Sheet no.

(Compiled by *National Diet Library*)

HEALTH CENTER CHECK SHEET

Cities
Towns 4
Villages 18

Owned by Govt
Population 104,000
Prefecture Mie
Health Center
Grade C
Location Owase, Mie-machi
Date opened 11 Sept 52
Size: BLDG 180 tsubo Land 1020 tsubo
Type of construction Wooden

Date	Visitor	Director	no. Doctors	Nurses PHN	Nurses MW	Nurses CN	Vet. FI	Vet. Vet.	Sanitary Staff ESI	Sanitary Staff ASI	Sanitary Staff ST	Other tech.	no. clerk	Total Staff	Sanitation Bldg.	Sanitation Land	Administration Gen	Administration Clinic	Administration PHN
11 Sept 52	M.F.B.	Dan Takeuchi	2	2	0	0	1	2	1	0	0	3	9	27					
18 Apr 53	GB	Sensho																	

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
	Construction Expenditure = 305,000 Facilities = 7 rooms
	New location
	Nurse in Village
18 Apr 53	Conference and Inspection Health Center well kept and clean - clinics seem to be operated efficiently - The Shikoku plan has been adopted since Nov. 1950 - Ordered to use Penicillin for Syphilis & a demonstration held about each patient over a period of time so that patient would not necessarily have to stay at one time. The BB organization, all new patients visited & contacts are reminded and advised. VD contacts are not traced due to diseases being confined in Beppu & Oita. The village nurses attend HC P.H. Nurse Conference. HC P.H. nurses stay in the Villages not covered by Village nurses - return to Health Center Wed & Saturdays to report. Visited nine of the Areas organized & Village nurses accompanies - to hold Clinics - Midwives show many of their patients attend the Clinics in the field - This opportunity is a good liaison between Midwives & H.C. nurses & doctors.

18 Apr. Conference + Inspection Continued -
Clinic Schedule
2 P. mon. Wed Fri Adults - A.M.
Treatments Prenatal - P.M.
VP. Mon Friday Am - morphaisen — Syphilis
Penicillin + Sulfa drugs for gonorrhea } Penicillin therapy for syphilis discovered -

AP. Tues + Thurs + Sat. }
Inf. " " " } A.M.
Child. " " "
Other " " "

Nurses Schedule -
2 PH. Nurses in Clinic
4 PH. Nurses do full time field work -
Case Files kept up to date - identifying tabs of various colors - for different type of case - And a monthly visit allocation is followed - An inactive file is also established. gp.

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NS



HEALTH CENTER CHECK SHEET

Cities ---
Towns 4
Villages 13

Akita Prefecture — Owned by Pref. — Population 58,133
Takeda Health Center — Grade C — Location Kawai-gun, Takeda-machi
Date opened 1943 — Size: BLDG 98. Tsubo — Land 304 Tsubo — Type of construction Wooden

Date	Visitor	Director	no. Doctors	Nurses: PHN	MW	CN	Vet.: FI	Vet.	Sanitary Staff: ESI	ASI	ST	Other tech.	no. Clerk	Total Staff	Sanitation: Bldg.	Land	Administration: Gen	Clinic	PHN
11 Sept	PHB	Dr. Takeuchi	2	X6	0	1	2 (W)	1	1	0	16	2	7	24	G	G	?		
18 Apr	93	Iwayoshi												26					

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
11 Sept 50	New building was constructed 30 Sept 1949
	Building is in exact - Immunizations Spr 90%
	Typh. 24% BCG Dip.
	One Sanitary Teams in town of six people
	PHNurses Average
	5 PH Nursing Clinics 2 in country (average 220
	Visits a month
	No Trained Lab Technician No Nutritionist
18 Apr 51	Refer to note on back

DECLASSIFIED E.O. 12065 SECTION 3-402/NARS

DECLASSIFIED E.O. 12065 SECTION 3-402/NND NO.

18 April Conference & Inspection -
Building in good condition - an apparent attempt is made to keep it clean & keep surgical cleanliness & Clinical
preformance. A new Portable X-Ray machine has been put into action through Mass Exam: in native village
"Others" - under mass examination Consist of General medical Care, eye care etc.
" Home Visits are cases handled by private Physicians as well as many T.B. Home visits
and a good T.B. following program kept in touch with a PH to all new Cases & complete
Physical Checkup on Contacts - Pyaws treatment is not done at P.C. but Private Doctors cooperate
with H.C. in this case.

Clinic Schedule -
T.B. - Mon - Wed - Fri A.M.
V.D. - Mon. & Thurs. P.M.
Ant. Tues & Sat morning — Wed P.M.
Inf. Tues & Sat
Childre " " morning —

Nurses Schedule -
1 Cl. Nurse in clinic
1 PH. Nurse in Field
4 PH Nurses in the field - covering area each one
Can file on monthly visit Basis. village nurses -
Inactive file in use. "Shikohuklan"

This schedule seems to work well - not using too much
nursing service & allowing more time out in field -

V.D. Contacts are difficult to trace due to infection being contracted in other places - Marphurs & Bismuth
used for Syphilis & Penicillin & Sulfadrugs for Granuloma & Suggestions were offered about introducing Penicillin
Therapy for Syphilis and arranging a plan for drawn out payment in stead of immediate exhorbitant cost.

cp.

HEALTH CENTER CHECK SHEET

Cities 1 | Towns 12 | Villages 2019

Aichi Prefecture | Owned by Pref | Population 112,000

Saeki Health Center | Grade C | Location Saeki city

Date opened Oct 1944 | Size: BLDG 132 tsubo | Land 200 tsubo | Type of construction Wooden

New H.C. opened 28 Jan 1951 — 189 — 550 — Concrete

Date	Visitor	Director	no. Doctors	Nurses: PHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ESI	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
12 Sept 50	R.T.B.	Dr. Fukue	4	6	0	1	2	1	1	0	3	4	4	25	F	P	?	?	?
19 Apr 51	GB.	Tsuchiya	3-1/2	4											good.	good	good	good	good

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
12 Sept 50	New H.C. Building (under construction) Building 198 tsubo Land 551 tsubo Expect to complete Dec this year R.T. Brown
19 Apr 51	Refer to back -

DECLASSIFIED E.O. 12065 SECTION 3.402/NND No. ____

DECLASSIFIED E.O. 12065 SECTION 3.4(b) NARA NO.

19 Apr Conference and Inspection - The new H.C. Building was opened 28 Jan. 1951. The staff of 24 is not adequate to carry out the planned program but gradually it is being increased. There are 3 doctors actually working and one has been on sick leave one year -

Mass Chest. are done twice a month and City owned vehicles are borrowed if unable necessary transportation. The "Rehabilitation Plan" has been started with a limited program - due to lack of Village nurses. Hfdn the Director discussed her plan to assist among the villages & stressed the necessity of a village H.D. talks with Village & town officials.

The Clinic Schedule was also discussed & suggestions were made in re arranging days & times to suit P.H. Nurses to better advantage.

Schedule -

2B } mon. Wed Fri & Sat. a.m. - Penicillin treatment also given during Clinics.
Gen Med. }

VD } 2 nurses & 2 hours - 8:30 a.m to 5 p.m.
Inf. }

The Smallpox innoculation program started 9 Apr 51 - Private Physicians and Health Centers employees will co-operate in an all out coverage of the H.C. area.

Nurses Schedule -

1 Cl. Nurse } in clinics
1 P.H. Nurse } full time
2 P.H. Nurses in field 3 full days.
2 " " " " 1/2 day - twice a week.

Nurses Case files - Identification system as well as monthly visit file used - an in active file also in use - Village Nurses - Industrial and School Nurses attend Conferences at the P.H. Center.

A good T.B. program is being carried out - through home visits and examining of all contacts.

VD Treatment - Mapharsen & Bismuth for Syphilis and Penicillin for gonorrhea - Suggestions were offered recommending the Penicillin therapy - and adapts have patients pay for it without an immediate financial cost.

63

HEALTH CENTER CHECK SHEET

Cities	1
Towns	3
Villages	21

O.I.T.A Prefecture — Owned by Prefecture — Population 200,000 +

O.I.T.A model Health Center — Grade A — Location: Oita City

Date opened — Size: BLDG tsubo Land tsubo — Type of construction

Date	Visitor	Director	no. Doctors	Nurses			Vet.		Sanitary Staff			Other tech.	no. clerk	Total Staff	Sanitation		Administration		
				PHN	MW	En.	F.I	Vet.	ESI	ASI	ST				Bldg.	Land	Gen	Clinic	PHN
8 Nov.	[redacted]	Dr Kawano	5	12	1	1	1	2	2			9	25	61	Good	Good	Good	Good	Good

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
8 Nov.	Dr. Kimura, Chief of Medical Affairs Sect. Kocha accompanied KCAV Deputy Director to H.C. Dr. Kawano, Chief of Preventive Medicine at H.C. who has obtained the "Shikoku Plan" at Katahira Kagawa Ken - discussed the plan and after a visit to Katahira by one of his nurses and the P.H. nurse from Kochi Nursing Division is thinking of adopting the plan in the Oita H.C. The P.H. nurses program out in the field has been hampered by the lack of cooperation of Private Physicians in the Villages. Good idea of approach was discussed.

DECLASSIFIED E.O. 12065 SECTION 3.5(C) NARS

HEALTH CENTER CHECK SHEET

Cities	0
Towns	2
Villages	3

OITA Prefecture — Owned by PREFECTURE — Population 50,000

SAKANOUICHI Health Center — Grade — Location SAKANOUICHI

Date opened 1946 — Size: BLDG 173 tsubo Land 783 tsubo — Type of construction WOODEN

Date	Visitor	Director	no. Doctors	Nurses: PHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ESI	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
9 AUG 10	EVO	DR HIROSE	1	3	0	1	1 (Pharm)	1	1	1	2	1 Xray	5	17	POOR	FAIR	POOR	POOR	FAIR

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
GAGE 1956	Old building in good condition - Staff small No lab. technician - M.D. PHN Vet + Pharm to the lab. work. A part time MD comes to do 2 of the 3 scheduled TB clinics - Attendance in chest clinics small, person going - ~~most~~ many go to the next nikkoo TB clinic nearby 3TH (approx) 160 TB cases reported in past 7 mos. No. TB nursing work this considering size of staff Maternity + Child clinics to all towns + villages 1x mo - Lowest statistics also attendance is mostly children. Have started pencilling for syphilis - (one case so far). Below 1% is not as practiced by Ishatsu HS - Edward to follow. Apparently very little if any VD contact tracing since after 1st 10 only encouraged to ~~entered~~ enter statistics since Jan 102 for small pox. Adv. Cleaning of place. Urged this as priority program. EVO

HEALTH CENTER CHECK SHEET

Cities	1
Towns	1
Villages	9

OITA Prefecture — Owned by PREFECTURE — Population 82,565

USUKI Health Center — Grade C — Location USUKI CITY

Date opened Oct 1944 — Size: BLDG 82 tsubo Land 300 tsubo — Type of construction WOODEN.

Date	Visitor	Director	no. Doctors	Nurses: PHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ESI	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
7 AUG 1948	EVD	DR GOTO	3	5	0	1		1	1	1	4	1 Xray 1 Lab	6	22	FAIR	FAIR	FAIR	FAIR	FAIR

★ Code - W. Ministry Grade A or C A = staff over 31, C = Under 31 Sani. and Adm criter - Good, Fair or Poor

Date	Remarks
7 AUG 1948	Inspection visit. Building to have some remodeling for expansion, to start soon. Difficult to evaluate activities statistics - aids to get different understanding on calculations of some. Injuries show considerable "other treatments" given, these must be for med + surg. Aids to give more stress to TB, VD, Mat + Child Health programs - Very poor Maty program, report "people uneducated" aids to attitude. Knocks med info by education of med mores in area. Only 12 Maty exams here last month - report Usuki City conducts an AP exam clinic (last month HC did 40 AP blood tests from that clinic. PHNs take AP blood tests on home visits) TB + VD PHN follow-up program a poor, discussed in detail. Good PHN program, urging TB as priority program. Outside PHN do the follow up in their areas - gathered conferences at HC 1x mo. Chief nurse attend 2 mos refresher (PHN) course in Oita in June + July 50. 26 syphilis cases treated with procaine pcn. - most their cases are late syphilis - discussed Schatton 24. Complete 24 5% small pox immunity in whole district; Typhoid program in progress but only 2 villages have completed - reported as for (for 5,212 persons) No teaching clinics are held except on request of a village - discussed + suggested utilization of "Shakedown Plan" for teaching clinics. Final conditions of HC as fair. Discussed cleaning etc.

HEALTH CENTER CHECK SHEET

Cities 1
Towns 1
Villages 17

OITA Prefecture — Owned by PREFECTURE — Population 103,850
NAKATSU Health Center — Grade C — Location
Date opened 1938 — Size: BLDG 140 tsubo — Land 500 tsubo — Type of construction WOODEN

Date	Visitor	Director	no. Doctors	Nurses: PHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ESI	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
8 AUG '56	EGO	DR HOASHI	3	8	0	1	2	1	1	0	4	1 Lab 1 Pharm.	8	29	FAIR	FAIR	FAIR	FAIR	GOOD

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
8 Aug 1956	Health Center in / good condition. Clinic schedule adhered to (except for previous clinic) even tho schedule is made out because there is only one room & the treatment room (exception VD take-way off) Advised to set-up schedule & try to follow. Lay out of rooms not adequate for well conducted clinics, private hearing taking room, further distant from "main desk" clinic rooms, & is partially separated as often is necessary. Advised changes in room arrangements & discussed med for privacy on TB & VD hearing taking. Statistics on "VD Mass Exams" as kept by private Med Women. Grade TB follow-up program fair good. Discussed Simple PHN. TB follow-up program - keeping it as previous program - 446 cases TB newly cases since Jan. 1956. Total small pox vaccinations since Apr 49 to date - 107,372 (56 "27), Typhoid program - 42,195 vacc completed. Since Apr 1956 BCG totals 6,756. Have started penicillin for syphilis - adv. to follow Schultz Test # 2.5 for proper follow-up.

HEALTH CENTER CHECK SHEET

Cities 0
Towns 5
Villages 22

OITA Prefecture
YOKKAICHI Health Center
Owned by PREFECTURE Population 63,000
Grade Location YOKKAICHI MACHI, USA GUN
Date opened 1944 Size: BLDG 90 tsubo Land 300 tsubo Type of construction WOODEN

Date	Visitor	Director	no. Doctors	Nurses PHN	Nurses MW	Nurses CN	Vet. FI	Vet. Vet.	Sanitary Staff ESI	Sanitary Staff ASI	Sanitary Staff ST	Other tech.	no. Clerk	Total Staff	Sanitation Bldg.	Sanitation Land	Administration Gen	Administration Clinic	Administration PHN
8 AUG 56	EVD	DR Tabamura	3	5	0	0	1	1	1	1	2			27	POOR	FAIR	POOR	POOR	POOR

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
8 AUG 1956	Old health center building in rental good condition. Expect new bldg to be started "this fiscal year but not until March 57" since fuel appropriation was not provided - bond issue to start. Statistics on clinics are low - expect "Other Minor Treatments" are very high - these are mostly Med. + Surgical cases. - Advised re functions of H.C. clinics - apparently beginning to realize they are not used in very recent change in statistics. Suggested conducting clinics on schedule - urged stressing TB as priority program - 160 new TB cases left in past 7 mos - has casual field TB follow-up program (contacts with an open case gets pred. am 1X year). PHN staff limited for good TB follow-up - nurses are unable to reach all villages in district - apparently 5 are not covered by PHN service. TB follow-up has poor - records made by PHN or trace - "contacts are brought in by source case". Small pox immunizing completed 60,163 (of 61,865 to be given) - Typhoid program not in progress - all school children immunized in July.

DECLASSIFIED E.O. 12065 SECTION 3.402/NARS

HEALTH CENTER CHECK SHEET

Cities 0
Towns 5
Villages 22

OITA Prefecture
YOKKAICHI Health Center
Owned by PREFECTURE Population 63,000
Grade Location YOKKAICHI MACHI, USA GUN
Date opened 1944 Size: BLDG 90 tsubo Land 300 tsubo Type of construction WOODEN

Date	Visitor	Director	no. Doctors	Nurses: PHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ESI	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. Clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
8 AUG 56	EHO	Dr Takamizawa	3	5	0	0	1	1	1	1	3			27	POOR	FAIR	POOR	POOR	POOR

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
8 AUG 1956	Old health center building in routine poor condition. Expect new bldg to be started "this fiscal year but not until March 56" since full appropriation was not possible - does YES ossible to start. Statistics on clinics are low - suspect "other visits + treatments" are very high - these are mostly Med. + Surgical cases. - Advised re functions of H.C. clinics - apparently beginning to realize they do not fit in very recent change in statistics. Suggested conducting clinics on schedule - urged starting TB as private program - 160 new TB cases reported in past 7 mos - has caused fine TB follow-up program (contacts with an open case gets x-ray am 1X year). PHN staff limited for good TB follow-up - nurses are unable to reach all villages in district - apparently (are not covered by PHN service) TB follow-up very poor - visits made by PHN or nurse - "contacts are brought in by doctor case". Smallpox immunizing completed 60,163 (of 81,805 to be given) - Typhoid program not in progress - all school children are completed in July.

DECLASSIFIED E.O. 12065 SECTION 3 NLZ/RAC

HEALTH CENTER CHECK SHEET

Oita Prefecture — Owned by Pref. — Population 82,225

Usuki Health Center — Grade C — Location Usuki City

Date opened Oct 1946 — Size: BLDG 85 tsubo — Land 300 tsubo — Type of construction Wooden

Cities 32/000 — Towns 1 — Villages 9

Date	Visitor	Director	no. Doctors	Nurses: PHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ESI	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
12 Sept 50	CTB	Dr. Goto	3	6/1	0	0	2	1	1	0	3½	2	4	22	6	6	7	7	7

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
12 Sept 50	25 tsubo building will be extended within this year. ¥ 105,000 - Kang 195,000 local
	no nutritionist, statistician
	2 Home Class for Extension

DECLASSIFIED E.O. 12065 SECTION 3

DECLASSIFIED E.O. 12065 SECTION 3 NARA

72
84
156

HEALTH CENTER CHECK SHEET

Cities ---
Towns 6
Villages 12

Oita Prefecture
Kunisaki Health Center
Owned by Pref. Population 77,000
Grade ___ Location Higashi Kunisaki-gun Kunisaki-machi
Date opened Aut 1944 Size: BLDG 72 tsubo Land 588 tsubo Type of construction Wooden

Date	Visitor	Director	no. Doctors	Nurses PHN	Nurses MW	Nurses CN	Vet. FI	Vet. Vet.	Sanitary Staff ESI	Sanitary Staff ASI	Sanitary Staff ST	Other tech.	no. clerk	Total Staff	Sanitation Bldg.	Sanitation Land	Administration Gen	Administration Clinic	Administration PHN
9 Sept	PTE	Dr. S. Hyoiwa Hirai	2	4	0	1	2nd	1	1	0	0	2 Jun	6	19	P	F	P	P	P

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
	Building is poor - Rare glass for extensions. Need more PHN. TRANSPORTATION Problem.

S

HEALTH CENTER CHECK SHEET

Cities ----
Towns 2
Villages 3

Aita Prefecture — Owned by Pref. — Population 50,072
Sakanoichi Health Center — Grade C — Location Kita Tamahegun, Sakanoichi Machi
Date opened Oct 1944 — Size: BLDG 173 Tsubo Land 780 tsubo — Type of construction Wooden

Date	Visitor	Director	no. Doctors	Nurses: DHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ESI	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
12 Sept 45	R.H.B.	Dr. Takano Goto	1	3.	0	1	2	1	1	0	2	1	0	17	G	G	P	U	P.

★ Code - W. Ministry Grade A or C A = staff over 31, C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
	Dr Goto, director, in charge of Sakanoichi + Uzuki H.C.
12 Sept 45	Uzuki H.C
	Plan to amalgamate with Uzuki.
	Clinics held M.W.F.
	Does seven families live in Health center which
	was formerly a private hospital.
	Mild waste space. — R.H.Brown
	Advised to resurvey.

DECLASSIFIED E.O. 12065 SECTION 3

HEALTH CENTER CHECK SHEET

Oita Prefecture — Owned by Prefecture — Population 48,000 — Cities 0

Hiji Health Center — Grade C — Location Hayami-gun Hiji-machi — Towns 5

Date opened Oct 1944 — Size: BLDG 89 tsubo Land 460 tsubo — Type of construction Wood

Villages 9

Date	Visitor	Director	no. Doctors	Nurses: PHN	Nurses: MW	Nurses: CN	Vet.: FI	Vet.: Vet.	Sanitary Staff: ES:	Sanitary Staff: ASI	Sanitary Staff: ST	Other tech.	no. clerk	Total Staff	Sanitation: Bldg.	Sanitation: Land	Administration: Gen	Administration: Clinic	Administration: PHN
9 Sept	PHK	Dr Murano Ueyangi	2	6	0	0	2	1	1	0	2	1	5	19					

★ Code - W. Ministry Grade A or C A = staff over 31 C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
9 Sept	New Plan — Bldg 180 Land 340 T. Advised to purchase at least 800 Tsubo of land. Need new Lab Technician. Assist in Ent Sanit + School under / Transportation poor. Immunizations.

DECLASSIFIED E.O. 12065 SECTION 3.402/NND

HEALTH CENTER CHECK SHEET

Oita Prefecture
Beppu + Health Center
Date opened ?1925

Owned by Pref. Population 95,150
Grade Other Location Beppu City
Size: BLDG tsubo Land tsubo Type of construction Wooden

Cities	1
Towns	8
Villages	0

Date	Visitor	Director	no. Doctors	Nurses PHN	Nurses MW	Nurses CN	Vet. FI	Vet. Vet.	Sanitary Staff ESI	Sanitary Staff ASI	Sanitary Staff ST	Other tech.	no. clerk	Total Staff	Sanitation Bldg.	Sanitation Land	Administration Gen	Administration Clinic	Administration PHN
22 Dec 53	Dr.	Dr Takahashi	5	7	0	1	2	1	1			Xray Lab Pharm.		38	Poor	Poor	?	Poor	Poor

★ Code - W. Ministry Grade A or C A = staff over 31, C = Under 31 Sani. and Adm enter - Good, Fair or Poor

Date	Remarks
22 Dec 1953	Subject new H.C bldg to be completed in April 1951 - to be a Class A- H.C - Former director resigned + Dr Takahashi is replacing him, coming from Oita Health Center 3 mos ago. Health Center in poor condition - over crowded. In reviewing statistics it is noted that 200 to 900 H.C. consultations per month fell in the "other" category (also there had to a decrease in this since new director) - Pointed out function of H.C. clinics not as med or surg. treatment centers - Statistics of PHN home visits to TB good, good. Pointed out poor utilization of PHN in clinics (esp in VD clinic). Discussed + advised to set up nurse home visit file by age. Inquiry of BCG program reveals that program was completed 15 Dec for all school children but as for other groups to 30 yrs of age - only those coming for mass exams get TB test + BCG. - Director estimates they receive med about 50% of their needs for BCG which is distributed directly from Kenchi - Points out difficulty of receiving BCG in 100 dose ampules instead of smaller size dose. Advised re nursing program + to especially begin plans that are necessary in setting up for the program in their new health center. Key report says # of PHN staff will not be increased when new bldg opens

DECLASSIFIED E.O. 12065 SECTION 3 NND

HEALTH CENTER CHECK SHEET

Prefecture Oita

Date	Health Center	Grade A	Grade B	Location	Director	Chief of Gen. Affairs	no. Nurses	no. Doctors	Total Staff	Population	Remarks
	Oita									202,609	
	Beppu									96,685	
	Hiji									67,994	
	Kunizaki									75,220	
	Takada									34,317	
	Yokkaichi									100,316	
	Nakatsu									102,490	
	Hita									92,416	
	Mori									46,950	
	Sakanoichi									48,954	
	Usuki									81,795	
	Saeki									110,387	
	Mie									96,025	
	Taketa									57,493	
									Total	1,233,601	

DECLASSIFIED E.O. 12065 SECTION 3 (E)(1)