

ITEM	DESCRIPTION	UNIT	QUANTITY	TOTAL ESTIMATED WEIGHT	NUMBER OF CARLOADS	REMARKS
<u>OIL STORE ROOM</u>						
Single story wooden construction with artificial corrugated slate roofs and outside walls, mortar-finished inside walls and concrete floor occupying 1,500 sq.ft.						
If building be dismembered, the following materials (item 1-28) may be available.						
Lumber (Items 1-11) plane-finished on visible surfaces (about one-third) as constructed. Otherwise rough.						
1	Under-roof plates 5/8" thick (various sizes) to cover 1,210 sq.ft.	B.S.	721			incl. 50% poor
2	Straps 5/8" x 3 1/2" x 2.5'	"	6			" " "
	" x " x 5.5'	"	118			" " "
3	Columns 1 3/8" x 4" x 0.5'	"	6			" 30% "
	" x " x 2.5'	"	10			" " "
	" x " x 3'	"	38			" " "
	" x " x 7'	"	204			" " "
4	Straps 1 1/2" x 1 1/2" x 2.5'	"	13			" 50% "
	" x " x 5.5'	"	32			" " "
	" x " x 7'	"	44			" " "
5	Straps, Stays 2" x 4" x 3'	"	8			" 18% "
	" x " x 5.5'	"	35			" 26% "
	" x " x 6'	"	34			" 18% "
	" x " x 8'	"	91			" " "
6	Supports 2 1/2" x 4" x 3'	"	35			" 10% "
	" x " x 5.5'	"	61			" 32% "
	" x " x 6'	"	35			" 10% "
7	Stays 2 1/2" x 4" x 3.5'	"	47			" 45% "
	" x " x 12'	"	70			" " "
8	Railings 2 1/2" x 6" x 5.5'	"	59			" 26% "

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

	" x " x 5.5'	"	51			32%
	" x " x 6'	"	35			10%
7	Stays 2 1/2" x 4" x 3.5'	"	47			45%
	" x " x 12'	"	70			"
8	Nailin g 2 1/2" x 6" x 5.5'	"	59			26%
9	Column s & Beams 4" x 4" x 2'	"	24			10%
	" x " x 2.5'	"	7			"
	" x " x 3'	"	78			"
	" x " x 5'	"	205			"
	" x " x 5.5'	"	32			"
	" x " x 6'	"	35			"
	" x " x 7'	"	366			30%
	" x " x 12'	"	1,205			45%
10	Ditto 4" x 6" x 3'	"	50			10%
	" x " x 5.5'	"	34			"
	" x " x 8'	"	264			"
	" x " x 12'	"	343			"
	" x " x 18'	"	298			"
11	Main beams 5" x 5" x 12'	"	158			
Total quantity for lumber (Items 1-11)		"	4,761			
of which "n ot sui t able for reuse"		"	1,421			
Estimat ed Net Available Quantity		B.F.	3,340	8,745 lbs	0.5	incl. 45% poor
<u>Artificial Corrugated Slates</u> 3/8" thick 2.2" x 6'						Estimated quantity suitable for reuse abt. 70% at best
12	For 1,210 sq. ft. of roof	sheets	108			
13	For 1,317 sq.ft. outside walls	"	111			
Total quantity		"	213			
Estimated Av ail able quantity, 70%		"	149	1,788 lbs	0.1	
<u>Glasses</u> (fitted in windows):						
(survey on 8th Jan.)						
14	Glasses for 9sets of double sliding windows con tain ing 8 sheets 12"x15"	sq.ft.	90			Estimated quantity available for reuse by taking off from windows,abt. 80%
Estimated available quant ity 57 sheets		"	71.25	125 lbs	--	
				incl. packing		

Glasses (fitted in windows)

(Survey on 8th Jan.)

Estimated quantity available for reuse by taking off from windows, abt. 80%

14. Glasses for 9 sets of double sliding windows containing 8 sheets 12"x16"
Estimated available quantity 57 sheets

sq. ft. 90
" 71.25

125 lbs
incl. packing

--

Main Pipes of Sheet Iron

If taken off from building, practically whole quantity as follows may be rendered unsuitable for reuse

15 Vertical Pipes, 3" ϕ , 10 pcs. of 10' length.
Total length:-

ft 100

--

--

16 Horizontal Pipes, 4" ϕ 2 lines of 84 ft. extended length
Total Length:-

" 168

--

--

Iron Pipes for construction

17 Bolts with hexagonal nuts and square washers, 5/8" ϕ 6"-12" long
Available quantity, about 70%

pcs 120
" 84

105 lbs

18 Bolts 1/2" ϕ 12" long
Available quantity, about 70%

" 16
" 11

22 "

Total Quantity for Bolts

" 95

127 "

19 1/2" ϕ Clamps, 5" size
Available quantity, 20% at best

" 35
" 7

Total Available Quantity for Iron Pieces for Construction (Items 17-19)

pcs 102

129 lbs

20 Roping is not existing.

Electric Light Equipment

21 4-layer insulated wire 1.6mm
" " 5.5 "

ft 85
" 19

22 Double Pole Switch 30A

pcs 1

23 Conduit tubes 5/8"
" 3/4"

ft 42
" 19

24 Conduit tubes 5/8"

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

Total Available Quantity for Iron
 Pieces for Construction (Items 17-19)

pcs 102

129 lbs

20 Piping is not existing.

Electric Light Equipment

21	4-layer Insulated wire	1.6mm	ft	85
	"	5.5 "	"	19
22	Double Pole Switch 30A		pcs	1
23	Conduit tubes	5/8"	ft	42
		3/4"	"	19
24	Couplings	5/8"	pcs	5
		3/4"	"	2
25	Saddles (Clamps for conduit tubes)	5/8"	"	12
		3/4"	"	3
26	One piece each of joint boxes with 1, 2 and 3 leads	Total	pcs	3
27	Receptacles with globes		"	4
28	Service Cap	1"	"	1

INSTALLED MATERIALS AND SUPPLIES

ITEM	DESCRIPTION	UNIT	QUANTITY	TOTAL ESTIMATED WEIGHT	NUMBER OF CARLOADS	REMARKS
<u>SMALL STORE ROOM</u>						
Single story wooden construction cement tile roof, walls of plaster and concrete floor, occupying 712 sq. ft.						
If building be dismembered, the following materials (Items 1-9) may be available.						
<u>LUMBER</u>						
Items 1-6, plane-finished on visible surfaces (about one-third) as constructed. Otherwise rough.						
1	Under-roof plates, 3/8" thick various sizes.	B.F.	127			incl. 60% poor
2	Floor planks, 1/2" thick, various sizes.	"	125			" " "
3	Columns and planks, smallest dimension falling below 2 1/2" various sizes totalling:	"	257			Item 3 & following incl. 27% (average) "poor"
4	Beams 2 1/2" x 2 1/2" x 9'	"	90			
5	Columns & Ties 3 1/2" x 3 1/2" x 6'-12'	"	756			
6	Beams 4" x 7" x 12'	"	327			
Total Quantity for Items 1-6		"	1,682			
of which "unsuitable for reuse"		"	526			
Estimated Available Quantity for Lumber		B.F.	1,156	3,028 lbs	0.2	
7	Cement Tiles (Japanese style "kawara") to cover 820 sq. ft. of roof, of which about 67% is					

6	Beams	4" x 7" x 12'	"	327		
	Total Quantity for Items 1-6		"	1,682		
	of which "unsuitable for reuse"		"	526		
	Estimated Available Quantity for Lumber		B.F.	1,156	3,028 lbs	0.2

7	Cement Tiles (Japanese style "kawara") to cover 820 sq.ft. of roof, of which about 67% is estimated as "suitable for reuse" as follows.		pcs	980	6,700 lbs	0.4
---	---	--	-----	-----	-----------	-----

GLASSES fitted in doors
(Survey on 8th Jan.)

8	Glasses for doors each containing 12 sheets 15" x 10 1/2"		sq. ft.	27		
---	--	--	---------	----	--	--

9	<u>Ditto. 12 sheets, 15" x 12 1/2"</u>		"	94		
	Total for Items 8 & 9		"	121		

	Estimated Available Quantity for Glasses 55% of above		"	67	110 lbs incl. packing	--
--	--	--	---	----	--------------------------	----

10 Piping and Electric Light are not equipped.

ITEM	DESCRIPTION	UNIT	QUANTITY	TOTAL ESTIMATED WEIGHT	NUMBER OF CARLOADS	REMARKS
CARBIDE STORE ROOM						
Single story wooden construction with artificial slate roof, walls of mortar finish in g on wooden fibre and concrete floor						
If building dismantled, the following materials (Items 1-) may be available						
Lumber (Items 1-12) plane-finished on visible surfaces (about one-third) as constructed. Otherwise rough.						
1.	Under-roof plates, 1/2" thick, various sizes	B.F.	451			incl. 47% poor
2.	Straps 1 1/2" x 2 1/2" x 6'	"	28			" 37% "
	" x " x 12'	"	28			" " "
3.	Ditto " x 3 1/2" x 7'	"	28			" 44% "
	" x " x 8'	"	12			" 21% "
4.	Boards " x 6" x 12'	"	71			
5.	Columns & Stays 1.3/8" x 4" x 2.5'	"	14			" 28% "
	" x " x 4.5'	"	48			" " "
	" x " x 7.5'	"	117			" " "
6.	Straps, 1.5/8" x 3 1/2" x 1.8'	B.F.	12			incl. 21% poor.
	" x " x 8'	"	17			" " "
7.	Columns, 1.3/4" x 1.3/4" x 6'	"	13			" 44% "
	" x " x 8.5'	"	193			" 21% "
8.	Straps, " x 5" x 12'	"	34			" " "
9.	Ditto, " x 6" x 12'	"	85			" " "
10.	Columns & Beams, 2" x 4" x 5.5'	"	63			" " "

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013

6.	Straps,	1.5/8" x 3 1/2" x 1.8'	B.F.	12			
	"	" x " x 8'	"	17			incl. 21% poor.
7.	Columns,	1.3/4" x 1.3/4" x 6'	"	13			" " "
		" x 8.5'	"	193			" 44% "
8.	Straps,	" x 5" x 12'	"	34			" 21% "
9.	Ditto,	" x 6" x 12'	"	85			" " "
10.	Columns & Beams,	2" x 4" x 5.5'	"	63			" " "
	"	" x 9'	"	64			" 28% "
11.	Ditto,	3" x 3" x 8'	"	24			" 44% "
12.	Ditto,	4" x 4" x 1.3'	"	206			" " "
	"	" x 2.5'	"	40			" 38% "
	"	" x 3'	"	18			" " "
	"	" x 4.5'	"	130			" " "
	"	" x 5.5'	"	32			" " "
	"	" x 7.5'	"	282			" " "
	"	" x 12'	"	1160			" 23% "

Total quantity for Lumber (Items 1 - 12) B.F. 3167
 of which "not suitable for reuse" " 803
 Estimated Net Available quantity B.F. 2364 6,192 lbs. 0.3

Artificial slate, 900 sq. ft. for roof
 will not be suitable for reuse, if
 construction dismembered.

	Glasses fitted indoors. (Survey on 8th Jan. About 60% suitable for reuse).				
13	Glasses for doors containing 10 sheets, 12" x 12"	sq.ft.	80		
14	Ditto				

ITEM

DESCRIPTION

QUANTITY

WEIGHT
OF ITEM

	Glasses fitted indoors. (Survey on 8th Jan. About 60% suitable for reuse).				
13	Glasses for doors containing 10 sheets, 12" x 12"	sq.ft.	80		
14	Ditto, 4 sheets 12" x 12"	"	4		
	Total quantity of glasses	"	84		
	Estimated available quantity 60%	"	50	100 lbs. incl.packing.	--
	Rain pipes of AWG No.27(approx.) Sheet Iron				
		Total			
15.	Vertical pipes, 3" ϕ , 12 pcs. of 9'	ft.	108	--	--
16.	Off-sets, 1.5' long	pcs.	12	--	--
17.	Horizontal pipes, 3 $\frac{1}{2}$ " ϕ Extended length:-	ft.	120	--	--
20.	Architectural belts 5/8" ϕ 12" long, with hexagonal nuts and square washers	pcs.	32	53 lbs.	--

Practically whole quantity "unsuitable for reuse" if dismembered from building.

INSTALLED MATERIALS AND SUPPLIES

ITEM	DESCRIPTION	UNIT	QUANTITY	TOTAL ESTIMATED WEIGHT	NUMBER OF CARLOADS	REMARKS
<u>URINAL & WASH ROOM</u>						
Single story wooden construction with artificial corrugated slate roof, outside overlapping wooden walls, inside wooden wall panelling and concrete floor, occupying 926 sq.ft.						
Urinals and lavatory of primitive Japanese style without porcelain articles; wash room of simplest execution.						
If building be dismembered, the following materials (Items 1-10) may be available.						
<u>LUMBER</u>						
Items 1-7 plane-finished on visible surfaces (about one-third) as constructed. Otherwise rough.						
1	Under-roof plates, overlapping wall boards, inside wall paneling, wash stands all of 5/8" thickness, various sizes.	B.P.	1,370			incl. 45% poor
2	Floor planks, 7/8" thick, various sizes "		119			" " "
3	Columns & Planks, smallest dimension falling below 4" various sizes totalling:"		804			Item 3 and following incl. average 30% "poor"
4	Columns 4" x 4" x 2'-12'	"	928			
5	Beams 4" x 6" x 10'-12'	"	29			
6	" 4" x 7" x 12'	"	90			
7	" 5" x 8 1/2" x 18'	"	476			

4	Columns	4" x 4" x 2'-12'	"	928		
5	Beams	4" x 6" x 10'-12'	"	29		
6	"	4" x 7" x 12'	"	90		
7	"	5" x 3 1/2" x 18'	"	476		
	Total quantity for Items 1-7 of which "unsuitable for reuse"		"	3,516		
			"	1,356		
	Estimated Available Quantity for Lumber		B.F.	2,460	6,440 lbs	0.3
8	Artificial corrugated Slates, 3/8" x 2.2' x 6' to cover 1175 sq.ft. of roof, of which abt. 70% at best is estimated as "suitable" for reuse as follows.		sheets	69	830 lbs	--
9	Doors of Japanese style are not suit- able for reuse, devoid of glass sheets.					
10	5/8" Bolts, 12" long, with nuts and washers are being used for construc- tion. Only a portion of this could be taken into consideration for re- use.		pcs	46	70 lbs	--
11	About 180 sq.ft. of galvanized sheet iron is being used at urinal and wash room, but regarded as unsuitable for reuse.					
12	The accomodation of this building at time of survey on 8th Jan., appear- ed forsaken; hence piping and glass paneling and light equipment have not been completed.					

ITEM	DESCRIPTION	UNIT	QUANTITY	TOTAL ESTIMATED WEIGHT	NUMBER OF CARLOADS	REMARKS
<u>RAILS</u> (Survey on 8th Jan.)						
1	Between Machine Shop and Finishing Shop (for 208 ft. track-line) 75-pound Rails, each of 32.8 ft. and odd length Total length:-	ft	416			
2	Between Derrick Crane and Machine Shop (for 558 ft. track-line within range of survey of Hasegawa Team) Rails likewise as Item 1 Total length:-	ft	1,116			
3	Between Derrick Crane and Finishing Shop (for 66 ft. track-line. Some of originally laid rails were missing on the date of survey in-between the range of Hasegawa Team) Rails likewise as Item 1 Total length:-	ft	132			
	Total extended length of 75-pound Rails as per Items 1-3	ft	1,664	41,600 lbs		
	Accessories: (for Items 1-3)					
	Fish Plates	pcs	96	2,800 "		
	About 70% of bolts and nuts suitable for reuse	sets	67	210 "		
	About 60% of spikes suitable for reuse	pcs	660	600 "		
	Whole of about 280 wooden ties are regarded as unsuitable for reuse					
	Total estimated weight for Rails and accessories as per Items 1-3			45,210 lbs	1	Special Wagon, such as "O-chi-ki" Type is required.
4	Shunting (for 65.6 ft. within range of Hasegawa Team and towards Aboshi					

Station)

each of 32.8 ft. and

<p>Total estimated weight for Rails and accessories as per Items 1-3</p> <p>4 Shunting (for 65.6 ft. within range of Hasegawa Team and towards Aboshi</p>			45,210 lbs	1	Special Wagon, such as "O-chi-ki" Type is required.
---	--	--	------------	---	---

<p>Station) 100-p und rails, each of 32.8 ft. and odd length</p> <p>Total length:-</p>	ft	1,312	43,800 lbs		
<p>Accessories:</p> <p>Fish Plates</p> <p>About 70% of bolts and nuts suitable for reuse</p> <p>About 60% of spikes suitable for reuse</p>	pcs	76	3,800 *		
	sets	53	270 *		
	pcs	530	600 *		
<p>Whole of about 220 wooden ties are regarded as unsuitable for reuse.</p>					
<p>Total estimated weight for Rails and accessories as per Item 4</p>			48,470 lbs	1	Special Wagon, such as "O-chi-ki" Type is required.
<p>Grand Total for Item 1-4</p>			93,680 lbs	2	

DECLASSIFIED E.O. 12065 SECTION 3-402/NNDG NO. 775013